

VALOUR COMMUNITY CENTRE
GYMNASIUM ADDITION
AND RENOVATIONS

Section 26 50 00
Luminaire Schedule

PROJECT NO: 286-2007

LUMINAIRE SCHEDULE

TYPE	MANUFACTURER	CATALOGUE NO.	VOLTS	LAMPS	REMARKS
1	CFI LITHONIA METALUX PEERLESS	AA348-AA 2GTF332A12125 GEB 2GR8-332A125-EB82-DF-24-W LACH-24F-332-12.125-120-EL	120	3-F32T8	2 x 4 RECESSED IN DRYWALL CEILING C/W FRAMED .125" K12 LENS AND EL1ECTRONIC BALLAST. MIDDLE LAMP BALLASTED SEPARATELY FROM OUTER LAMP.
2	LITHONIA	FGB24654T5HO N1X20A12	120	6-F54T5HO	2 x 4 HI-BAY LUMINAIRE MIRO 4 NORMAL BEAM REFLECTOR W/VENTED SLOTS &A12 LENS
3	LITHONIA CFI METALUX PEERLESS	2LB232-GEB TX248 WA-232A-EB81 KOPA-15-232-120-EL	120	2-F32T8	SUFACE MOUNTED LOW PROFILE WRAPAROUND C/W ACRYLIC LENS AND ELECTRONIC BALLAST. WHITE BODY.
3A	CFI LITHONIA METALUX PEERLESS	CSB248 WC232-GEB BC-232-EB81 CNW-4-232-120-EL	120	2-F32T8	DOUBLE LAMP WALL MOUNTED CUBELITE. WHITE BODY. HEIGHT AS INDICATED C/W ELECTRONIC BALLAST.
4	LITHONIA	CP8A AR	120	1-150 A21	PENDANT SUSPENDED CYLINDER LUMINAIRE C/W BALL ALIGNER SUSPENDED TO U/S OF STRUCTURE
5	CFI LITHONIA METALUX PEERLESS	SXT2SVA3402X4 2BX332A12125 GEB I/OSW 2M-332A125-EB82 LX-24-332-12.125-AS-120-EL	120	3-F32T8	2 x 4 SURFACE MOUNTED C/W FRAMED .125" K12 LENS AND ELECTRONIC BALLAST. MIDDLE LAMP BALLASTED SEPARATELY FROM OUTER LAMP.
6	CFI LITHONIA METALUX PEERLESS	SB148 S132-120V GEB SN-132-EB81 LS-4-132-120-EL	120	1-F32T8	SINGLE LAMP STRIPLIGHT MOUNTED IN VALANCE OR SURFACE MOUNTED C/W ELECTRONIC BALLAST. SEE ARCHITECTURAL DETAILS.
7	CFI LITHONIA METALUX PEERLESS	SB148T TS132-120V GEB 8TSN-132-EB81 LS-8-232-120-EL	120	2-F32T8	SINGLE LAMP STRIPLIGHT MOUNTED IN VALANCE OR SURFACE MOUNTED C/W ELECTRONIC BALLAST. SEE ARCHITECTURAL DETAILS.
8	P & S	274-WH		120	1-100W A-19 SURFACE MOUNTED (C/W WITH WIREGUARDS IN CRAWLSPACE OR WHERE WALL MOUNTED).
9	LITHONIA PRESCOLITE HALO LIGHTOLIER	AF2/26DTT6MB120 GEB CFR626-3872EB PD6-H226E-6HBB 7726HT120/8056MG	120	2-26W QUAD	6" - 7 3/8" APERATURE BLACK BAFFLE, ELECTRONIC BALLAST
10	KIM LIGHTING	WD14D2-100PMH120V-STD FINISH		1-100W MH	MH SPEC. WALL PACK LIGHT DISTRIBUTION TYPE II CONFIRM FINISH WITH CONTRACT ADMINISTRATOR
11	KIM LIGHTING	WD14D3-100PMH120V-STD FINISH		1-100W MH	MH SPEC. WALL PACK LIGHT DISTRIBUTION TYPE III CONFIRM FINISH WITH CONTRACT ADMINISTRATOR
12	KIM LIGHTING	1S-SAR2-150MH120V-STD FINISH		1-150W MH	MH SPEC. POLE. MOUNTED. LIGHT DISTRIBUTION TYPE III C/W FULL CUT OFF.
13	LITHONIA PRESCOLITE FAIL SAFE	LGH70MH7RWFFL120 91S6-70MHFE-F8-120 FRR-1-70MH-120-96/80	120	1-70W MH	HPS POTLIGHT. VANDALPROOF C/W FLUSH TAMPED LENS.