



# 551-2008 ADDENDUM 1

## SUPPLY & DELIVERY OF SINGLE AXLE SANDER SPREADERS

### URGENT

**PLEASE FORWARD THIS DOCUMENT TO  
WHOEVER IS IN POSSESSION OF THE BID  
OPPORTUNITY**

ISSUED: September 4, 2008  
BY: B Dupuis Smith  
TELEPHONE NO. (204) 986-2492

**THIS ADDENDUM SHALL BE INCORPORATED  
INTO THE BID OPPORTUNITY AND SHALL  
FORM A PART OF THE CONTRACT  
DOCUMENTS**

Template Version: A20070419

---

**Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid Opportunity, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 8 of Form A: Bid may render your Bid non-responsive.**

---

### PART A – BID SUBMISSION

Replace: 551-2008 Bid Submission with 551-2008 Addendum 1 - Bid Submission. The following is a summary of changes incorporated in the replacement Bid Submission:

### PART B – BIDDING PROCEDURES

Revise: B2.1 to read: **The Submission Deadline is 4:00 p.m. Winnipeg time, September 12, 2008.**

### PART N – DETAILED SPECIFICATIONS

Revise: 16.1 to read:

Hydraulic pump – front mounted, variable displacement, load sensing axial piston pump, Parker P1075 pump, no substitutes\_\_\_\_\_

Revise: 16.2 to read:

Hydraulic valve bank – pressure compensated, stackable, proportionally controlled using electric solenoids with pulse width modulation, Parker Pulsar VPL, no substitutes. \_\_\_\_\_

Revise 16.2.2 to read:

The valve bank (**for 5 sanding units**) shall be configured to operate the following functions:

- i) Main conveyor – shall operate in two (2) directions with proportional speed. \_\_\_\_\_
- ii) Spinner – shall operate in two (2) directions with proportional speeds. \_\_\_\_\_
- iii) Box Hoist(s) – State make & Model \_\_\_\_\_
- iv) Plow hydraulics – double acting cylinders providing raise/lower and angling left and right. \_\_\_\_\_
- v) Gate – valve shall provide bi-directional control of gate. \_\_\_\_\_

**Revise 16.5 to read:**

Valve enclosure and hydraulic tank ( for sanding units) – 1-piece design, mounted behind the cab on top of the frame rails, approx. 35"H x 24"W x 12"D. Enclosure shall be spring mounted on one side to allow for truck frame flexing. Hydraulic tanks for future dump bodies shall be frame rail mounted. \_\_\_\_\_

**Add 16.2.2.1:**

The valve bank (for future 4 dump bodies) shall be configured to operate the following functions:

- i) Box Hoist(s) – State Make & Model \_\_\_\_\_
- ii) Plow hydraulics double acting cylinders providing raise/lower and angling left and right \_\_\_\_\_

Page numbering on some forms may be changed as a result.