



PLAN - DECK SLAB CONTROL POUR SEQUENCE

1 : 750

- THE CONTRACTOR SHALL PLACE DECK SLAB CONCRETE IN ACCORDANCE TO THE POUR SEQUENCE AND DIRECTION SHOWN IN THE ABOVE PLAN.
- THE CONTRACTOR MAY VARY FROM THE SEQUENCE SHOWN ONLY IF APPROVED BY THE CONTRACT ADMINISTRATOR.
- PIER ZONE CONCRETE SHALL NOT BE PLACED UNTIL THE ADJACENT MIDSPAN AND END SPAN ZONE CONCRETE IS PLACED.
- ARROWS SHOW DIRECTION OF POUR.

0	ISSUED FOR ADDENDUM 2	08.02.29	RHW
NO.	DESCRIPTION	DATE	BY
REVISIONS/ISSUE			

THE CITY OF WINNIPEG
 PUBLIC WORKS DEPARTMENT
 TRANSPORTATION ENGINEERING DIVISION

WARDROP | Engineering Inc.

FORT GARRY TWIN BRIDGES - WESTBOUND STRUCTURE
 REHABILITATION AND ASSOCIATED WORKS
DECK SLAB CONTROL- POUR SEQUENCE

DESIGNED BY: R.H.W.	DRAWN BY: G.I.	DWG NO.
CHECKED BY:	DATE: 08.02.29	0600070700-SKT-S0714