



532-2021 ADDENDUM 1

820 CLOUTIER DRIVE SLOPE STABILIZATION AND PERMANENT FLOOD PROTECTION WORKS

URGENT

PLEASE FORWARD THIS DOCUMENT TO WHOEVER IS IN POSSESSION OF THE BID/PROPOSAL

ISSUED: November 30, 2021
BY: Andrew Ziegler
TELEPHONE NO. 204 986-8687

THIS ADDENDUM SHALL BE INCORPORATED INTO THE BID/PROPOSAL AND SHALL FORM A PART OF THE CONTRACT DOCUMENTS

Template Version: Add 2021-03-05

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid/Proposal, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid/Proposal may render your Bid/Proposal non-responsive.

PART E – SPECIFICATIONS

Add: E3.5	Site access shall be provided by using either path depicted in Appendix C. Trees within this route on the City ROW (Burnham Rd) shall be the contractor's responsibility and removed by a pre-qualified contractor from the Urban Forestry Branch. The appraised value of 7 existing trees within the City ROW is \$6,735.00 and must be included under Item 1 (mobilization/demobilization). The contractor shall supply temporary construction fencing 6-8 ft in height along the west side of the route to protect existing trees. The contractor will be responsible for temporary installation of the access route and a 400mm culvert across the ditch on Cloutier Dr, if required. Costs associated with temporary Hydro service connections shall be included under Item 1 (Mobilization/Demobilization), if required. The site shall be rough graded to its original condition upon demobilization.
-----------	--

APPENDICES

Add: Appendix C	Site Access
Add: Appendix B	Appendix B_E-T3700_Installation_of_Rockfill_Caissons Appendix B_E-T3710_Sleeving_of_Rockfill_Caissons

QUESTIONS AND ANSWERS

- Q1: Is a pump to be supplied as part of the sump pit under Item 9 in form B?
A1: Yes, a pump with 1-1/4" discharge line to be routed over the dike is to be provided.
- Q2: Where can material be stock piled?
A2: Material shall be stored away from the river bank. A location in front of the home on 820 Cloutier Dr would be suitable. Temporary Hydro service relocation will be the responsibility of the contractor, if required.
- Q3: Which route shall be taken to access the work site.
A3: See E3.5 and Appendix C
- Q4: Which tree removals are the responsibility of the Contractor?

A4: All trees within the City ROW will be the responsibility of the contractor. The appraised value of trees within the City ROW is \$6,735, which shall be included in Form B: Prices under Item 1 (Mobilization/Demobilization and Site Access for Shoreline Work). A pre-qualified contractor from the Urban Forestry Branch must be used for removal of trees within the City ROW. The homeowner at 820 Cloutier Dr will remove any trees requiring removal within their property.