



- NOTES:**
- STATIONING IN SOUTH GUTTER OF MARION ST. UNLESS NOTED OTHERWISE.
 - EXISTING CURB INLET ON S.W. SIDE OF MARION ST. = STA. 0+100.0.
 - SEE DWG P3289-06 FOR TYPICAL CROSS SECTIONS AND DETAILS.
 - FINAL CURB HEIGHT TYPICALLY 75mm OR LOWER IN AREAS WHERE DRAINAGE MUST BE MAINTAINED.
 - ALL DIMENSIONS ARE TO BACK OF CURB.
 - ADJUST OR REPLACE EXISTING DRAINAGE INLETS WITH NEW SD-024 OR SD-023 AS DIRECTED BY THE CONTRACT ADMINISTRATOR.
 - ISOLATE MISCELLANEOUS ITEMS IN NEW CONCRETE WORKS AS PER SD-228C.
 - PLANE HEADERS AT ALL INTERSECTING PUBLIC STREETS.
 - LEGAL PLAN AND UNDERGROUND INFORMATION FROM CITY OF WINNIPEG LBIS.
 - 200mm THICK BASE COURSE UNDER CONCRETE PAVEMENT AT MAJOR RADI IMPROVEMENTS.
 - STREET LIGHTS ON SOUTH SIDE TO BE REMOVED AND NORTH SIDE TO BE RELOCATED TO PROPERTY LINE BY OTHERS.
 - TRAFFIC SIGNAL POLES, CONTROLLERS AND UNDERGROUND APPURTENANCES IN PROJECT AREA TO BE UPGRADED BY OTHERS.

METRIC
WHOLE NUMBERS INDICATE MILLIMETRES
DECIMALIZED NUMBERS INDICATE METRES

EXISTING	LEGEND-PLAN	PROPOSED	EXISTING	LEGEND-PLAN	PROPOSED	EXISTING	LEGEND-PROFILE	PROPOSED
150 mm W.M.	WATERMAIN	150 mm W.M.	HYDRO	M.T.S.	150 mm W.M.	WATERMAIN	HYDRANT	150 mm W.M.
300 mm L.D.S.	LAND DRAINAGE SEWER	300 mm L.D.S.	CONCRETE	ASPHALT	300 mm L.D.S.	LAND DRAINAGE SEWER	VALVE	300 mm L.D.S.
250 mm W.W.S.	WASTE WATER SEWER	250 mm W.W.S.	PLANTING	SIDEWALK	250 mm W.W.S.	WASTE WATER SEWER	Q PROFILE	250 mm W.W.S.
○	MANHOLE	●	PAVING STONES	PARTIAL DEPTH REPAIR	□	NORTH/WEST GUTTER	SOUTH/EAST GUTTER	□
▽	CATCH BASIN	▲	CURB INLET	PROPERTY LINE	○	NORTH EDGE OF LANE	SOUTH EDGE OF LANE	○
□	JUNCTIONS	■	SURVEY BAR	CURB RAMP	○			○
□	CULVERT	■			○			○
□	GAS	■			○			○

UNDERGROUND STRUCTURES

DESIGNED BY: S.P.C.
DRAWN BY: A.P.
CHECKED BY: D.B.W.
APPROVED BY:

2 ISSUED FOR TENDER 03/10/08 S.P.C.
1 ISSUED FOR REVIEW 02/1/08 S.P.C.

NO. REVISIONS DATE BY

DILLON CONSULTING

RELEASED FOR CONSTRUCTION

DATE

DESIGNED BY: S.P.C.
DRAWN BY: A.P.
CHECKED BY: D.B.W.
APPROVED BY:

HOR. SCALE: 1:250
VERTICAL: 1:10

DATE: JAN. 23, 2008

THE CITY OF WINNIPEG
PUBLIC WORKS DEPARTMENT

MARION STREET
KENNY STREET TO RUE DES MEURONS
CONCRETE REPAIRS AND ASPHALT OVERLAY
STA. 0+250 TO STA. 0+400

CITY DRAWING NUMBER: P-3289-02
SHEET 2 OF 6

CONSULTANT PROJECT NO.: 07-8632