

Part 1 General

1.1 REFERENCES

- .1 Canadian Standards Association (CSA International)
 - .1 CSA S350-M1980(R1998), Code of Practice for Safety in Demolition of Structures.
- .2 Transport Canada (TC) : Transportation of Dangerous Goods Act, 1992 (TDGA), c. 34.

1.2 SUBMITTALS

- .1 Submit shop drawings in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Before proceeding with demolition of load bearing walls or of other walls and where required by authority having jurisdiction submit for review by Contract Administrator shoring and underpinning drawings prepared by qualified professional engineer registered or licensed in the Province of Manitoba showing proposed method.

1.3 REMOVAL OF HAZARDOUS WASTES

- .1 Prior to start of deconstruction work remove contaminated or hazardous materials from site and dispose of at designated disposal facilities in safe manner in accordance with TDGA and other applicable regulatory requirements.

1.4 SITE CONDITIONS

- .1 Review designated substance report and take precautions to protect environment.
- .2 Should material resembling spray or trowel-applied asbestos or other designated substance listed as hazardous be encountered, stop work, take preventative measures, and notify Contract Administrator immediately.
 - .1 Do not proceed until written instructions have been received from Contract Administrator.
- .3 Notify Contract Administrator before disrupting building access or services.
- .4 Site Environmental Requirements
 - .1 Ensure that selective demolition work does not adversely affect adjacent watercourses, groundwater and wildlife, or contribute to excess air and noise pollution.
 - .2 Do not dispose of waste of volatile materials including but not limited to, mineral spirits, oil, petroleum based lubricants, or toxic cleaning solutions into watercourses, storm or sanitary sewers.
 - .1 Ensure proper disposal procedures are maintained throughout the project.
 - .3 Do not pump water containing suspended materials into watercourses, storm or sanitary sewers or onto adjacent properties.

- .4 Control disposal or runoff of water containing suspended materials or other harmful substances in accordance with as directed by Contract Administrator.
- .5 Protect trees, plants and foliage on site and adjacent properties where indicated.

Part 2 Products

2.1 NOT USED

- .1 Not used.

Part 3 Execution

3.1 PROTECTION

- .1 Prevent movement, settlement, or damage to adjacent structures, utilities, and parts of building to remain in place. Provide bracing and shoring required.
- .2 Keep noise, dust, and inconvenience to occupants to minimum.
- .3 Protect building systems, services and equipment.
- .4 Provide temporary dust screens, covers, railings, supports and other protection as required.

3.2 DEMOLITION AND DISPOSAL

- .1 Remove parts of existing building to permit new construction.
- .2 Trim edges of partially demolished building elements to tolerances as defined by Contract Administrator to suit future use.
- .3 Dispose of removed materials, off site except where specified otherwise, in accordance with authority having jurisdiction.

3.3 CLEANING AND RESTORATION

- .1 Keep site clean and organized throughout deconstruction.
- .2 Upon completion of project, remove debris, trim surfaces and leave work site clean.
- .3 Upon completion of project, reinstate areas, parking surfaces, walkways, light standards, affected by Work to match condition of adjacent, undisturbed areas.

END OF SECTION