



NOTES:

- DO NOT IMPART EXCESSIVE LOADING ON CLARIFIER WALLS AND UNDERGROUND STRUCTURES. PROVIDE CRANE PAD LOCATIONS AND DESIGN CALCULATIONS TO CONTRACT ADMINISTRATOR FOR REVIEW 2 WEEKS PRIOR TO POSITIONING CRANE.
- RESTORE SOD, ASPHALT, TREES, SHRUBS, SPRINKLER SYSTEM, ETC. TO EXISTING CONDITION SUBSEQUENT TO THE COMPLETION OF CONSTRUCTION.
- PROVIDE 100 MM HOUSEKEEPING PADS FOR NEW EXHAUST FANS - REF. MECHANICAL DRAWINGS M0001 AND M0002.
- REFERENCE MECHANICAL DRAWING M0004 FOR NEW ROOF TOP AIR CONDITIONING UNIT. RESIZE ROOF OPENING TO SUIT.
- IF ANY CLARIFIER IS EMPTY BETWEEN NOV.1 AND MARCH 30, THE CLARIFIER SHALL BE HOARDED AND HEATED TO MAINTAIN A TEMPERATURE WITHIN THE CLARIFIER OF NOT LESS THAN 10° C.

COWLEGGEND



B.M. ELEV.			
0	ISSUED FOR TENDER	13/02/08	RJL
NO.	REVISIONS	DATE	BY

KGS GROUP
CONSULTING ENGINEERS & PROJECT MANAGERS

DESIGNED BY: RJL
DRAWN BY: MB

CH2MHILL

CHECKED BY: [Signature]
APPROVED BY: [Signature]

HOR. SCALE: 1:250
VERTICAL: .

RELEASED FOR CONSTRUCTION: [Signature]
DATE: -/12/07

ENGINEER'S SEAL

CONSULTANT DRAWING NO. 1-0101P-C0002-001

THE CITY OF WINNIPEG
WATER AND WASTE DEPARTMENT

PROJECT TITLE: NORTH END WATER POLLUTION CONTROL CENTRE PRIMARY CLARIFIERS SITE PLAN

SHEET OF 01 01

KGS JOB NUMBER: 06-0107-03

CITY DRAWING NUMBER: 1-0101P-C0002-001