



**RECORD DRAWING**

CONTRACTOR  
**Aico Electrical Limited**  
 930 BRADFORD STREET  
 WINNIPEG, MANITOBA  
 (204) 697-1000

DATE COMPLETED: \_\_\_\_\_ SIGNED BY: \_\_\_\_\_

NOTICE: THIS RECORD DRAWING HAS BEEN PREPARED, BASED UPON INFORMATION FURNISHED BY OTHERS. WHILE THIS INFORMATION IS BELIEVED TO BE RELIABLE, THE CONTRACTOR CANNOT ASSURE ITS ACCURACY, AND THIS IS NOT RESPONSIBLE FOR ANY ERRORS OR OMISSIONS WHICH MAY HAVE BEEN INCORPORATED INTO IT AS A RESULT.

Friesen Tokar Architects  
 200 - 2013 Portage Avenue  
 Winnipeg, Canada R3J 0K3  
 Tel: 204.265.9323 Fax: 204.837.7235

DESIGN BY: AA/RC  
 CHECKED BY: CB  
 DATE: APRIL 2004  
 PROJECT NO: 01716  
 FILE NAME: \_\_\_\_\_

REVISIONS:  
 1. ISSUED FOR 50% REVIEW  
 FEBRUARY 6, 2004  
 2. ISSUED FOR 75% REVIEW  
 MARCH 5, 2004  
 3. ISSUED FOR PRETENDER REVIEW  
 APRIL 2004  
 4. ISSUED FOR TENDER  
 MAY 14, 2004  
 5. AS BUILT  
 JUNE 2007

FOR CONTINUATION REFER TO DRAWING E2.3

FOR CONTINUATION, REFER TO DRAWING E2.5

- NOTES:
- "HATCHED AREA" SURROUNDING SKYLIGHTS INDICATES AREA THAT THE CEILING SYSTEM WILL BE REMOVED. ELECTRICAL TO REMOVE AND REINSTALL LIGHTING, FIRE ALARM, PUBLIC ADDRESS, ETC. AS REQUIRED. RELOCATE ANY CONDUITS/WIRING AS NECESSARY TO ACCOMMODATE NEW ROOF OPENING FOR SKYLIGHTS.
  - EXISTING CIRCUITS IN THIS AREA ARE:  
 - EA-1 (EXIT SIGN)  
 - L1-B (NORMAL LIGHTING)  
 - EA-1S (EMERGENCY LIGHTING)
  - OPEN AREA LIGHTING TO BE SWITCHED FROM HERE.
  - LIGHTING LEVEL SENSOR AND OCCUPANCY SENSOR MOUNTED ON CEILING. PROGRAMMED TO TURN OFF ADJACENT FLUORESCENT LIGHTS.
  - SKYLIGHT FIXTURES TO BE WIRED/CONTROLLED BY A LINE VOLTAGE DAY LIGHT SENSOR MOUNTED ON ADJACENT CEILING.
  - CIRCUITS L3-3 AND EA-6 ARE EXISTING LIGHTING CIRCUITS FOR THIS AREA.

**PART MAIN FLOOR PLAN - PART B LIGHTING**  
 SCALE 1/10

**SMS ENGINEERING**  
 02-019-01

ORIGINAL CONTRACT DRAWING  
 SIGNED AND SEALED BY  
 A.J.M. LOISEL, P. ENG  
 MAY 13, 2004

**APECM**  
 Certificate of Authorization  
 SMS Engineering Ltd.  
 No. 966 Expiry April 30, 2005

Drawings and specifications, as instruments of service are the property of the architect. The copyright in the same being reserved to him. No reproduction may be made without the permission of the architect and when made, must bear his name. All copies to be returned to the architect. The contractor shall verify dimensions and shall not be held responsible for accepting any discrepancy in the work for adjustment. This drawing shall not be used for building purposes until countersigned by:

THE CITY OF WINNIPEG

OFFICE ADDITION AND RENOVATIONS  
 1155 PACIFIC AVENUE  
 WINNIPEG, MANITOBA

FRIESEN TOKAR ARCHITECTS

MAIN FLOOR PLAN  
 PART B - LIGHTING  
**E2.4**

2007-04-06 - JANUARY 30, 2008 - 3.4.00V C31 - REMASTER