



**CONCRETE NOTES:**

REINFORCING STEEL SHALL CONFORM TO CAN/CSA - G-30.18  
GRADE 400W

CONCRETE MATERIALS & PLACEMENT SHALL CONFORM TO CAN /CSA - A23.1-04  
EXPOSURE CLASS C-2

32 MPa TYPE 10

MAXIMUM WATER /CEMENT RATIO 0.45

5-8% AIR ENTRAINMENT

PROVIDE 1/2" WIDE CONTROL JOINT FITTED W/ 1/2" FLEXCELL BOARD BETWEEN ALL ADJACENT SLABS AND AT CONSTRUCTION JOINTS. UPON CURE OF CONCRETE, CAULK ALL JOINTS W/ BASF/SONNEBORN SL-1 (LIMESTONE COLOUR) PER MANUFACTURER'S SPECIFICATIONS.

ORIGINAL STAMPED BY: BRENT PINIUTA, P. ENG.  
DATE: 2008.06.26



CITY OF WINNIPEG  
PLANNING, PROPERTY AND  
DEVELOPMENT DEPARTMENT  
CIVIC ACCOMMODATIONS DIVISION  
300-65 GARRY STREET R3C 4K4

PROJECT  
BROOKSIDE CEMETARY  
MONUMENT SUPPORT BEAMS  
3001 NOTRE DAME AVENUE

SHEET TITLE  
TYPICAL SLAB PLAN VIEW  
& CONCRETE NOTES

DRAWN BY

MMK

CHECKED BY

BP

APPROVED BY

BP

DATE

2008.06.24

eFILE

2008039V0.dwg

SCALE

AS SHOWN

PROJECT

NO. 2008-039

SHEET NO.

DS1