The City of Winnipeg RFP No. 1159-2018

Appendix A Page 1 of 1 Template Version: SrC120181015 - Consulting Services RFP

## **APPENDIX A - PRELIMINARY UPGRADE RECOMMENDATIONS**

## CITY OF WINNIPEG WATER AND WASTE DEPARTMENT WASTEWATER SERVICES DIVISION PRELIMINARY RECOMMENDATIONS

#### **Mission FPS:**

#### **Electrical and Automation/Instrumentation**

- 1. Replace or upgrade all existing electrical equipment including but not limited to: service entrance equipment, electrical distribution panels, switchgear, circuit breakers, control panels and motor starters.
- 2. Replace or upgrade Remote Terminal Unit/ Level Sensors and Transmitters
- 3. Install and integrate a Motor Control Centre (MCC)
- 4. Remove existing resistance typed reduced voltage starters (RVS)
- Replacement of electrical distribution system including but not limited to new cabling and wiring, new interior and exterior lighting, wall receptacles in the Station.

## Mechanical

- 1. Main floor cooling fan system upgrades
- 2. Drywell ventilation system upgrades
- 3. New heaters as required
- 4. Replace existing seal water valving

## **Building and Site**

- 1. Localized wood frame wall repair
- 2. Insulate main floor of building
- 3. Exterior siding and/or trim refinishing
- 4. Replace entry door and frame
- 5. Replace existing window and infill wall opening
- 6. Foamed plastic installation in drywell remediation or upgrades
- 7. Repair or replace existing roof, hatch and any associated roof repairs

# Substructure

- 1. Repair grade beam cracks and/or spalling
- 2. Inject & patch cracks in drywell concrete walls and or beams
- 3. Repair drywell floor for drainage
- 4. Repair spalled pump base concrete, grout and/or anchor bolts
- 5. Install new access platforms for pump shaft guide bearings
- 6. Repair wet well roof, wall and column concrete(cracks and or spalling)
- 7. Repair wet well intermediate slab and beam, floor slab and culvert(cracks and/or spalling)
- 8. Inspect and upgrade/repair wet well trash racks
- 9. Upgrade/repair wet well ladders and railings