# FORM A: BID (See B8)

1.	Contract Title	SUPPLY AND DELIVER UTILITY VEHICLES	Y OF FULL SIZE POLICE PURS	SUIT SPORT
2.	Bidder			
		Name of Bidder		
		Usual Business Name of Bidde	er as it appears on Invoice (if different fro	m above)
		Street		
		City	Province	Postal Code
		Email Address of Bidder		
		Facsimile Number		
	(Mailing address if different)	Street or P.O. Box		
		City	Province	Postal Code
		GST Registration Number (if a	pplicable)	
		The Bidder is:		
	(Choose one)	a sole proprietor		
		a partnership		
		a corporation		
		carrying on business und	der the above name.	
3.	Contact Person	The Bidder hereby authorse the Bidder for purposes	orizes the following contact persof the Bid.	son to represent
		Contact Person	Title	
		Telephone Number	Facsimile Number	
		Email Address		
4.	Definitions	All capitalized terms us	sed in the Contract shall have	e the meanings

ascribed to them in the General Conditions and D3.

5.	Offer	The Bidder hereby offers to perform the Work in accordance with the Contract for the price(s), in Canadian funds, set out on Form B: Prices, appended hereto.
6.	Commencement of the Work	The Bidder agrees that no Work shall commence until he/she is in receipt of a notice of award from the Award Authority authorizing the commencement of the Work.
7.	Contract	The Bidder agrees that the Bid Opportunity in its entirety shall be deemed to be incorporated in and to form a part of this offer notwithstanding that not all parts thereof are necessarily attached to or accompany this Bid.
8.	Addenda	The Bidder certifies that the following addenda have been received and agrees that they shall be deemed to form a part of the Contract:
		No Dated
9.	Time	This offer shall be open for acceptance, binding and irrevocable for a period of sixty (60) Calendar Days following the Submission Deadline.
10.	Indigenous Self- Declaration	The City is requesting that Bidders identify if their business is at least 51% owned by one or more Indigenous persons of Canada.
		YES, 51% or more Indigenous ownership
		NO, it is not
		This information is being gathered for statistical purposes only and will not be used for purposes of evaluation.

1.	Signatures	The Bidder or the Bidder's authorized official or	officials have signed thi
		day of	, 20
		Signature of Bidder or Bidder's Authorized Official or Officials	
		(Print here name and official capacity of individual whose si	gnature appears above)
		(Print here name and official capacity of individual whose si	gnature appears above)

# **FORM B: PRICES**

(See B9)

# SUPPLY AND DELIVERY OF FULL SIZE POLICE PURSUIT SPORT UTILITY VEHICLES

# **UNIT PRICES**

ITEM NO.	DESCRIPTION	SPEC. REF.	UNIT	QUANTITY	UNIT PRICE
1.	Full Size Police Pursuit Sport Utility Vehicle	18046	Each	2	

Name of Bidder

#### **FORM N: DETAILED SPECIFICATIONS 18046**

#### FULL SIZE POLICE PURSUIT SPORT UTILITY VEHICLE

## 1. <u>TYPE</u>

- 1.1 Shall be a 2019, 4-door, 4wd, full size police pursuit sport utility vehicle (SUV). The SUV shall be furnished complete and ready for use with all features and equipment as described herein.
- 1.2 STATE MAKE AND MODEL BEING BID: 2019

## 2. OTHER SPECIFICATIONS AND STANDARDS

2.1 All applicable SAE standards form an integral part of these specifications and shall have precedence in any conflict concerning minimum acceptable standards.

Society of Automotive Engineers, SAE: http://www.standardsportal.org/usa\_en/sdo/sae.aspx

2.2 The completed unit and all its components shall comply with all C.M.V.S.S. and Manitoba Highway Traffic Act regulations and requirements including, but not limited to, a Manitoba Government Inspection.

Manitoba Highway Traffic Act: http://web2.gov.mb.ca/laws/statutes/ccsm/h060e.php

Canadian Motor Vehicle Safety Standards, CMVSS: https://www.tc.gc.ca/eng/acts-regulations/acts-1993c16.htm

Under Writers of Canada, ULC: https://canada.ul.com/

## 3. SERVICE FACILITY

3.1 For the purpose of warranty repairs, the manufacturer shall have an authorized service facility located within 10 km of the boundaries of the City of Winnipeg. The facility, or a portion thereof, shall be dedicated to the service and maintenance of the type equipment being offered. Further to B10, Bidders shall provide a description of the service facility including, but not limited to, number of qualified service staff, years of service experience, and general service capabilities within three (3) Business Days upon request of the Contract Administrator.

#### 4. INSTRUCTIONS FOR COMPLETION OF SPECIFICATIONS

- 4.1 All items in these specifications must be answered indicating compliance or non-compliance. Bidders shall state "yes" for compliance or state deviation, or give reply where requested to do so. Deviations shall be clearly stated and fully detailed. Alternatives will be considered subject to evaluation.
- 4.2 Each bidder is required to fill in every blank. Failure to do so may be used as a basis for rejection of bid.

5.		SPECIFICATION	BIDDER TO STATE "YES" OR STATE DEVIATION
5.1	Wheelbase	116 in. approx., <b>state</b>	
5.2	GVWR	7300 lbs. approx., state	
5.3	Engine	5.3L V8	

5.4	Horsepower	355 HP	
5.5	Torque	383 lbf-ft	
5.6	Block heater	Submersible coolant type	
5.7	Cooling	External engine oil cooler, heavy duty air-to-oil for severe service	
5.8	Coolant	Extended Life Coolant, -35°C	
5.9	Battery	720 CCA	
5.10	Alternator	150 Amp	
5.11	Transmission	6-speed automatic with column mounted shifter, electronically controlled with overdrive and tow/ haul mode	
5.12	Transmission cooling	Heavy-duty auxiliary oil cooler for severe service	
5.13	Drive	4-wheel drive with electronic dash mounted switch	
5.14	Transfer case	Active, 2-speed electronic	
5.15	Police pursuit package	State Order Code	
5.16	Skid plates	For engine, transmission and transfer case	
5.17	Frame	Full frame design with 2-front, frame-mounted recovery hooks	
5.18	Rear axle	Heavy duty rear locking differential	
5.19	Towing prep package	Class 3 or 4, 2 in. receiver hitch, Police rated, c/w 7-wire harness, 7-way sealed connector, and trailer sway control	
5.20	Steering	Electric power assist steering	
5.21	Brakes	Upgraded, Police modified, 4-wheel heavy duty, ABS disk brakes	
5.22	OEM wiring harness 1	OEM wiring harness for grille lamps and siren speakers, <b>state</b> Order Code	
5.23	OEM wiring harness 2	OEM wiring harness for horn and siren circuit, state Order Code	
5.24	Ready for patrol prep pkg.	Kerr Industries or equivalent in accordance with B6. Substitutes, including LED corner modules mounted in headlamps and taillamps, two (2) grille LED lights, two (2) liftgate window LED lights, two (2) LED lights in liftgate lip, 100 watt siren speaker, rear door lock release and controller, <b>state</b> Order Code	
5.25	Wheels	Heavy duty steel wheels	
5.26	Tires – front & rear	BSW all terrain radials, P265/60R17, police V-rated, <b>state</b> make and model being bid	
5.27	Tire pressure monitoring	Air pressure sinsors in each tire with pressure display at driver information centre	
5.28	Spare wheel & tire	Full size, same as front and rear wheels and tires, complete with carrier	
5.29	Suspension	Heavy duty, police-rated	
5.30	License plate brackets	Front and rear	

5.3	1 Floor covering	Heavy duty rubber/vinyl floor covering throughout with throw-in rubber floor mats in front	
5.3	32 Mirrors, exterior	Dual exterior, power adjustable, heated	
5.3	3 Mirror, interior	Day/night centre rearview	
5.3	34 Windshield wipers	Intermittent with washer, front and rear	
5.3	35 Ignition keys	Four (4) keys per vehicle, random key code for each vehicle	
5.3	66 Remote keyless entry	Two (2) per vehicle	
5.3	7 Vehicle anti-theft system	Kerr Industries or equivalent in accordance with B6. Substitutes, allowing for removal of key while engine is running, <b>state</b> Order Code	
5.3	88 Speedometer	Certified calibration speedometer	
5.3	9 Spotlamp	OEM, left-hand side, state Order Code	
5.4	0 Liftgate release	Power	
5.4	1 Air conditioning	Unit to be equipped with A/C	
5.4	2 Steering wheel	Tilt type	
5.4	3 Cruise control	Electronic	
5.4	4 Ballistic doors	Kerr Industries or equivalent in accordance with B6. Substitutes, NIJ Level 3 ballistic door panels for front driver and passenger doors including heavy duty check strap and hinge pillar reinforcement on each door, <b>state</b> Order Code	
5.4	5 Door locks	Power	
5.4	6 Rear door locks/handles	Inoperable	
5.4	7 Glass	Deep tint with power windows	
5.4	8 Rear windows	Rear power delete, rear switches inoperable, state Order Code	
5.4	9 Seats, front	40/20/40 split bench, cloth upholstery including 6-way power driver seat	
5.5	60 Seats, rear	Bench, heavy duty vinyl upholstery	
5.5	51 Seats, 3 <sup>rd</sup> row	Seat delete	
5.5	2 Rear window defroster	Electric	
5.5	3 Radio	AM-FM with USB and auxiliary ports	
5.5	64 Radio suppression pkg.	Complete with grounding straps	
5.5	55 Air bags	Front driver and passenger w/side impact, safety canopy with rollover sensor (A-to-D-pillars) knee air bag on front passenger	
5.5	66 12-Volt power point(s)	State quantity and location(s) of outlets	
5.5	7 110 Volt power outlet	To be supplied, state location	
5.5	8 Bluetooth <sup>®</sup> technology	For use with cellular phones, "hands-free" capable, voice command activated through vehicle's radio circuit	
5.5	9 Rear view camera	To be supplied	- <u></u> -
5.6	60 Fuel tank	Fully fuelled upon delivery	

5.61	Colour, interior	Charcoal or black	
5.62	Colour, exterior	Black	
5.63	Warranty	The Contractor is to provide all detailed published warranty information (including all exclusions) at the time of delivery of the equipment. <b>State</b> the following warranties:	
5.64	Basic vehicle	Comprehensive, state	
5.65	Drivetrain coverage	State	
5.66	Roadside assistance	State	
5.67	Corrosion, sheet metal	State	
5.68	Corrosion, rust through	State	
5.69	Delivery point	Vehicles to be serviced, ready for operation and delivered F.O.B. with the freight prepaid, in- cluding N.I.V.S. to the Winnipeg Fleet Manage- ment Agency, 185 Tecumseh St., Winnipeg MB	
5.70	Delivery time	Within 21-calendar weeks from the date of award of contract. Equipment to be delivered between 8:00 am and 3:00 pm on Business Days	
5.71	Delivery contact	The Contractor is to contact the Contract Administrator prior to delivery of the equipment	
5.72	PDI	A pre-delivery inspection is to be performed by the Contractor on the equipment. Proof upon inspection including completed check list	
5.73	Manuals	Manuals to cover the complete equipment including all components thereof, CD and on-line are preferred where available	
5.74	Operator's manual	One (1) per unit	