

GENERAL NOTES


- A. ALL ABANDONED EQUIPMENT AND SERVICES WITHIN AREA OF WORK SHALL BE REMOVED.
- B. THIS BUILDING MAY CONTAIN ASBESTOS. REFER TO FRONT END
- SPECIFICATIONS FOR FURTHER INFORMATION. C. REFER TO ROOF DETAILS FOR ALL NEW AND CAPPED OPENINGS.


DEMOLITION KEY NOTES

- DEMOLISH AND REMOVE EXISTING SIDEWALL SPRINKLER HEAD PROVIDING COVERAGE BELOW OVERHEAD DOOR.
- 2. REMOVE EXISTING OVERHEAD DOOR AND ALL ASSOCIATED HARDWARE, COUNTER BALANCE, DOOR TRACK, TRAFFIC LIGHTS AND CONTROLLERS. RETAIN EXISTING FRAME AND MAKE SUITABLE FOR INSTALLATION OF NEW DOOR. REQUEST REVIEW BY THE CONTRACT ADMINISTRATOR.
- 3. DEMOLISH AND REMOVE EXISTING DOOR CONTROLLER.
- 4. DEMOLISH AND REMOVE EXISTING TRAFFIC LIGHTS AND PATCH
- 5. DEMOLISH AND REMOVE EXISTING ABANDONED PHOTO EYES, RAILING AND WAND SUPPORT BRACKET.
- 6. RETAIN EXISTING IN-FLOOR SENSOR CONTROL AND RE-USE FOR NEW DOOR.

KEY NOTES ⊕

- 1. PROVIDE NEW RAPID ROLL DOOR. CONTRACTOR TO SECURE THE NEW DOOR MOUNTING ANGLES TO THE EXISTING CONCRETE STRUCTURE USING 1/2" DIAMETER X 4" EMBEDMENT HILTI HAS-R ROD AND HILTI HIT-HY 200 GROUT SPACED AS PER THE MOUNTING ANGLE BOLTING HOLES. ELECTRICAL SUBCONTRACTOR TO RECONNECT EXISTING IN-FLOOR VEHICLE SENSING LOOP. CONFIGURE DOOR TO SUIT TRAFFIC IN BOTH DIRECTIONS.
- 2. PROVIDE NEW RED/GREEN TRAFFIC LIGHTS FOR NEW OVERHEAD DOOR. COORDINATE FINAL PLACEMENT AND ANGLE ON SITE WITH











CITY OF WINNIPEG FORT ROUGE TRANSIT BASE - RAPID ROLL DOORS AND RADIANT HEATERS REPLACEMENT

WINNIPEG

MANITOBA

J. T. HORROCKS Member 24767

Drawing Title
MAIN FLOOR PLAN -MAINTENANCE AND REPAIR BUILDING - DEMOLITION AND NEW CONSTRUCTION - MECHANICAL

CONSTRUCTION - MECHANICAL		
Drawn By XZ/IE	Checked By	Approved By JH
Scale AS SHOWN	Date APRIL 2019	Project No. 19-028-01
Revision Number	Drawing Number	Sheet Order
0	M2.2	3 OF 4

