

THE CITY OF WINNIPEG

REQUEST FOR PROPOSAL

RFP NO. 798-2020

PROVISION OF LABORATORY TESTING SERVICES

TABLE OF CONTENTS

PART A - PROPOSAL SUBMISSION

Form A: Bid/Proposal Form B: Prices

PART B - BIDDING PROCEDURES

B1.	Contract Title	1
B2.	Submission Deadline	1
B3.	Enquiries	1
B4.	Confidentiality	1
	Addenda	2
	Substitutes	2
	Proposal Submission	3
	Proposal	4
	Prices	4
	Experience of Proponent and Subcontractors (Section C)	5
	Details of Services the Proponent and Subcontractors Provides (Section D)	5
B12.	Capacity and Ability to provide the Service (Section E)	6
B13.	Disclosure	6
B14.	Conflict of Interest and Good Faith	7
B15.	Qualification	8
	Opening of Proposals and Release of Information	8
	Irrevocable Offer	9
	Withdrawal of Offers	9
	Interviews	
		9
	Negotiations	9
	Evaluation of Proposals	9
B22.	Award of Contract	10
PART C	GENERAL CONDITIONS	
C0.	General Conditions	1
PART D	SUPPLEMENTAL CONDITIONS	
Gene	ral	
	General Conditions	1
	Scope of Services	1
	Cooperative Purchase	1
	Definitions	2
	Contract Administrator	3
	Contractor's Supervisor	3
D7.	Notices	3
Subr	nissions	
	Authority to Carry on Business	4
	Safe Work Plan	
_		4
	Insurance	4
D11.		
	Subcontractor List	4
Sche	Subcontractor List	4
	Subcontractor List dule of Work	
D12.	Subcontractor List dule of Work Commencement	5
D12. D13.	Subcontractor List dule of Work Commencement COVID-19 Schedule Delays	5
D12. D13. D14.	Subcontractor List dule of Work Commencement COVID-19 Schedule Delays Deficiencies	5 5 5
D12. D13. D14. D15.	Subcontractor List dule of Work Commencement COVID-19 Schedule Delays Deficiencies Orders	5 5 5 6
D12. D13. D14. D15.	Subcontractor List dule of Work Commencement COVID-19 Schedule Delays Deficiencies	5 5 5
D12. D13. D14. D15. D16.	Subcontractor List dule of Work Commencement COVID-19 Schedule Delays Deficiencies Orders	5 5 5 6
D12. D13. D14. D15. D15. Meas	Subcontractor List dule of Work Commencement COVID-19 Schedule Delays Deficiencies Orders Records	5 5 5 6
D12. D13. D14. D15. D16. Meas D17.	Subcontractor List dule of Work Commencement COVID-19 Schedule Delays Deficiencies Orders Records surement and Payment	5 5 5 6 6

	Payment Schedule Purchasing Card	7 7
	ranty	_
	Warranty	1
Form	n J: Subcontractor List	8
	- SPECIFICATIONS	
Gen		
E1.	Applicable Specifications and Drawings	1
E2.	Services	1
E3.	Section a (Water)	3
E4.	Section B (Wastewater)	9
E5.	Section C (Schedule A, Wastewater)	13
E6.	Section D (Giardia & Cryptosporidium, Water/Wastewater)	20
E7.	Section E (Regulatory Testing in Water)	21
E9.	Section G (water and Soils, from Landfills)	32
E10.	Turn around time	46

E10. Turn around time

PART B - BIDDING PROCEDURES

B1. CONTRACT TITLE

B1.1 PROVISION OF LABORATORY TESTING SERVICES

B2. SUBMISSION DEADLINE

- B2.1 The Submission Deadline is 12:00 noon Winnipeg time, April 28, 2021.
- B2.2 The Contract Administrator or the Manager of Materials may extend the Submission Deadline by issuing an addendum at any time prior to the time and date specified in B2.1.

B3. ENQUIRIES

- B3.1 All enquiries shall be directed to the Contract Administrator identified in D5.1.
- B3.2 If the Proponent finds errors, discrepancies or omissions in the Request for Proposal, or is unsure of the meaning or intent of any provision therein, the Proponent shall promptly notify the Contract Administrator of the error, discrepancy or omission at least five (5) Business Days prior to the Submission Deadline.
- B3.3 Responses to enquiries which, in the sole judgment of the Contract Administrator, require a correction to or a clarification of the Request for Proposal will be provided by the Contract Administrator to all Proponents by issuing an addendum.
- B3.4 Responses to enquiries which, in the sole judgment of the Contract Administrator, do not require a correction to or a clarification of the Request for Proposal will be provided by the Contract Administrator only to the Proponent who made the enquiry.
- B3.5 All correspondence or contact by Proponents with the City in respect of this RFP must be directly and only with the Contract Administrator. Failure to restrict correspondence and contact to the Contract Administrator may result in the rejection of the Proponents Proposal Submission.
- B3.6 The Proponent shall not be entitled to rely on any response or interpretation received pursuant to B3 unless that response or interpretation is provided by the Contract Administrator in writing.
- B3.7 Any enquiries concerning submitting through MERX should be addressed to: MERX Customer Support Phone: 1-800-964-6379 Email: merx@merx.com

B4. CONFIDENTIALITY

- B4.1 Information provided to a Proponent by the City or acquired by a Proponent by way of further enquiries or through investigation is confidential. Such information shall not be used or disclosed in any way without the prior written authorization of the Contract Administrator. The use and disclosure of the confidential information shall not apply to information which:
 - (a) was known to the Proponent before receipt hereof; or
 - (b) becomes publicly known other than through the Proponent; or
 - (c) is disclosed pursuant to the requirements of a governmental authority or judicial order.
- B4.2 The Proponent shall not make any statement of fact or opinion regarding any aspect of the Request for Proposal to the media or any member of the public without the prior written authorization of the Contract Administrator.

B5. ADDENDA

- B5.1 The Contract Administrator may, at any time prior to the Submission Deadline, issue addenda correcting errors, discrepancies or omissions in the Request for Proposal, or clarifying the meaning or intent of any provision therein.
- B5.2 The Contract Administrator will issue each addendum at least two (2) Business Days prior to the Submission Deadline, or provide at least two (2) Business Days by extending the Submission Deadline.
- B5.3 Addenda will be available on the MERX website at <u>www.merx.com</u>.
- B5.4 The Proponent is responsible for ensuring that he/she has received all addenda and is advised to check the MERX website for addenda regularly and shortly before the Submission Deadline, as may be amended by addendum.
- B5.5 The Proponent shall acknowledge receipt of each addendum in Paragraph 10 of Form A: Bid/Proposal. Failure to acknowledge receipt of an addendum may render a Proposal nonresponsive.
- B5.6 Notwithstanding B3, enquiries related to an Addendum may be directed to the Contract Administrator indicated in D5.

B6. SUBSTITUTES

- B6.1 The Work is based on the Plant, Materials and methods specified in the Request for Proposal.
- B6.2 Substitutions shall not be allowed unless application has been made to and prior approval has been granted by the Contract Administrator in writing.
- B6.3 Requests for approval of a substitute will not be considered unless received in writing by the Contract Administrator at least five (5) Business Days prior to the Submission Deadline.
- B6.4 The Proponent shall ensure that any and all requests for approval of a substitute:
 - (a) provide sufficient information and details to enable the Contract Administrator to determine the acceptability of the Plant, Material or method as either an approved equal or alternative;
 - (b) identify any and all changes required in the applicable Work, and all changes to any other Work, which would become necessary to accommodate the substitute;
 - (c) identify any anticipated cost or time savings that may be associated with the substitute;
 - (d) certify that, in the case of a request for approval as an approved equal, the substitute will fully perform the functions called for by the general design, be of equal or superior substance to that specified, is suited to the same use and capable of performing the same function as that specified and can be incorporated into the Work, strictly in accordance with the proposed work schedule and the dates specified in the Supplemental Conditions for Total Performance;
 - (e) certify that, in the case of a request for approval as an approved alternative, the substitute will adequately perform the functions called for by the general design, be similar in substance to that specified, is suited to the same use and capable of performing the same function as that specified and can be incorporated into the Work, strictly in accordance with the proposed work schedule and the dates specified in the Supplemental Conditions for Total Performance.
- B6.5 The Contract Administrator, after assessing the request for approval of a substitute, may in his/her sole discretion grant approval for the use of a substitute as an "approved equal" or as an "approved alternative", or may refuse to grant approval of the substitute.

- B6.6 The Contract Administrator will provide a response in writing, at least two (2) Business Days prior to the Submission Deadline, to the Proponent who requested approval of the substitute.
- B6.6.1 The Contract Administrator will issue an Addendum, disclosing the approved materials, equipment, methods and products to all potential Proponents. The Proponent requesting and obtaining the approval of a substitute shall be responsible for disseminating information regarding the approval to any person or persons he/she wishes to inform.
- B6.7 If the Contract Administrator approves a substitute as an "approved equal", any Proponent may use the approved equal in place of the specified item.
- B6.8 If the Contract Administrator approves a substitute as an "approved alternative", any Proponent bidding that approved alternative may base his/her Total Bid Price upon the specified item but may also indicate an alternative price based upon the approved alternative. Such alternatives will be evaluated in accordance with B21.
- B6.9 No later claim by the Contractor for an addition to the Total Bid Price because of any other changes in the Work necessitated by the use of an approved equal or an approved alternative will be considered.

B7. PROPOSAL SUBMISSION

- B7.1 The Proposal shall consist of the following components:
 - (a) Form A: Bid/Proposal;
 - (b) Form B: Prices.
- B7.2 The Proposal should also consist of the following components:
 - (a) Experience of Proponent and Subcontractors (Section C) in accordance with B10;
 - (b) Details of Service the Proponent and Subcontractors provides (Section D), in accordance with B11; and
 - (c) Details of the Capacity and Ability to provide Services (Section E) in accordance with B11.1.
- B7.3 Further to B7.1 all components of the Proposal shall be fully completed or provided in the order indicated, and submitted by the Proponent no later than the Submission Deadline, with all required entries made clearly and completely, to constitute a responsive Proposal.
- B7.4 Further to B7.2, all components of the Proposal should be fully completed or provided in the order indicated, and submitted by the Proponent no later than the Submission Deadline, with all required entries made clearly and completely.
- B7.5 Proposal format, including number of pages, size of pages and, font, etc., will not be regulated, except that the Proposal should contain a table of contents, page numbering and should be in the Sections identified above. Proponents are encouraged to use their creativity to submit a Proposal which provides the requested information for evaluation and other information which illustrates the strength of their proposed solution
- B7.6 The Proposal shall be submitted electronically through MERX at <u>www.merx.com</u>.
- B7.6.1 Proposals will **only** be accepted electronically through MERX.
- B7.7 Proponents are advised that inclusion of terms and conditions inconsistent with the Request for Proposal, will be evaluated in accordance with B21.1(a).
- B7.8 Any cost or expense incurred by the Proponent that is associated with the preparation of the Proposal shall be borne solely by the Proponent.

B8. PROPOSAL

- B8.1 The Proponent shall complete Form A: Bid/Proposal, making all required entries.
- B8.2 Paragraph 2 of Form A: Bid/Proposal shall be completed in accordance with the following requirements:
 - (a) if the Proponent is a sole proprietor carrying on business in his/her own name, his/her name shall be inserted;
 - (b) if the Proponent is a partnership, the full name of the partnership shall be inserted;
 - (c) if the Proponent is a corporation, the full name of the corporation shall be inserted;
 - (d) if the Proponent is carrying on business under a name other than his/her own, the business name and the name of every partner or corporation who is the owner of such business name shall be inserted.
- B8.2.1 If a Proposal is submitted jointly by two or more persons, each and all such persons shall identify themselves in accordance with B8.2.
- B8.3 In Paragraph 3 of Form A: Bid/Proposal, the Proponent shall identify a contact person who is authorized to represent the Proponent for purposes of the Proposal.
- B8.4 Paragraph 13 of Form A: Bid/Proposal shall be signed in accordance with the following requirements:
 - (a) if the Proponent is a sole proprietor carrying on business in his/her own name, it shall be signed by the Proponent;
 - (b) if the Proponent is a partnership, it shall be signed by the partner or partners who have authority to sign for the partnership;
 - (c) if the Proponent is a corporation, it shall be signed by its duly authorized officer or officers;
 - (d) if the Proponent is carrying on business under a name other than his/her own, it shall be signed by the registered owner of the business name, or by the registered owner's authorized officials if the owner is a partnership or a corporation.
- B8.4.1 The name and official capacity of all individuals signing Form A: Bid/Proposal should be entered below such signatures.
- B8.5 If a Proposal is submitted jointly by two or more persons, the word "Proponent" shall mean each and all such persons, and the undertakings, covenants and obligations of such joint Proponents in the Proposal and the Contract, when awarded, shall be both joint and several.

B9. PRICES

- B9.1 The Proponent shall state a price in Canadian funds for each item of the Work identified on Form B: Prices.
- B9.1.1 Notwithstanding C12.2.3, prices on Form B: Prices shall not include the Goods and Services Tax (GST) or Manitoba Retail Sales Tax (MRST, also known as PST), which shall be extra where applicable.
- B9.2 Form B Prices shall contain all fees associated with the testing or the sample including but not limited to sample disposal and sample preparation fee.
- B9.3 The quantities listed on Form B: Prices are to be considered approximate only. The City will use said quantities for the purpose of comparing Proposals.
- B9.4 The quantities for which payment will be made to the Contractor are to be determined by the Work actually performed and completed by the Contractor, to be measured as specified in the applicable Specifications.

B9.5 Where applicable, payments to Non-Resident Contractors are subject to Non-Resident Withholding Tax pursuant to the Income Tax Act (Canada).

B10. EXPERIENCE OF PROPONENT AND SUBCONTRACTORS (SECTION C)

- B10.1 Proposals should include:
 - (a) Details demonstrating the history and experience of the Proponent and Subcontractors in providing the services requested relevant to the scope of work in D2 on up to three projects of similar complexity, scope volume and value in the following areas;
 - (i) Biological Analysis and/or
 - (ii) Chemical Analysis.
- B10.2 For each project listed in B10.1(a), the Proponent should submit:
 - (a) description of the project;
 - (b) testing provided;
 - (c) number of tests and average turn-around times;
 - (d) details about what was done when an instrument and/or operational issue occurred;
 - (e) reference information (two current names with telephone numbers per project) as well as:
 - (i) Name of Client's Organization;
 - (ii) Email Address; and
 - (iii) These references may be contacted without prior notice to the proponent.
- B10.2.1 Where applicable, information should be separated into Proponent and Subcontractor project listings.
- B10.3 Further to B10.2(e) The City reserves the right to make inquiries within the Organization regarding the Proponents work performance and expertise.
- B10.4 The Proposal should include general firm profile information, including years in business, average volume of work, number of employees and other pertinent information for the Proponent and all Subcontractors.

B11. DETAILS OF SERVICES THE PROPONENT AND SUBCONTRACTORS PROVIDES (SECTION D)

- B11.1 Submit details on the following services provided relevant to the scope of work in D2:
 - (a) Location of where the work will be completed (address);
 - (b) Alternate location if an issue arises at the primary location;
 - (c) Description of your sample kit (bottle ordering) procedure;
 - (d) Description of your sample reception procedure;
 - (e) Description of the method used for testing each parameter;
 - (f) Description of your Quality Control / Quality Assurance Programs;
 - (g) Description of your reporting procedure; and
 - (h) Type of services available for priority, rush and emergencies analysis upon request.
- B11.2 Submit the experience and qualifications of the Key Personnel assigned to the services provided in the Contract. Include the following:
 - (a) Names and roles of key personnel in providing the service required; and
 - (b) One page resumes for team members identified as key personnel.
 - (i) Including education, training, job title, years of experience and related work experience; location of work and responsibilities.

- B11.3 The Proposal should include information on the following key feature of the Proponent's operation:
 - (a) Availability of customer customization for reporting, and testing;
 - (b) Description of IT supporting system that the Proponent offers for data migration, collection, customer reporting, downloading and web viewing; and
 - (c) Description of your ability to accept legal samples.

Contingency

- B11.4 The proposal should include a detailed plan on how service levels will be maintained under this Contract if an instrument and/or operational issue occurs.
 - (a) If the plan includes subcontracting, the Proposal should include a list of any Subcontractors that the Proponent may use over the course of the Contract and including the following information for them;
 - (i) Company Name, location, years of business and expertise;
 - (ii) Which services they will be providing on behalf of the Proponent; and
 - (iii) Accreditation Information.

B12. CAPACITY AND ABILITY TO PROVIDE THE SERVICE (SECTION E)

- B12.1 The Proposal should include information which confirms the Proponent has the capacity and ability to provide the services relevant to the scope of work in D2 which includes;
 - (a) Size of the facility and the layout; and
 - (b) Number of instruments and equipment used for each type of analysis performed.
- B12.2 The proposal should include at least one (1) typical workflow for each type of testing under the scope of work the Proponent would provide in D2. This includes;
 - (a) Information on the work flow from sample reception to result reporting
 - (i) Including details about capacity per run and Turn-around Times in accordance with E10.
- B12.3 The Proposal should complete the Accreditation Table for each parameter listed in D2 with the following information related to the scope of work the Proponent would provide under D2. See **Appendix 1**
 - (a) Accredited under D2 Yes/No, and
 - (b) If No, Industry Accreditation Available Yes/No

Site Inspection

B12.4 A site inspection may be performed to confirm the information of the most advantageous offers received, in which a tour of the facility is performed live, or by high quality audio and video recording, or by internet (i.e. seminar, webinar, webex, etc.) of the laboratory in operation and performing analysis identical or similar in nature as proof of the information provide in B11.1

B13. DISCLOSURE

- B13.1 Various Persons provided information or services with respect to this Work. In the City's opinion, this relationship or association does not create a conflict of interest because of this full disclosure. Where applicable, additional material available as a result of contact with these Persons is listed below.
- B13.2 The Persons are:
 - (a) N/A

B14. CONFLICT OF INTEREST AND GOOD FAITH

- B14.1 Further to C3.2, Proponents, by responding to this RFP, declare that no Conflict of Interest currently exists, or is reasonably expected to exist in the future.
- B14.2 Conflict of Interest means any situation or circumstance where a Proponent or Key Personnel proposed for the Work has:
 - (a) other commitments;
 - (b) relationships;
 - (c) financial interests; or
 - (d) involvement in ongoing litigation;

that could or would be seen to:

- exercise an improper influence over the objective, unbiased and impartial exercise of the independent judgment of the City with respect to the evaluation of Proposals or award of the Contract; or
- (ii) compromise, impair or be incompatible with the effective performance of a Proponent's obligations under the Contract.
- (e) has contractual or other obligations to the City that could or would be seen to have been compromised or impaired as a result of its participation in the RFP process or the Project; or
- (f) has knowledge of confidential information (other than confidential information disclosed by the City in the normal course of the RFP process) of strategic and/or material relevance to the RFP process or to the Project that is not available to other proponents and that could or would be seen to give that Proponent an unfair competitive advantage.
- B14.3 In connection with its Proposal, each entity identified in B14.2 shall:
 - (a) avoid any perceived, potential or actual Conflict of Interest in relation to the procurement process and the Project;
 - (b) upon discovering any perceived, potential or actual Conflict of Interest at any time during the RFP process, promptly disclose a detailed description of the Conflict of Interest to the City in a written statement to the Contract Administrator; and
 - (c) provide the City with the proposed means to avoid or mitigate, to the greatest extent practicable, any perceived, potential or actual Conflict of Interest and shall submit any additional information to the City that the City considers necessary to properly assess the perceived, potential or actual Conflict of Interest.
- B14.4 Without limiting B14.3, the City may, in its sole discretion, waive any and all perceived, potential or actual Conflicts of Interest. The City's waiver may be based upon such terms and conditions as the City, in its sole discretion, requires to satisfy itself that the Conflict of Interest has been appropriately avoided or mitigated, including requiring the Proponent to put into place such policies, procedures, measures and other safeguards as may be required by and be acceptable to the City, in its sole discretion, to avoid or mitigate the impact of such Conflict of Interest.
- B14.5 Without limiting B14.3, and in addition to all contractual or other rights or rights at law or in equity or legislation that may be available to the City, the City may, in its sole discretion:
 - (a) disqualify a Proponent that fails to disclose a perceived, potential or actual Conflict of Interest of the Proponent or any of its Key Personnel;
 - (b) require the removal or replacement of any Key Personnel proposed for the Work that has a perceived, actual or potential Conflict of Interest that the City, in its sole discretion, determines cannot be avoided or mitigated;
 - (c) disqualify a Proponent or Key Personnel proposed for the Work that fails to comply with any requirements prescribed by the City pursuant to B14.4 to avoid or mitigate a Conflict of Interest; and

- (d) disqualify a Proponent if the Proponent, or one of its Key Personnel proposed for the Project, has a perceived, potential or actual Conflict of Interest that, in the City's sole discretion, cannot be avoided or mitigated, or otherwise resolved.
- B14.6 The final determination of whether a perceived, potential or actual Conflict of Interest exists shall be made by the City, in its sole discretion.

B15. QUALIFICATION

- B15.1 The Proponent shall:
 - (a) undertake to be in good standing under The Corporations Act (Manitoba), or properly registered under The Business Names Registration Act (Manitoba), or otherwise properly registered, licensed or permitted by law to carry on business in Manitoba, or if the Proponent does not carry on business in Manitoba, in the jurisdiction where the Proponent does carry on business; and
 - (b) be financially capable of carrying out the terms of the Contract; and
 - (c) have all the necessary experience, capital, organization, and equipment to perform the Work in strict accordance with the terms and provisions of the Contract.
- B15.2 The Proponent and any proposed Subcontractor (for the portion of the Work proposed to be subcontracted to them) shall:
 - (a) be responsible and not be suspended, debarred or in default of any obligations to the City. A list of suspended or debarred individuals and companies is available on the Information Connection page at The City of Winnipeg, Corporate Finance, Materials Management Division website at <u>https://www.winnipeg.ca/matmgt/Templates/files/debar.pdf</u>
- B15.3 The Proponent and/or any proposed Subcontractor (for the portion of the Work proposed to be subcontracted to them) shall:
 - (a) have successfully carried out work similar in nature, scope and value to the Work; and
 - (b) be fully capable of performing the Work required to be in strict accordance with the terms and provisions of the Contract; and
 - (c) have a written workplace safety and health program, if required, pursuant to The Workplace Safety and Health Act (Manitoba).
- B15.4 The Proponent shall submit, within three (3) Business Days of a request by the Contract Administrator, proof satisfactory to the Contract Administrator of the qualifications of the Proponent and of any proposed Subcontractor.
- B15.5 The Proponent shall provide, on the request of the Contract Administrator, full access to any of the Proponent's equipment and facilities to confirm, to the Contract Administrator's satisfaction, that the Proponent's equipment and facilities are adequate to perform the Work.

B16. OPENING OF PROPOSALS AND RELEASE OF INFORMATION

- B16.1 Proposals will not be opened publicly.
- B16.2 After award of Contract, the Contract amount and the name of the successful Proponent and their address will be available on the MERX website at <u>www.merx.com</u>.
- B16.3 The Proponent is advised any information contained in any Proposal Submission may be released if required by The Freedom of Information and Protection of Privacy Act (Manitoba), by other authorities having jurisdiction, or by law or by City policy or procedures (which may include access by members of City Council).
- B16.3.1 To the extent permitted, the City shall treat as confidential information, those aspects of a Proposal Submission identified by the Proponent as such in accordance with and by

reference to Part 2, Section 17 or Section 18 or Section 26 of The Freedom of Information and Protection of Privacy Act (Manitoba), as amended.

B16.4 Following the award of Contract, a Proponent will be provided with information related to the evaluation of his/her submission upon written request to the Contract Administrator.

B17. IRREVOCABLE OFFER

- B17.1 The Proposal(s) submitted by the Proponent shall be irrevocable for the time period specified in Paragraph 11 of Form A: Bid/Proposal.
- B17.2 The acceptance by the City of any Proposal shall not release the Proposals of the other responsive Proponents and these Proponents shall be bound by their offers on such until a Contract for the Work has been duly formed and the contract securities have been furnished as herein provided, but any Bid shall be deemed to have lapsed unless accepted within the time period specified in Paragraph 11 of Form A: Bid/Proposal.

B18. WITHDRAWAL OF OFFERS

B18.1 A Proponent may withdraw his/her Proposal without penalty prior to the Submission Deadline.

B19. INTERVIEWS

B19.1 The Contract Administrator may, in his/her sole discretion, interview Proponents during the evaluation process.

B20. NEGOTIATIONS

- B20.1 The City reserves the right to negotiate details of the Contract with any Proponent. Proponents are advised to present their best offer, not a starting point for negotiations in their Proposal Submission.
- B20.2 The City may negotiate with the Proponents submitting, in the City's opinion, the most advantageous Proposals. The City may enter into negotiations with one or more Proponents without being obligated to offer the same opportunity to any other Proponents. Negotiations may be concurrent and will involve each Proponent individually. The City shall incur no liability to any Proponent as a result of such negotiations.
- B20.3 If, in the course of negotiations pursuant to B20.2, the Proponent amends or modifies a Proposal after the Submission Deadline, the City may consider the amended Proposal as an alternative to the Proposal already submitted without releasing the Proponent from the Proposal as originally submitted.

B21. EVALUATION OF PROPOSALS

- B21.1 Award of the Contract shall be based on the following evaluation criteria:
 - (a) compliance by the Proponent with the requirements of the Request for Proposal or acceptable deviation therefrom: (pass/fail)
 - (b) qualifications of the Proponent and the Subcontractors, if any, pursuant to B15:

. ,		(pass/fail)
(c)	Evaluated Bid Price (Section B)	40%
(d)	Experience of Proponent and Subcontractor; (Section C)	10%
(e)	Details of Services the Proponent Provides; (Section D)	25%
(f)	Capacity and Ability to Provide the Service; (Section E)	25%

(g) Economic analysis of any approved alternative pursuant to B6

- B21.2 Further to B21.1(a), the Award Authority may reject a Proposal as being non-responsive if the Proposal Submission is incomplete, obscure or conditional, or contains additions, deletions, alterations or other irregularities. The Award Authority may reject all or any part of any Proposal, or waive technical requirements or minor informalities or irregularities if the interests of the City so require.
- B21.3 Further to B21.1(b), the Award Authority shall reject any Proposal submitted by a Proponent who does not demonstrate, in its Proposal or in other information required to be submitted, that it is qualified.
- B21.4 If, in the sole opinion of the City, a Proposal does not achieve a pass rating for B21.1(a) and B21.1(b), the Proposal will be determined to be non-responsive and will not be further evaluated.
- B21.5 Further to B21.1(c), the Evaluated Bid Price shall be the sum of the quantities multiplied by the unit prices for each item shown on Form B: Prices.
- B21.5.1 Further to B21.1(a), in the event that a unit price is not provided on Form B: Prices, the City will determine the unit price by dividing the Amount (extended price) by the approximate quantity, for the purposes of evaluation and payment.
- B21.6 Further to B21.1(d), Experience of Proponent and Subcontractors will be evaluated considering the experience of the organization on projects of similar size and complexity as well as other information requested and submitted in response to B10.
- B21.7 Further to B21.1(e), Details of Service the Proponent Provides will be evaluated considering each detail of the service, based on the information requested and submitted in response to B11.
- B21.8 Further to B21.1(f), Capacity and Ability to Provide the Service will be evaluated to determine if the testing is possible and the capacity is available to complete the work based on the information requested and submitted in response to B11.1.
- B21.9 Notwithstanding B21.1(d) to B21.1(f), where Proponents fail to provide a response to B7.2(a) to B7.2(c), the score of zero may be assigned to the incomplete part of the response.
- B21.10 Proposals will be evaluated considering the information in the Proposal Submission and any interviews held in accordance with B19.
- B21.11 Where references are requested, the reference checks to confirm information provided may not be restricted to only those submitted by the Proponent, and may include organizations representing Persons, known to have done business with the Proponent.
- B21.12 This Contract will be awarded as a whole or by sections.

B22. AWARD OF CONTRACT

- B22.1 The City will give notice of the award of the Contract, or will give notice that no award will be made.
- B22.2 The City will have no obligation to award a Contract to a Proponent, even though one or all of the Proponents are determined to be qualified, and the Proposals are determined to be responsive.
- B22.2.1 Without limiting the generality of B22.2, the City will have no obligation to award a Contract where:
 - (a) the prices exceed the available City funds for the Work;
 - (b) the prices are materially in excess of the prices received for similar work in the past;
 - (c) the prices are materially in excess of the City's cost to perform the Work, or a significant portion thereof, with its own forces;

- (d) only one Proposal is received; or
- (e) in the judgment of the Award Authority, the interests of the City would best be served by not awarding a Contract.
- B22.3 Where an award of Contract is made by the City, the award shall be made to the qualified Proponent submitting the most advantageous offer.
- B22.4 Further to Paragraph 7 of Form A: Bid/Proposal and C4, the City may issue an award letter to the successful Proponent in lieu of execution of Contract Documents.
- B22.4.1 The Contract documents as defined in C1.1(o)(ii) in their entirety shall be deemed to be incorporated in and to form a part of the award letter notwithstanding that they are not necessarily attached to or accompany said award letter.
- B22.5 Following the award of contract, a Proponent will be provided with information related to the evaluation of his/her Proposal upon written request to the Contract Administrator.
- B22.6 If, after the award of Contract, the Project is cancelled, the City reserves the right to terminate the Contract. The Proponent will be paid for all Services rendered up to time of termination.

PART C - GENERAL CONDITIONS

C0. GENERAL CONDITIONS

- C0.1 The *General Conditions for Supply of Services* (Revision 2020-01-31) are applicable to the Work of the Contract.
- C0.1.1 The General Conditions for Supply of Services are available on the Information Connection page at The City of Winnipeg, Corporate Finance, Materials Management Division website at http://www.winnipeg.ca/matmgt/gen_cond.stm
- C0.2 A reference in the Request for Proposal to a section, clause or subclause with the prefix "**C**" designates a section, clause or subclause in the *General Conditions for Supply of Services*.

PART D - SUPPLEMENTAL CONDITIONS

GENERAL

D1. GENERAL CONDITIONS

D1.1 In addition to the *General Conditions for Supply of Services*, these Supplemental Conditions are applicable to the Work of the Contract.

D2. SCOPE OF SERVICES

- D2.1 The Work to be done under the Contract shall consist of provision of laboratory testing services from date of award until April 30, 2022 with the option of four (4) mutually agreed upon one (1) year extensions.
- D2.1.1 The City may negotiate the extension option with the Proponent within sixty (60) Calendar Days prior to the expiry date of the Contract. The City shall incur no liability to the Proponent as a result of such negotiations.
- D2.1.2 Changes resulting from such negotiations shall become effective on May 1 of the respective year. Changes to the Contract shall not be implemented by the Contractor without written approval by the Contract Administrator.
- D2.1.3 Bidders are advised that, in future, the City may be participating in collaborative procurement initiatives with other levels of government. Accordingly, extensions to this Contract may not be exercised.
- D2.2 The major components of the Work are as follows:
 - (a) Contractor will be responsible for samples from the time they take possession from the agreed upon location;
 - (b) Contractor will be responsible for prepared sample bottles until a City of Winnipeg employee takes possession from the agreed upon location;
 - (c) Detailed reports; and
 - (d) Detailed and summarized invoices.
- D2.3 The Work shall be done on an "as required" basis during the term of the Contract.
- D2.3.1 The type and quantity of Work to be performed under this Contract shall be as authorized from time to time by the Contract Administrator and/or Users.
- D2.3.2 Subject to C7, the City shall have no obligation under the Contract to purchase any quantity of any item in excess of its actual operational requirements.
- D2.4 A site inspection can take place anytime throughout the term of the Contract to confirm that the capacity and ability to provide the service is still in place.
- D2.5 The City may add the scope of work from Bid Opportunity # 79-2018 Provision of Laboratory Services for Landfills as listed under Section G, E9 to this contract at the completion of the City's existing contract, including extensions, if exercised.
- D2.6 Notwithstanding D2.1, in the event that operational changes result in substantial changes to the requirements for Work, the City reserves the right to alter the type or quantity of work performed under this Contract, or to terminate the Contract, upon thirty (30) Calendar Days written notice by the Contract Administrator. In such an event, no claim may be made for damages on the ground of loss of anticipated profit on Work.

D3. COOPERATIVE PURCHASE

D3.1 The Contractor is advised that this is a cooperative purchase.

- D3.2 The Contract Administrator may, from time to time during the term of the Contract, approve other public sector organizations and utilities, including but not limited to municipalities, universities, schools and hospitals, to be participants in the cooperative purchase.
- D3.3 The Contract Administrator will notify the Contractor of a potential participant and provide a list of the delivery locations and estimated quantities.
- D3.4 If any location of the potential participant is more than ten (10) kilometres beyond the boundaries of the City of Winnipeg, the Contractor shall, within fifteen (15) Calendar Days of the written notice, notify the Contract Administrator of the amount of any additional delivery charge for the location.
- D3.5 If any additional delivery charges are identified by the Contractor, the potential participant may accept or decline to participate in the cooperative purchase.
- D3.6 The Contractor shall enter into a contract with each participant under the same terms and conditions as this Contract except:
 - (a) supply under the contract shall not commence until the expiry or lawful termination of any other contract(s) binding the participant for the same goods;
 - (b) a participant may specify a duration of contract shorter than the duration of this Contract;
 - (c) a participant may specify that only some items under this Contract and/or less than its total requirement for an item are to be supplied under its contract; and
 - (d) any additional delivery charge identified and accepted in accordance with clause D3.4 and D3.5 will apply.
- D3.7 Each participant will be responsible for the administration of its contract and the fulfilment of its obligations under its contract. The City shall not incur any liability arising from any such contract.
- D3.8 No participant shall have the right or authority to effect a change in the Contract, or of any other participant in this Contract.

D4. DEFINITIONS

- D4.1 When used in this Request for Proposal:
 - (a) "/100L" means per one hundred (100) litres;
 - (b) "CALA" means Canadian Association for Laboratory Accreditation;
 - (c) "cfu/mL" means colony forming units per millilitre;
 - (d) "cfu/100mL" means colony forming units per 100 millilitre;
 - (e) "E. coli" means Escherichia coliform;
 - (f) "ISO/IEC" means International Standards Organization;
 - (g) "MDL" means method detection limit;
 - (h) "mg/kg" means milligrams per kilogram;
 - (i) "mg/L" means milligrams per liter;
 - (j) "MPN" means most probable number;
 - (k) "MPNU/mL" means most probable number units per 100 millilitre;
 - (I) "ng/L" means nanograms per litre;
 - (m) "Open water season" means the period beginning in spring when all the ice on the surface waters are melted until the time when ice has started to form on the surface waters where the City conducts its sampling. Typically approximately 7 months duration;
 - (n) "pg/L" means picograms per litre;
 - (o) "pg/mL" means picograms per millilitre;

- (p) ""Proponent" means any Person or Persons submitting a Proposal for Services;
- (q) "**Positive**" means a coliform result of greater than one (1);
- (r) "SCC" means Standard Council of Canada;
- (s) "**Turn-around Time**" means the time (expressed in Calendar Days') required to report test results from the time a sample is received by Contractor;
- (t) "µg/L" means micrograms per litre;
- (u) "**User**" means a person, department or other administrative unit of the City authorized by the Contract Administrator or order Work under this Contract.

D5. CONTRACT ADMINISTRATOR

D5.1 The Contract Administrator is:

Courtney Diduck Analytical Services Brach Head

Telephone No. 204-986-4752 Email Address.: <u>cdiduck@winnipeg.ca</u>

D5.2 At the pre-commencement meeting, the Contract Administrator will identify additional personnel representing the Contract Administrator and their respective roles and responsibilities for the Work.

D6. CONTRACTOR'S SUPERVISOR

- D6.1 Further to C6.22, the Contractor shall employ and keep on the Work, at all times during the performance of the Work, a competent supervisor and assistants, if necessary, acceptable to the Contract Administrator. The supervisor shall represent the Contractor on the Site. The supervisor shall not be replaced without the prior consent of the Contract Administrator unless the supervisor proves to be unsatisfactory to the Contractor and ceases to be in his/her employ.
- D6.2 Before commencement of Work, the Contractor shall identify his/her designated supervisor and any additional personnel representing the Contractor and their respective roles and responsibilities for the Work.
- D6.2.1 Further to C5.5 Contract Administrator may give instructions or orders to the Contractor's supervisor and such instructions or orders shall be deemed to have been given to the Contractor.

D7. NOTICES

- D7.1 Except as provided for in C22.4, all notices, requests, nominations, proposals, consents, approvals, statements, authorizations, documents or other communications to the Contractor shall be sent to the address or facsimile number identified by the Contractor in Paragraph 2 of Form A: Bid/Proposal.
- D7.2 All notices, requests, nominations, proposals, consents, approvals, statements, authorizations, documents or other communications to the City, except as expressly otherwise required in, D7.4 or elsewhere in the Contract, shall be sent to the attention of the Contract Administrator identified in D4.
- D7.3 All notices, requests, nominations, proposals, consents, approvals, statements, authorizations, documents or other communications required to be submitted or returned to the City Solicitor shall be sent to the following facsimile number:

The City of Winnipeg Legal Services Department Attn: Director of Legal Services Facsimile No.: 204 947-9155

SUBMISSIONS

D8. AUTHORITY TO CARRY ON BUSINESS

D8.1 The Contractor shall be in good standing under The Corporations Act (Manitoba), or properly registered under The Business Names Registration Act (Manitoba), or otherwise properly registered, licensed or permitted by law to carry on business in Manitoba, or if the Contractor does not carry on business in Manitoba, in the jurisdiction where the Contractor does carry on business, throughout the term of the Contract, and shall provide the Contract Administrator with evidence thereof upon request.

D9. SAFE WORK PLAN

- D9.1 The Contractor shall provide the Contract Administrator with a Safe Work Plan at least five (5) Business Days prior to the commencement of any Work on the Site but in no event later than the date specified in C4.1 for the return of the executed Contract.
- D9.2 The Safe Work Plan should be prepared and submitted in the format shown in the City's template which is available on the Information Connection page at The City of Winnipeg, Corporate Finance, Materials Management Division website at http://www.winnipeg.ca/matmgt/safety/default.stm

D10. INSURANCE

- D10.1 The Contractor shall provide and maintain the following insurance coverage:
 - (a) commercial general liability insurance, in the amount of at least two million dollars (\$2,000,000.00) inclusive, with The City of Winnipeg added as an additional insured; such liability policy to also contain a cross-liability clause, non-owned automobile liability and products and completed operations cover, to remain in place at all times during the performance of the Work;
 - (b) if applicable, Automobile Liability Insurance covering all motor vehicles, owned and operated and used or to be used by the Contractor directly or indirectly in the performance of the Service. The Limit of Liability shall not be less than \$2,000,000 inclusive for loss or damage including personal injuries and death resulting from any one accident or occurrence;
 - (c) Professional liability or Errors and Omissions liability insurance in the amount of at least one million dollars (\$1,000,000) per claim to remain in place at all times during the performance of the Work and throughout the warranty period.
- D10.2 Deductibles shall be borne by the Contractor.
- D10.3 The Contractor shall provide the Contract Administrator with a certificate(s) of insurance, in a form satisfactory to the City Solicitor, at least two (2) Business Days prior to the commencement of any Work on the Site but in no event later than the date specified in C4.1 for the return of the executed Contract Documents, if applicable.
- D10.4 The Contractor shall not cancel, materially alter, or cause the policy to lapse without providing at least thirty (30) Calendar Days prior written notice to the Contract Administrator.
- D10.5 The City shall have the right to alter the limits and/or coverages as reasonably required from time to time during the continuance of this agreement.

D11. SUBCONTRACTOR LIST

D11.1 The Contractor shall provide the Contract Administrator with a complete list of the Subcontractors whom the Contractor proposes to engage (Form J: Subcontractor List) at least two (2) Business Days prior to the commencement of any Work on the Site.

SCHEDULE OF WORK

D12. COMMENCEMENT

- D12.1 The Contractor shall not commence any Work until he/she is in receipt of a notice of award from the City authorizing the commencement of the Work.
- D12.2 The Contractor shall not commence any Work on the Site until:
 - (a) the Contract Administrator has confirmed receipt and approval of:
 - (i) evidence of authority to carry on business specified in D8;
 - (ii) evidence of the workers compensation coverage specified in C6.14;
 - (iii) evidence of the insurance specified in D10; and
 - (iv) the Subcontractor list specified in D11.
 - (b) the Contractor has attended a meeting with the Contract Administrator, or the Contract Administrator has waived the requirement for a meeting.

D13. COVID-19 SCHEDULE DELAYS

- D13.1 The City acknowledges that the schedule for this Contract may be impacted by the COVID-19 pandemic. Commencement and progress of the Work shall be performed by the Contractor with due consideration to the health and safety of workers and the public, directives from health authorities and various levels of government and in close consultation with the Contract Administrator.
- D13.2 If the Contractor is delayed in the performance of the Work by reason of the COVID-19 pandemic, the Work schedule may be adjusted by a period of time equal to the time lost due to such delay and costs related to such delay will be determined as identified herein.
- D13.3 A minimum of seven (7) Calendar Days prior to the commencement of Work, the Contractor shall declare whether COVID-19 will affect the start date. The Contractor shall provide sufficient evidence that the delay is directly related to COVID-19, including but not limited to evidence related to availability of staff, availability of Material or work by others.
- D13.4 For any delay related to COVID-19 and identified after Work has commenced, the Contractor shall within seven (7) Calendar Days of becoming aware of the anticipated delay declare the additional delay and shall provide sufficient evidence as indicated in D13.3. Failure to provide this notice will result in no additional time delays being considered by the City.
- D13.5 The Work schedule, including the durations identified in D12 where applicable, will be adjusted to reflect delays accepted by the Contract Administrator.
- D13.6 Any time or cost implications as a result of COVID-19 and in accordance with the above, as confirmed by the Contract Administrator, shall be documented in accordance with C7.

D14. DEFICIENCIES

- D14.1 Further to C11.7, the Contract Administrator may order the Contractor to alter or improve his/her methods, to increase or improve his/her Plant, to furnish additional or more suitable Material, or to employ additional or more qualified labour if, at any time, the Contract Administrator determines that:
 - (a) the Work is not being, or will likely not be, performed satisfactorily; or
 - (b) progress is not being, or will likely not be, maintained in accordance with the work schedule.

D15. ORDERS

D15.1 The Contractor shall provide a local Winnipeg telephone number or a toll-free telephone number at which orders for service may be placed.

D16. RECORDS

- D16.1 The Contractor shall keep detailed records of the services supplied under the Contract.
- D16.2 The Contractor shall record, as a minimum, for each item listed on Form B: Prices:
 - (a) user name(s) and addresses;
 - (b) order date(s);
 - (c) service date(s); and
 - (d) description and quantity of services provided.
- D16.3 The Contractor shall provide the Contract Administrator with a copy of the usage records for each year within thirty (30) Calendar Days of the end of year one (1) and within thirty (30) Calendar days at the end of any Contract extension period should the Contract be extended.

MEASUREMENT AND PAYMENT

D17. INVOICES

D17.1 Further to C12, the Contractor shall submit monthly invoice(s) to each Contract Supervisor for each portion of work performed and completed during the previous calendar month to:

The City of Winnipeg Corporate Finance - Accounts Payable 4th Floor, Administration Building, 510 Main Street Winnipeg MB R3B 1B9

Facsimile No.: 204- 949-0864 Send Invoices to <u>CityWpgAP-INVOICES@winnipeg.ca</u> Send Invoice Inquiries to <u>CityWpgAP-INQUIRIES@winnipeg.ca</u>

- D17.2 Invoices must clearly indicate, as a minimum:
 - (a) the City's purchase order number;
 - (b) reference to the contract number;
 - (c) date of delivery;
 - (d) delivery address;
 - (e) account owner/contract supervisor;
 - (f) summary of the type and quantity of work performed;
 - (g) the amount payable with GST, MRST, and any applicable environmental handling charges/fees identified and shown as separate amounts; and
 - (h) the Contractor's GST registration number.
- D17.3 The City will bear no responsibility for delays in approval of invoices which are improperly submitted.

D18. PAYMENT

D18.1 Further to C12, the City may at its option pay the Contractor by direct deposit to the Contractor's banking institution.

Payment Deductions;

- D18.2 If the test results and reports as per E2.7 to E2.9 for Routine and/or Rush Samples are not provided to the Contract Administrator or Contract Supervisor within the applicable Turn-around Time(s) specified in E10, the test results and report is considered late and the Contractor shall reduce the fees payable with respect to the testing service submitted according to the following rates:
 - (a) 1 Calendar Day late, fee reduction is 20%
 - (b) 2 Calendar Days late, fee reduction is 50%
 - (c) 3 or more Calendar Days late, fee reduction is 100%
- D18.3 Further to D18.2, if the Contractor has made contact as per E2.11 payment deductions may not be applied.

D19. PAYMENT SCHEDULE

D19.1 Further to C12, payment shall be in Canadian funds net thirty (30) Calendar Days after receipt and approval of the Contractor's invoice.

D20. PURCHASING CARD

- D20.1 The Contractor shall allow Users to charge items to their purchasing cards at no extra cost.
- D20.2 The Contractor's credit card website/gateway shall have appropriate current Payment Card Industry Data Security standards (PCI DSS) certification, (<u>https://www.pcisecuritystandards.org/index.shtml</u>). The credit card gateway shall meet the credit card data security requirements outlined by the Payment Card Industry Security Standards Council (PCI SSC) for service providers and/or software vendors.

WARRANTY

D21. WARRANTY

D21.1 Notwithstanding C13, Warranty does not apply to this Contract.

FORM J: SUBCONTRACTOR LIST

(See D11)

PROVISION OF LABORATORY TESTING SERVICES

Name	Address
	<u></u>

PART E - SPECIFICATIONS

GENERAL

E1. APPLICABLE SPECIFICATIONS AND DRAWINGS

- E1.1 These Specifications shall apply to the Work.
- E1.2 Bidders are reminded that requests for approval of substitutes as an approved equal or an approved alternative shall be made in accordance with B6. In every instance where a brand name or design specification is used, the City will also consider approved equals and/or approved alternatives in accordance with B6.

E2. SERVICES

- E2.1 The Contractor shall supply Laboratory Testing in accordance with the requirements hereinafter specified.
- E2.2 All tests shall be done according to Environmental Protection Agency (EPA) method or 21st Standard Methods for the Examination of Water and Wastewater, or method agreed upon between the Contract Administer and Contractor.
- E2.3 Each test that is not conducted, through human, instrument, or other error shall be reported as "No Result" or "Not Analyzed" with a corresponding explanation stated. In these cases, the City will not be charged for the sample preparation unless the prepared sample is analyzed for another parameters nor shall they be charged for the testing that is not performed.
- E2.4 The Contractor must contact the Contract Administrator or Contract Supervisors as quickly as possible if Samples are damaged, fail to meet submission protocols/standards associated with the analysis, or when information is questionable on the Submission Form or the Sample containers.
- E2.5 The Contractor shall promptly notify the Contract Administrator if the Sample(s) are lost, incorrectly analyzed, or incorrectly reported or not tested within the method hold time and request resampling or approval to continue testing.
- E2.6 The Contractor must record the date, time and temperature of all sample that are dropped off, picked up or delivered to the Laboratory and make this information available to the Contract Administrator.
- E2.7 Test results and reports shall;
 - (i) be available on the web site, with an electronic copy e-mailed to the specified address and contact person(s);
 - (ii) include Quality Control test reports;
 - (iii) be made available in hard copy format;
 - (iv) be made delivered as an electronic file suitable to be used as Electronic Data Deliverables (EDD) in a format such as XML, CSV, XLS and include Laboratory and sample specific unique identifiers; and
 - (v) be in accordance with the requirements outlined under section 7.8 Reporting of results of the ISO/IEC 17025:2017 Third Edition international standard or otherwise agreed upon between the Contract Administrator and Contractor.
- E2.8 Preliminary or unofficial test results shall be available in accordance with E2.7 with the mutual understanding that the final official results may differ.
- E2.9 Notification shall be made to the Contract Administrator that preliminary results for rush analysis are available to the Contract Administrator.

- E2.10 Further to E.2.9, Notifications shall be made by phone or email.
- E2.11 Notification to the Contract Administrator or Contract Supervisors, shall occur before the required Turn-around Time, if analysis and reporting is not within the required Turn-around Time accompanied with an estimate of the date when the analysis and reporting will be given.
- E2.12 The Contractor shall supply all the bottles required within five business (5) days of ordering for regular testing in a "ready to use" condition and have them available for pick-up by the City from the same location at the drop-off location or have the samples delivered to a location agreed upon between the Contract Administrator and Contractor. Emergency sampling bottles shall be available within the time frame agreed upon between the Contract Administrator and Contractor.
- E2.13 The Contractor will supply the City with sample kits which include shipping containers (e.g. coolers), sample bottles, ice packs, directions and precautions and Material Safety Data Sheets, when reagents, preservatives, or special handling is required as part of the sampling protocol at no additional cost.
- E2.14 The Contractor shall accept delivery of samples between the hours of 8:00a.m and 5:00pm daily during the Monday to Friday workweek.
- E2.15 The Contractor shall accept delivery of samples on Saturdays, Sundays, and statutory holidays. The Contractor shall accept delivery for consecutive hours on Saturdays, Sundays, and statutory holidays as agreed upon by the Contract Administrator. Statutory holidays must be agreed upon at a later date, but within forty-eight (48) hours of the holiday.
- E2.16 All Bacteriological test methods, (Total Coliform, Fecal Coliform, E. Coli) shall commence the same day that samples are received, conditional that the City has met the agreed upon submission deadline and 24 hrs, when the City has missed the deadline.
- E2.17 The Contractor shall have a contact person(s) and phone number that the City can contact at anytime for emergency purposes.
- E2.18 Emergency testing shall commence immediately upon sample delivery and are considered highest priority for analysis, if the City has met the agreed upon conditions with regards to availability, acceptability and notification with the Contractor and it has been agreed upon.
- E2.19 The Contractor shall be currently accredited and maintain status of accreditation for the duration of the contract as per ISO:17025;2017 Third Edition, General Requirements for the Competence of Testing and Calibration Laboratories by one of the following bodies;
 - (i) CALA (Canadian Association for Laboratory Accreditation); or
 - (ii) Standards Council of Canada.
- E2.20 The Contractor shall notify the Contract Administrator immediately in writing of a suspended, withdrawal, or a revoked accredited test being performed under this Contract. Upon review the Contract Administer reserves the right to have the Contractor subcontract the analysis for which accreditation has been suspended, withdrawal, or revoked at no cost to the City. The subcontractor must meet the conditions of this Tender and be approved by the Contract Administer.
- E2.21 If any parameter to be tested under this contract cannot be completed by the Contractor due to an instrument/equipment and/or operational issue and Subcontracting is required to maintain the level of service. The Contract Administer must be advised of the Subcontracting and they must meet the conditions of this Tender and be approved.
- E2.22 The Contractor shall notify the contract administrator of changes, additions or deletions of any test names, test list(s), method detection limit(s), unit of measure or unique identifiers for any test result(s) reported pursuant to E2.7(iv).

- E2.23 A Corrective Action Report is required if any issues arise that impacted the results reported under this contract or if requested by the Contract Administrator, for issues regarding data-related investigations or service requirement.
- E2.24 Further to E2.23, all Corrective Active Reports shall be submitted to the Contract Administrator.
- E2.25 An accredited method is required for testing all parameters listed below.
 - (a) A non-accredited test method for testing any parameters listed below requires the Contract Administrator approval.
- E2.26 Section E7 Regulatory Testing has the following additional mandatory requirements which must meet in order to accept and report results under this selection;
 - (a) Samples submitted under this section are;
 - (i) Required to be submitted on the Water System Submission Form known as the Chain of Custody in the format required by the Office of Drinking Water and approved by the Laboratory and Special Contracts Coordinator of the Office of Drinking Water.
 - (ii) Manitoba Conservation and the Office of Drinking water reserve the right to make changes to the format of the Chain of Custody Form at any time over the course of this Contract at which the Contractor will be required to update and receive approval.
 - (b) Results are required to be reported to the Office of Drinking water by email.
 - (c) Reporting of results need to be done in accordance to Manitoba Conservation and Water Stewardship Environmental Management System EMS Lab Data File Format Schedule 14, Appendix 2.Section A (Water) and the Terms and Conditions for Data Transfer for Manitoba Conservation and Water Stewardship need to be done in accordance to Schedule 14. See Appendix 2 for these documents.
- E2.27 The Contractor shall create custom test codes, for use on the chain of custodies for sample summited consistently with the same required tests.

SPECIFIC TESTING

E3. SECTION A (WATER)

- E3.1 Item 1, Taste and Odour Compound in water shall:
 - (a) consist of approximately twenty four (24) samples annually;
 - (b) consist of three to four (3-4) water samples submitted with each sampling period, occurring more frequently during "open water season";
 - (c) have tests performed to include the following parameters:

Item 1 Taste & Od	our Compound, Water		
Parameters		Units	MDL
2-isopropyl-3-methoxypyra	zine	ng/mL	0.2
2-isobutyl-3-methoxypyraz	ine	ng/mL	0.2
2-methylisoborneol		ng/mL	10
2,4,6-trichloroanisole		ng/mL	0.5
2,3,6-trichloroanisole		ng/mL	0.5
Geosmin		ng/mL	1
3,4,5-trichloroveratrole		ng/mL	0.2

- E3.2 Item 2, Volatile Organic Compounds in water shall:
 - (a) consist of approximately ten (10) samples annually;
 - (b) consist of two to three (2-3) water samples submitted quarterly;

(c) have tests performed to include the following parameters:

Item 2	Item 2 Volatile Organic Compounds, Water		
Parameters Units MDL			MDL
Methylene Chloride		µg/L	2
MTBE		µg/L	0.2

- E3.3 Item 3, N-Nitrosodimethylamine (NDMA) in water, shall:
 - (a) consist of approximately twenty (10) samples annually;
 - (b) consist of two to three (2-3) water samples submitted quarterly;
 - (c) have tests performed to include the following parameters:

Item 3	N-Nitrosodimethylamine (NDMA), Water		
Parameters	Parameters Units MDL		
NDMA		ng/L	0.5

- E3.4 Item 4, Microcystin in water shall:
 - (a) consist of approximately twenty four (24) routine and irregular samples annually;
 - (b) occur more frequently during the summer months (April to October);
 - (c) have tests performed to include the following parameter:

Item 4	Microcystin, Water		
Parameter	'S	Units	MDL
Total Microcystin,		μg/L	1.5
Microcystin LR		μg/L	0.2

- E3.5 Item 5, Total Mercury in water shall:
 - (a) consist of approximately sixty four (64) samples annually;
 - (b) consist of sixteen (16) water samples submitted quarterly;
 - (c) have a minimum of sixteen (16) sample bottles, pre-cleaned and available within four
 (4) hours notice;
 - (d) have tests performed to include the following parameter:

Item 5	Total Mercury, Water		
Parameters		Units	MDL
Total Mercur	y	µg/L	0.005

- E3.6 Item 6, Pesticides and Herbicides (COW Test #12) in water, shall:
 - (a) consist of approximately twenty (20) tests annually;
 - (b) have tests performed to include the following parameters:

Item 6	Pesticides and Herbicides (COW Test #12), Water				
Paramete	Parameters Units MDL				
Pesticide List 1 (LC/MS-MS)					
Eptam		μ g/L	< 0.2		
Propachlo	ſ	μg/L	< 0.2		
Propanil		μg/L	< 0.2		
Propoxur μg/L < 0.2		< 0.2			
Pesticide List 2 (LC/MS-MS)					

Trichlopyr	μg/L	< 0.2			
Chlorthalonil	μg/L	< 0.2			
Miscellaneous Pesticides	µg/L	< 0.2			
Alachlor	μg/L	< 0.2			
Aldicarb	μg/L	< 0.9			
Atrazine	μg/L	< 0.9			
Azinphosmethyl	μg/L	< 0.2			
Bendiocarb	μg/L	< 0.2			
Carbaryl	μg/L	< 0.5			
Carbofuran	μg/L	< 0.2			
Chlorpyrifos	μg/L	< 0.2			
Cyanazine Diazinon	μg/L	< 0.2			
	μg/L	< 0.2			
Diclofop-methyl	μg/L	< 0.2			
Dimethoate	μg/L	< 0.2			
Diquat	μg/L	< 1			
Diuron	μg/L	< 0.2			
Glyphosate	μg/L	< 0.2			
Malathion	μg/L	< 0.2			
Methyl Parathion	μg/L	< 0.2			
Metolachlor	μg/L	< 0.2			
Metribuzin	μg/L	< 0.2			
Paraquat	μg/L	< 1			
Parathion	μg/L	< 0.2			
Phorate	μg/L	< 0.2			
Picloram	μg/L	< 0.2			
Simazine	μg/L	< 0.2			
Terbufos	μg/L	< 0.2			
Triallate	μg/L	< 0.2			
Trifluralin	μg/L	< 0.05			
Organochlorine Pesticides					
Aldrin	μg/L	< 0.02			
alpha-BHC	μg/L	< 0.02			
beta-BHC	μg/L	< 0.02			
delta-BHC	μg/L	< 0.02			
alpha-Chlordane	μg/L	< 0.02			
gamma-Chlordane	μg/L	< 0.02			
op-DDD	μg/L	< 0.02			
pp-DDD	μg/L	< 0.02			
o,p-DDE	μg/L	< 0.02			
pp-DDE	μg/L	< 0.02			
op-DDT	μg/L	< 0.02			
p,p-DDT	μg/L	< 0.02			
Dieldrin	μg/L	< 0.02			
alpha-Endosulfan	μg/L	< 0.02			
beta-Endosulfan	μg/L	< 0.02			
Endrin	μg/L	< 0.02			
Heptachlor	μg/L	< 0.02			
Heptachlor Epoxide	μg/L	< 0.02			
Lindane (gamma-BHC)	μg/L	< 0.02			
Methoxychlor	μg/L	< 0.02			
	r-9-3				

Mirex	μg/L	< 0.02	
Polychlorinated Biphenyls (PCBs)			
Arochlor 1016	μg/L	< 0.1	
Arochlor 1221	μg/L	< 0.1	
Arochlor 1232	μg/L	< 0.1	
Arochlor 1242	μg/L	< 0.1	
Arochlor 1248	μg/L	< 0.1	
Arochlor 1254	μg/L	< 0.1	
Arochlor 1260	μg/L	< 0.1	
Phenoxy Acid Herbicides			
2,4,5-T	μg/L	< 0.05	
2,4,5-TP	μg/L	< 0.05	
2,4-D	μg/L	< 0.05	
2,4-DB	μg/L	< 0.05	
2,4-DP	μg/L	< 0.05	
Bromoxynil	μg/L	< 0.02	
Dicamba	μg/L	< 0.02	
Dichloroprop	μg/L	< 0.05	
Dinoseb	μg/L	< 0.05	
MCPA	μg/L	< 0.05	
MCPB	μg/L	< 0.05	
MCPP (Mecroprop)	μg/L	< 0.05	

E3.7 Item 7, Chromium, Hexavalent in water shall:

- (a) consist of approximately sixty four (64) samples annually;
- (b) consist of sixteen (16) water samples submitted quarterly;
- (c) have tests performed to include the following parameter:

Item 7	Chromium Hexavalent		
Parameters		Units	MDL
Chromium H	exavalent	mg/L	0.0005

E3.8 Item 8, Perchlorate in water shall:

- (a) consist of approximately sixteen (16) samples annually;
- (b) consist of four (4) water samples submitted quarterly;
- (c) have tests performed to include the following parameter:

Item 8	Perchlorate in Water		
Parameters		Units	MDL
Perchlorate		μg/L	0.2

- E3.9 Item 9, Total Metals, in water shall:
 - (a) consist of approximately ninety six (96) samples annually;
 - (b) consist of eight (8) water samples submitted monthly;
 - (c) have tests performed to include the following parameter:

Item 9	Total Metals in Water		
Parameters		Units	MDL

Total Silica (SiO2)	ma/L	0.3

- E3.10 Item 10, Total Kjeldahl Nitrogen in water shall:
 - (a) consist of approximately thirty six (36) sample annually;
 - (b) consist of three (3) water samples submitted monthly;
 - (c) have tests performed to include the following parameter:

Item 10	Total Kjeldahl Nitrogen		
Parameters		Units	MDL
Total Kjeldah	I Nitrogen (as N)	mg/L	0.2

- E3.11 Item 11, Total Phosphorus in water shall:
 - (a) consist of approximately thirty six (36) sample annually;
 - (b) consist of three (3) water samples submitted monthly;
 - (c) have tests performed to include the following parameter:

Item 11	Total Phosphorus, Water		
Parameters		Units	MDL
Total Phosph	orus (as P)	μg/L	1.0

- E3.12 Item 12, Total Reactive Phosphorus in water shall:
 - (a) consist of approximately thirty six (36) sample annually;
 - (b) consist of three (3) water samples submitted monthly;
 - (c) have tests performed to include the following parameter:

Item 12	Total Reactive Phosphorus, Water		
Parameters Units MDL			MDL
Total Reactiv	e Phosphorus (Dissolved)	μg/L	1.0

- E3.13 Item 13, Blue-Green Algae in water shall:
 - (a) consist of approximately ten (10) sample(s) annually;
 - (b) have the test performed to include the following parameter:

Item 13	Blue-Green Algae, Water		
Parameters	;	Units	MDL
Total cyanobacterial cell count in water cell/mL		1	
Genus of an	y cyanobacterial cells present	cell/mL	1

- E3.14 Item 14, Microtoxicity in water shall:
 - (a) consist of approximately ten (10) sample(s) annually;
 - (b) have the test performed to include the following parameter:

Item 14	Microtoxicity, Water		
Parameters		Units	MDL
Microtoxicity	, 15 minutes	%	<10.0
Non-Toxic <	10%		Toxic/Non-Toxic
Microtoxicity	, 5 minutes	%	<10.0

Non-Toxic <10%	Toxic/Non-Toxic

- E3.15 Item 15, Zebra Mussel identification in water shall:
 - (a) Consist of approximately five (5) samples annually;
 - (b) have the test performed to include the following parameter:

Item 15	Zebra Mussel, Water		
Parameters		Units	MDL
Zebra Musse	el Veligars	Counts/sample	0
Juvenile or A	dult Zebra Mussels	Counts/sample	0

- E3.16 Item 16, Alcohols and Glycols in water shall:
 - (a) Consist of approximately two (2) samples annually;
 - (b) Have the test performed to include the following parameter:

Item 16	Item 16 Alcohols and Glycols, Water		
Parameters		Units	MDL
Ethanol		mg/L	5.0
Isobutanol		mg/L	5.0
Isopropanol		mg/L	5.0
Methanol		mg/L	5.0
n-Butanol		mg/L	5.0
Pentanol		mg/L	5.0
Sec-butanol		mg/L	5.0
Diethylene G	lycol	mg/L	5.0
Ethylene Gly	col	mg/L	5.0
Propylene Gl	ycol	mg/L	5.0
Triethylene G	Slycol	mg/L	5.0
Tetraethtlene	Glycol	mg/L	5.0

- E3.17 Item 17, Algae Toxin Testing in water shall:
 - (a) Consist of approximately four (4) sample annually;
 - (b) Have the test performed to include the following parameters;

Item 17	Algae Toxins, Water		
Parameters		Units	MDL
Nodularin by ELISA		ng/mL	0.3
Cylindrospermopsin by ELISA		ng/mL	0.3
Saxitoxins by ELISA		ng/mL	0.3
Anatoxin-a b	y LCMS/MS	ng/mL	0.3

- E3.18 Item 18, Surcharge fee for rush analysis shall:
 - (a) consist of the unit cost for rush analysis of any sample tested under section E3.

E4. SECTION B (WASTEWATER)

- E4.1 Item 19, Fecal Coliform, wastewater shall:
 - (a) consist of up to thirteen hundred and sixty (1360) wastewater samples annually;
 - (b) consist of three (3) wastewater effluent samples submitted daily;
 - (c) the range or "pre-defined endpoint" shall be around twenty four hundred and nineteen (2419), and reported as "greater than" >2,419;
 - (d) or when requested 1 in 10 dilution the range or "pre-defined endpoint" shall be around twenty four thousand one hundred and ninety (24,190), and reported as "greater than" >24,190;
 - (e) have tests to include one (1) of the following parameters based on submission:

Item 19	Fecal Coliform In Wastewater		
Parameters		Units	MDL
Fecal Colifor	m by Quanti-Tray 97 to (pre-defined)		
endpoint		MPN/100 mL	<1
1:10 Fecal C	oliform by Quanti-Tray 97 to (pre-		
defined) end	point	MPN/100 mL	<10

- E4.2 Item 20, Fecal Coliform, to endpoint, (true endpoint), wastewater shall:
 - (a) consist of approximately seventy (70) wastewater samples submitted irregularly, when wastewater flows exceed the wastewater treatment plant's design capacity;
 - (b) be reported as a numerical value;
 - (c) have tests to include the following parameters:

Item 20	Fecal Coliform In Wastewater		
Parameters		Units	MDL
Fecal Coliform by Quanti-Tray 97 to true endpoint			
(no maximur	n value)	MPN/100 mL	<1

- E4.3 Item 21, Escherichia Coliform (E. Coli), wastewater shall:
 - (a) consist of up to thirteen hundred and sixty (1360) wastewater samples annually;
 - (b) consist of three (3) wastewater effluent samples submitted daily;
 - (c) the range or "pre-defined endpoint" shall be around twenty four hundred and nineteen (2419), and reported as "greater than" >2,419;
 - (d) or when requested 1 in 10 dilution the range or "pre-defined endpoint" shall be around twenty four thousand one hundred and ninety (24,190), and reported as "greater than" >24,190;
 - (e) have tests to include one (1) of the following parameters based on submission:

Item 21	Eschericia Coliform In Wastewate	r	
Parameters		Units	MDL
Escherichia Coliform by Quanti-Tray 97 to (pre-			
defined) end	point	MPN/100 mL	<1
1:10 Escherie	chia Coliform by Quanti-Tray 97 to		
(pre-defined)	endpoint	MPN/100 mL	<10

- E4.4 Item 22, Escherichia Coliform (E. Coli), to endpoint, (true endpoint), wastewater shall:
 - (a) consist of approximately seventy (70) wastewater samples submitted irregularly throughout the year, when wastewater flows exceed the wastewater treatment plant's design capacity;
 - (b) be reported as a numerical value.

(c) have tests to include the following parameter:

Item 22	Eschericia Coliform In Wastewater		
Parameters Units MDL			
E. Coli by Quanti-Tray 97 to true endpoint (no			
maximum va	lue)	MPN/100 mL	<1

- E4.5 Item 23, Total Coliform and Escherichia Coliform (E. Coli), wastewater shall:
 - (a) consist of approximately two hundred and twenty (220) wastewater samples submitted throughout the year";
 - (b) consist of eight to eleven (8 to11) surface water samples submitted weekly during "open water season";;
 - (c) the range or "pre-defined endpoint" shall be around twenty four hundred and nineteen (2419), and reported as "greater than" >2,419;
 - (d) have tests to include the following parameters:

Item 23	Total & Eschericia Coliform In Wa	stewater	
Parameters Units MDL		MDL	
E. Coli by Qu	anti-Tray 97 to (pre-defined)		
endpoint		MPN/100 mL	<1
Total Coliform by Quanti-Tray to (pre-defined)			
endpoint		MPN/100 mL	<1

- E4.6 Item 24, Total Coliform and Escherichia Coliform (E. Coli), (true endpoint) wastewater shall:
 - (a) consist of approximately one (1) test annually;
 - (b) be reported as a numerical value;
 - (c) have tests to include the following parameters:

Item 24	Total & Eschericia Coliform In Was	tewater	
Parameters Units MDL			MDL
E. Coli by Quanti-Tray 97 to true endpoint (no			
maximum va	ue)	MPN/100 mL	<1
Total Coliform by Quanti-Tray to true endpoint (no			
maximum va	ue)	MPN/100 mL	<1

- E4.7 Item 25, Total Mercury in wastewater shall:
 - (a) consist of approximately one (1) sample annually
 - (b) have a minimum of four (4) sample bottles, pre-cleaned and available within eight (8) hours notice;
 - (c) have tests performed to include the following parameter:

Item 25	Total Mercury, Wastewater		
Parameters		Units	MDL
Total Mercur	у	µg/L	0.0050

- E4.8 Item 26, Total Mercury in Dewatered Sludge shall;
 - (a) Consist of approximately twenty six (26) dewatered sludge samples submitted biweekly
 - (b) Have tests performed to include the following parameters;

Item 26	Total Mercury, Dewatered Sludge		
Parameters		Units	MDL

Total Mercury 0.2

- E4.9 Item 27, Total Organic Carbon in Dewatered Sludge;
 - (a) Consist of approximately three hundred (300) dewatered sludge samples submitted annually
 - (b) Sample will be provided in the dried state.
 - (c) Have tests performed to include the following parameters;

Item 27	Total Organic Carbon, Dewatered S	Sludge	
Parameters Units MDL		MDL	
Total Organic	c Carbon	% dry basis	0.050

- E4.10 Item 28, Moisture in Dewatered Sludge;
 - (a) Consist of approximately twenty six (26) dewatered sludge samples submitted biweekly
 - (b) Have tests performed to include the following parameters;

Item 28	Moisture, Dewatered Sludge		
Parameters Units MDL		MDL	
Total Moistur	e	%	0.1

- E4.11 Item 29, Total Nitrogen in wastewater;
 - (a) consist of approximately one (1) sample annually;
 - (b) Have tests performed to include the following parameters;

Item 29	Total Nitrogen, Wastewater		
Parameters		Units	MDL
Total Nitroge	n	mg/L	0.2

- E4.12 Item 30, Total Organic Carbon in wastewater;
 - (a) consist of approximately one (1) sample annually;
 - (b) Have tests performed to include the following parameter;

Item 30	tem 30 Total Organic Carbon, Wastewater		
Parameters		Units	MDL
Total Organic Carbon		mg/L	0.6

- E4.13 Item 31, Dissolved Organic Carbon in wastewater;
 - (a) consist of approximately one (1) sample annually;
 - (b) Have tests performed to include the following parameter;

Item 31	Dissolved Organic Carbon, Wastewater		
Parameters Units MDL		MDL	
Dissolved Organic Carbon		mg/L	0.6

- E4.14 Item 32, Ammonia by Colour in wastewater;
 - (a) consist of approximately one (1) sample annually;
 - (b) Have tests performed to include the following parameter;

Item 32	Ammonia, Wastewater		
Parameters		Units	MDL
Ammonia		mg/L N	0.01

E4.15 Item 33, Total Metals in wastewater shall:

- (a) consist of approximately one (1) sample annually;
- (b) have tests performed to include at least the following parameters:

Item 33	Total Metals		
Parameters		Units	MDL
Aluminum		mg/L	0.005
Antimony		mg/L	0.003
Arsenic		mg/L	0.0002
Cadmium		mg/L	0.0001
Chromium		mg/L	0.0007
Cobalt		mg/L	0.001
Copper		mg/L	0.0003
Iron		Mg/L	0.01
Lead		mg/L	0.0004
Manganese		mg/L	0.01
Molybdenum		mg/L	0.0002
Nickel		mg/L	0.002
Phosphorous	6	mg/L	0.1
Selenium		mg/L	0.001
Silver		mg/L	0.001
Tin		mg/L	0.001
Titanium		mg/L	0.001
Zinc		mg/L	0.001

- E4.16 Item 34, Total Nitrogen by Combustion in wastewater sludge;
 - (a) consist of approximately two hundred (200) sample annually;
 - (b) Sample will be provided in the dried state.
 - (c) Have tests performed to include the following parameter;

Item 34 Total Nitrogen, Wastewater Sludge			
Parameters Units MDL		MDL	
Total Nitroge	n	mg/kg	200

- E4.17 Item 35, Available Nutrients in dry Dewatered Sludge;
 - (a) consist of approximately twenty six (26) dewatered sludge samples submitted biweekly;
 - (b) Have tests performed to include the following parameter;

Item 35	Available Nutrients, Dewatered Sludge		
Parameters		Units	MDL
Total Nitrogen		mg/kg	6000
Total Kjeldahl Nitrogen		mg/kg	200

Nitrate+ Nitrite -N	mg/kg	5.0
Nitrate -N	mg/kg	5.0
Nitrite -N	mg/kg	2.0
Available Phosphate -P	mg/kg	40
Available Potassium	mg/kg	40
Available Sulfate - S	mg/kg	20

- E4.18 Item 36, Available Ammonia in wet Dewatered Sludge;
 - (a) consist of approximately twenty six (26) dewatered sludge samples submitted biweekly;
 - (b) Have tests performed to include the following parameter;

Item 36	Available Ammonia, Dewatered Sludge		
Parameters Units MD		MDL	
Available Ammonia -N		mg/kg	320

- E4.19 Item 37, Loss on Ignition at 375 °C wet Dewatered Sludge;
 - (a) consist of approximately twenty six (26) dewatered sludge samples submitted biweekly;
 - (b) Have tests performed to include the following parameter;

Item 37 Loss of Ignition, Dewatered Sludge			
Parameters		Units	MDL
Loss on Ignition at 375 °C		%	1.0

- E4.20 Item 38, Surcharge fee for rush analysis shall:
 - (a) consist of the unit cost for rush analysis of any sample tested under section E4.

E5. SECTION C (SCHEDULE A, WASTEWATER)

- E5.1 Item 39, Total Metals in wastewater shall:
 - (a) consist of approximately one (1) sample annually;
 - (b) have tests performed to include the following parameters:

Item 39	Total Metals, Wastewater		
Parameters		Units	MDL
Arsenic		μg/L	0.20
Cadmium		µg/L	0.01
Chromium		µg/L	1.00
Copper		µg/L	0.20
Lead		µg/L	0.09
Mercury		µg/L	0.0050
Molybdenun	ו	µg/L	0.20
Nickel		µg/L	2.00
Selenium		µg/L	1.00
Zinc		µg/L	5.00

- E5.2 Item 40, Miscellaneous Compounds in wastewater shall:
 - (a) consist of approximately one (1) sample annually

(b) have tests performed to include the following parameters:

Item 40 Miscellaneous Compounds, Wastewater			
Parameters Units MDL			
Chromium, Hexavalent	µg/L	1.0	
Phenols (4AAP)	μg/L	1.0	
Alkyl-Lead (Tetraethyl lead & Tetram	ethyl lead) µg/L	5.0	
Total Oil and Grease	mg/L	5.0	
Toxaphene	µg/L	0.25	
Tributyl Tin	μg/L	0.06	

E5.3 Item 41, Volatile Organic Compounds in wastewater shall:

- (a) consist of approximately one (1) sample annually
- (b) have tests performed to include the following parameters:

Item 41 Volatile Organic Compounds, Wastewater			
Parameters	Parameters Units MDL		
1,1,1,2-Tetracl	1,1,1,2-Tetrachloroethane		0.50
1,1,1-Trichloro	ethane	ug/L	0.50
1,1,2,2-Tetracl	hloroethane	ug/L	0.50
1,1,2-Trichloro	ethane	ug/L	0.50
1,1-Dichloroet	hane	ug/L	0.50
1,1-Dichloroet	hylene	ug/L	0.50
1,2-Dibromoet	hane	ug/L	0.50
1,2-Dichlorobe	enzene	ug/L	0.50
1,2-Dichloroet	hane	ug/L	0.50
1,2-Dichloropr	opane	ug/L	0.50
1,3-Dichlorobe	enzene	ug/L	0.50
1,4-Dichlorobe	enzene	ug/L	0.50
2-Hexanone		ug/L	20
Acetone		ug/L	20
Benzene		ug/L	0.50
Bromodichloro	methane	ug/L	0.50
Bromoform		ug/L	0.50
Bromomethan	e	ug/L	1.0
Carbon Disulfi	de	ug/L	0.50
Carbon tetrach	nloride	ug/L	0.50
Chlorobenzen	e	ug/L	0.50
Chloroethane		ug/L	1.0
Chloroform		ug/L	0.50
Chloromethan	e	ug/L	1.0
cis-1,2-Dichlor	oethylene	ug/L	0.50
cis-1,3-Dichlor	opropene	ug/L	0.50
Dibromochloro	omethane	ug/L	0.50
Dichlorodifluor	omethane	ug/L	1.0
Dichlorometha	ne	ug/L	0.50
Ethyl Benzene		ug/L	0.50
m+p-Xylenes		ug/L	1.0
Methyl Ethyl K	etone	ug/L	20
Methyl Isobuty	I Ketone	ug/L	20

MTBE	ug/L	0.50
o-Xylene	ug/L	0.50
Styrene	ug/L	0.50
Tetrachloroethylene	ug/L	0.50
Toluene	ug/L	0.50
trans-1,2-Dichloroethylene	ug/L	0.50
trans-1,3-Dichloropropene	ug/L	0.50
Trichloroethylene	ug/L	0.50
Trichlorofluoromethane	ug/L	1.0
Trihalomethanes (total)	ug/L	2.0
Vinyl chloride	ug/L	0.50
Xylenes (Total)	ug/L	1.5

E5.4 Item 42, Target Compounds (by GC/MS), in wastewater shall:

- (a) consist of approximately one (1) sample annually;
- (b) have tests performed to include the following parameters:

Item 42	Target Compounds (by GC/MS), Wastewater		
Parameters Units MDL		MDL	
Octachlorostyrene		ug/L	0.50
4,4'-Methylenebis(2-chloroaniline)		ug/L	0.50
Total Dinitrop	byrene	mg/L	0.02

- E5.5 Item 43, Phenoxyacid Herbicides (by GC/MS), in wastewater shall:
 - (a) consist of approximately one (1) sample annually;
 - (b) have tests performed to include the following parameters:

Item 43	Total Phenoxyacid Herbicides (by GC/MS), Wastewater		
Parameters		Units	MDL
2,4,5-TP		ug/L	0.5
MCPA		ug/L	0.5
Mecoprop		ug/L	0.5
2,4,5-T		ug/L	0.5
2,4-D		ug/L	0.5
Bromoxynil		ug/L	0.5
Dicamba		ug/L	0.5
Dinoseb		ug/L	0.5
Picloram		ug/L	0.5

- E5.6 Item 44, Organochlorine Pesticides in wastewater shall:
 - (a) consist of approximately one (1) sample annually;
 - (b) have tests performed to include the following parameters:

Item 44	Organochlorine Pesticides, Wastewater		
Parameters		Units	MDL
Aldrin		ug/L	1
a-chlordane		ug/L	10
g-chlordane		ug/L	10
alpha-BHC		ug/L	1

beta-BHC	ug/L	1
delta-BHC	ug/L	1
o,p-DDD	ug/L	10
pp-DDD	ug/L	10
o,p-DDE	ug/L	10
pp-DDE	ug/L	10
op-DDT	ug/L	10
pp-DDT	ug/L	10
Dieldrin	ug/L	10
alpha-Endosulfan	ug/L	25
beta-Endosulfan	ug/L	10
Endosulfan Sulfate	ug/L	10
Endrin	ug/L	10
Endrin Aldehyde	ug/L	10
Heptachlor	ug/L	1
Heptachlor Epoxide	ug/L	10
Lindane	ug/L	1
Methoxychlor	ug/L	10
Mirex	ug/L	10
Oxychlordane	ug/L	10

E5.7 Item 45, Polychlorinated Biphenyls (PCB) in wastewater shall:

- (a) consist of approximately one (1) sample annually;
- (b) have tests performed to include the following parameters:

Item 45	Item 45 Polychlorinated Biphenyls (PCB), Wastewater		
Parameters		Units	MDL
Aroclor 1016		ug/L	0.05
Aroclor 1221		ug/L	0.05
Aroclor 1232		ug/L	0.05
Aroclor 1242		ug/L	0.05
Aroclor 1248		ug/L	0.05
Aroclor 1254		ug/L	0.05
Aroclor 1260		ug/L	0.05
Aroclor 1262		ug/L	0.05
Aroclor 1268		ug/L	0.05
Total PCBs		ug/L	0.10

- E5.8 Item 46, PCDD (Dioxins) and PCDF (Furans) in wastewater shall:
 - (a) consist of approximately one (1) sample annually;
 - (b) have tests performed to include the following parameters:

Item 46	6 PCDD (Dioxins) and PCDF (Furans), Wastewater		
Parameters Units MDL		MDL	
2378 TeCDD		pg/L	0.6
12378 PeCD	D	pg/L	0.6
123478 HxCI	DD	pg/L	0.4
123678 HxCI	DD	pg/L	0.65
123789 HxCI	DD	pg/L	0.75

1234678 HpCDD	pg/L	0.5
OCDD	pg/L	1.0
Total TCDD	pg/L	*
Total PeCDD	pg/L	*
Total HxCDD	pg/L	*
Total HpCDD	pg/L	*
Total PCDDs	pg/L	*
2378 TeCDF	pg/L	*
12378 PeCDF	pg/L	0.45
23478 PeCDF	pg/L	0.35
123478 HxCDF	pg/L	0.4
123678 HxCDF	pg/L	0.5
123789 HxCDF	pg/L	0.5
234678 HxCDF	pg/L	0.5
1234678 HpCDF	pg/L	0.55
1234789 HpCDF	pg/L	0.3
OCDF	pg/L	0.75
Total TCDF	pg/L	*
Total PeCDF	pg/L	*
Total HxCDF	pg/L	*
Total HpCDF	pg/L	*
Total PCDFs	pg/L	*
Total TEQ (ND=0) (WHO Calc)	pg/L	-
Total TEQ (ND=0.5DL) (WHO Calc)	pg/L	-
Total TEQ (ND=DL) (WHO Calc)	pg/L	-

*lowest detection limit possible based on compounds analyzed

E5.9 Item 47, EPA 8270 Extractables in wastewater shall:

- (a) consist of approximately one (1) sample annually;
- (b) have tests performed to include the following parameters:

Item 47	EPA 8270 Extractables, Wastewater		
Parameters		Units	MDL
1-Chloronapl	nthalene	ug/L	0.4
1-Methylnapl	nthalene	ug/L	0.4
1,2-Dichlorob	benzene	ug/L	0.4
1,2,3-Trichlo	robenzene	ug/L	0.4
1,2,4-Trichlo	robenzene	ug/L	0.4
1,3-Dichlorob	benzene	ug/L	0.4
1,4-Dichlorob	benzene	ug/L	0.4
2-Chloronapl	nthalene	ug/L	0.4
2-Chlorophenol		ug/L	0.3
2-Methylnapl	nthalene	ug/L	0.4
2-Methylpher	nol	ug/L	0.5
2-Nitropheno	l	ug/L	0.5
2,3,4-Trichlo	rophenol	ug/L	0.5
2,3,4,5-Tetra	chlorophenol	ug/L	0.5
2,3,4,6-Tetra	chlorophenol	ug/L	0.5
2,3,5-Trichlo	rophenol	ug/L	0.5
2,3,5,6-Tetra	chlorophenol	ug/L	0.5

2,4-Dichlorophenol	ug/L	0.3
2,4-Dimethylphenol	ug/L	0.5
2,4-Dinitrophenol	ug/L	1
2,4-Dinitrotoluene	ug/L	0.4
2,4,5-Trichlorophenol	ug/L	0.5
2,4,6-Trichlorophenol	ug/L	0.5
2,6-Dichlorophenol	ug/L	0.5
2,6-Dinitrotoluene	ug/L	0.4
3,3'-Dichlorobenzidine	ug/L	0.4
3&4-Methylphenol	ug/L	0.5
4-Bromophenyl phenyl ether	ug/L	0.4
4-Chloro-3-methylphenol	ug/L	0.5
4-Chloroaniline	ug/L	0.4
4-Chlorophenyl phenyl ether	ug/L	0.4
4-Nitrophenol	ug/L	0.5
4,6-Dinitro-2-methylphenol	ug/L	2
5-Nitroacenaphthene	ug/L	0.4
Acenaphthene	ug/L	0.2
Acenaphthylene	ug/L	0.2
Anthracene	ug/L	0.2
Benzo(a)anthracene	ug/L	0.2
Benzo(a)pyrene	ug/L	0.01
Benzo(b)fluoranthene	ug/L	0.2
Benzo(ghi)perylene	ug/L	0.2
Benzo(k)fluoranthene	ug/L	0.2
Biphenyl	ug/L	0.4
Bis(2-chloroethoxy)methane	ug/L	0.4
Bis(2-chloroethyl)ether	ug/L	0.4
Bis(2-chloroisopropyl)ether	ug/L	0.4
Bis(2-ethylhexyl)phthalate	ug/L	2
Butylbenzyl phthalate	ug/L	0.4
Camphene	ug/L	0.4
Chrysene	ug/L	0.2
Cresols (total)	ug/L	1
Di-n-butylphthalate	ug/L	2
Di-n-octylphthalate	ug/L	0.4
Dibenzo(a,h)anthracene	ug/L	0.2
Diethylphthalate	ug/L	0.2
Dimethylphthalate	ug/L	0.2
Diphenyl ether	ug/L	0.4
Diphenylamine	ug/L	0.4
Fluoranthene	ug/L	0.2
Fluorene	ug/L	0.2
Hexachlorobenzene	ug/L	0.04
Hexachlorobutadiene	ug/L	0.2
Hexachlorocyclopentadiene	ug/L	0.4
Hexachloroethane	ug/L	0.4
Indeno(1,2,3-cd)pyrene	ug/L	0.2
Indole	ug/L	0.4
Isophorone	ug/L	0.4
N-Nitroso-di-n-propylamine	ug/L	0.4

Naphthalene	ug/L	0.2
Nitrobenzene	ug/L	0.4
Pentachlorophenol	ug/L	0.5
Perylene	ug/L	0.2
Phenanthrene	ug/L	0.2
Phenol	ug/L	0.5
Pyrene	ug/L	0.2
2-Fluorobiphenyl	%	
2,4,6-Tribromophenol	%	
Nitrobenzene d5	%	
p-Terphenyl d14	%	
Phenol d5	%	

E5.10 Item 48, Nonylphenols and Nonylphenol Ethoxylates in wastewater shall:

- (a) consist of approximately one (1) sample annually;
- (b) have tests performed to include the following parameters:

Item 48	Nonylphenols and Nonylphenol Ethoxylates, Wastewater		
Parameters Units MD			MDL
Nonylphenol	6	μg/L	100
Nonylphenol	Monoethoxylates	μg/L	500
Nonylphenol	Diethoxylates	μg/L	1200
Nonylphenol	Triethoxylates	μg/L	2000
t-Octylpheno		μg/L	2
t-Octylpheno	I Monoethoxylate	μg/L	10
t-Octylpheno	l Diethoxylate	μg/L	50
t-Octylpheno	I Triethoxylate	μg/L	200

(c) Acceptable to not include the following parameter;

Item 48	Nonylphenols and Nonylphenol Ethoxylates, Wastewater		
Parameters Units MDL			MDL
Nonylphenol Triethoxylates		μg/L	2000
t-Octylpheno	I Triethoxylate	μg/L	200

- E5.11 Item 49, Schedule A Testing Complete (complete set of test to include items 39 to 48) shall:
 - (a) consist of approximately twenty four (24) samples annually
 - (b) have tests performed to include all parameters listed under items 39 to 48.
- E5.12 Item 50, Trout Bioassay (Pass/Fail) in wastewater shall:
 - (a) consist of a total of three (3) twenty (20) litre wastewater effluent samples submitted quarterly for a total of twelve (12) twenty (20) litre samples submitted annually, along with item 49;
 - (b) have tests performed according to "Biological Test Method: Reference Method for Determining Acute Lethality of Effluents to Rainbow Trout (EPS 1/RM/13 Second Edition)" of the Environmental Protection Series from Environmental Canada for the following parameters:

Item 50	Trout Bioassay (Pass/Fail), Wastewater		
Parameters		Units	MDL

Trout Bioassay (Pass/Fail)	%	Pass/Fail
----------------------------	---	-----------

- E5.13 Item 51, Trout Bioassay (Pass/Fail) with pH Stabilization in wastewater shall:
 - (a) consist of a total of three (3) twenty (20) litre wastewater effluent samples submitted monthly for a total of thirty six (36) twenty (20) litre samples submitted annually along with item 49 & 50 on selected months;
 - (b) have tests performed according to "Biological Test Method: Reference Method for Determining Acute Lethality of Effluents to Rainbow Trout (EPS 1/RM/13 Second Edition)" and "Procedure for pH Stabilization During the Testing of Acute Lethality of Wastewater Effluent to Rainow Trout" of the Environmental Protection Series from Environmental Canada for the following parameters:

Item 51	Trout Bioassay (Pass/Fail) with pH Stabilization, Wastewater			
Parameters Units MDL				
Trout Bioassay (Pass/Fail) with pH Stabilization % Pass/Fail			Pass/Fail	
Ammonia by	Ammonia by Colour mg/L 0.01			

- E5.14 Item 52, Nitrate in wastewater
 - (a) Consist of approximately twelve (12) sample annually;
 - (b) have tests performed to include the following parameter;

Item 52	Nitrates, Wastewater		
Parameters		Units	MDL
Nitrate		mg/L	0.001

- E5.15 Item 53, Surcharge fee for rush analysis shall:
 - (a) consist of the unit cost for rush analysis of any sample tested under items E5.

E6. SECTION D (GIARDIA & CRYPTOSPORIDIUM, WATER/WASTEWATER)

- E6.1 Item 54, Giardia and Cryptosporidium in water shall:
 - (a) consist of approximately forty (40) filter samples annually, collected from surface waters;
 - (b) have tests performed to include the following parameter:

Item 54	Giardia & Cryptosporidium, Water		
Parameters		Units	MDL
Giardia cyst i	n water,Non-viable	cyst/100L	1.0
Giardia cyst i	n water, Viable	cyst/100L	1.0
Cryptosporid	ium oocyst in water, Non-viable	oocyst/100L	1.0
Cryptosporid	ium oocyst in water, Viable	oocyst/100L	1.0

- E6.2 Item 55, Giardia & Cryptosporidium in wastewater shall:
 - (a) consist of approximately four (4) wastewater samples annually;
 - (b) have tests performed to include the following parameter:

Item 55 Giardia & Cryptosporidium, Wastewater			
Parameters Units MDL			MDL
Giardia cyst	n wastewater, Non-viable	cyst/1L	1.0
Giardia cyst in wastewater, Viable cyst/1L 1.0		1.0	

Cryptosporidium oocyst in wastewater, Non-viable	oocyst/1L	1.0
Cryptosporidium oocyst in wastewater, Viable	oocyst/1L	1.0

- E6.3 Item 56, Filta-Max Filter Modules shall:
 - (a) consists of approximately forty (40) filters annually;
 - (b) filters may packaged and sold in bulk quantities no greater than 10 filter units per pack and;
 - (c) each filter must be individually wrapped/sealed.
- E6.4 Item 57, Surcharge fee for rush analysis shall:
 - (a) consist of the unit cost for rush analysis of any sample tested under items E6.

E7. SECTION E (REGULATORY TESTING IN WATER)

- E7.1 Item 58, Manitoba Conservation Test 54 PWS (General Chemistry Test)
 - (a) Consist of approximately eight (8) test annually
 - (b) Meet Manitoba Conservations Requirement for testing and reporting as described in E2.26
 - (c) Have test performed to include the following parameters

Item 58 Manitoba Conservation Test 54 PWS (General Chemistry)		
Parameters	Units	MDL
Alkalinity, Total (as CaCO3)	mg/L	1
Alkalinity, Bicarbonate (HCO3)	mg/L	0.5
Alkalinity, Carbonate (CO3)	mg/L	0.5
Alkalinity, Hydroxide (OH)	mg/L	0.5
Bromide (Br)	mg/L	0.01
Total Organic Carbon	mg/L	1
Dissolved Organic Carbon	mg/L	1
Chloride (Cl)	mg/L	0.2
Colour, True	CU	5
Conductivity	uS/cm	1
Total Hardness (as CaCO3)	mg/L	0.07
Saturation Index (4.4 °C) (Calculated)		<=-14
Saturation Index (60 °C) (Calculated)		<=-14
Fluoride (F)	mg/L	0.2
Aluminum (Al)-Total	mg/L	0.001
Antimony (Sb)-Total	mg/L	0.0002
Arsenic (As)-Total	mg/L	0.0002
Barium (Ba)-Total	mg/L	0.0002
Boron (B)-Total	mg/L	0.01
Cadmium (Cd)-Total	mg/L	0.00055
Calcium (Ca)-Total	mg/L	0.01
Cesium (Cs)-Total	mg/L	0.0001
Chromium (Cr)-Total	mg/L	0.0157
Copper (Cu)-Total	mg/L	0.0018
Iron (Fe)-Total	mg/L	0.01
Lead (Pb)-Total	mg/L	0.0003
Magnesium (Mg)-Total	mg/L	0.01

Manganese (Mn)-Total	mg/L	0.0002
Phosphorus (P)-Total	mg/L	0.03
Selenium (Se)-Total	mg/L	0.001
Sodium (Na)-Total	mg/L	0.01
Strontium (Sr)-Total	mg/L	0.0002
Uranium (U)-Total	mg/L	0.0001
Zinc (Zn)-Total	mg/L	0.002
Ammonia, Total (as N)	mg/L	0.01
Nitrite (as N)	mg/L	0.001
Nitrate (as N)	mg/L	0.01
рН	pH units	0.1
Sulfate (SO4)	mg/L	0.5
Total Dissolved Solids	mg/L	5
Turbidity	NTU	0.01
Transmittance, UV (254 nm)	% T	1

- E7.2 Item 59, Bromate shall consist of:
 - (a) consist of approximately four (4) tests annually;
 - (b) have tests performed to include the following parameters:

Item 59	BROMATE IN WATER		
Parameters		Units	MDL
Bromate		mg/L	0.005

- E7.3 Item 60, Total Metals shall consist of:
 - (a) Consist of approximately twenty four (24) test annually;
 - (b) Meet Manitoba Conservations Requirement for testing and reporting as described in E2.26
 - (c) Have tests performed to include the following parameters:

Item 60	TOTAL METALS IN WATER		
Parameters	·	Units	MDL
Aluminum		mg/L	0.001
Antimony		mg/L	0.0002
Arsenic		mg/L	0.0002
Barium		mg/L	0.0002
Beryllium		mg/L	0.0002
Bismuth		mg/L	0.0002
Boron		mg/L	0.01
Cadmium		mg/L	0.00055
Calcium		mg/L	0.01
Cesium		mg/L	0.0001
Chromium		mg/L	0.0157
Cobalt		mg/L	0.0002
Copper		mg/L	0.0018

Iron	mg/L	0.01
Lead	mg/L	0.0003
Lithium	mg/L	0.0002
Magnesium	mg/L	0.01
Manganese	mg/L	0.0002
Molybdenum	mg/L	0.073
Nickel	mg/L	0.0104
Potassium	mg/L	0.02
Phosphorous	mg/L	0.03
Rubidium	mg/L	0.0002
Selenium	mg/L	0.001
Silicon	mg/L	0.1
Silver	mg/L	0.0001
Sodium	mg/L	0.01
Strontium	mg/L	0.0002
Tellurium	mg/L	0.0002
Thallium	mg/L	0.008
Thorium	mg/L	0.0001
Tin	mg/L	0.0002
Titanium	mg/L	0.0005
Tungsten	mg/L	0.0001
Uranium	mg/L	0.0001
Vanadium	mg/L	0.0002
Zinc	mg/L	0.002
Zirconium	mg/L	0.002

- E7.4 Item 61, Surcharge fee for rush analysis shall:
 - (a) consist of the unit cost for rush analysis of any sample(s) tested under items E7.

E8. SECTION F (SCHEDULE B, INDUSTRIAL WASTE & SCHEDULE D, LAND DRAINAGE)

- E8.1 Item 62, Total Metals in industrial wastewater shall:
 - (a) be tested as a whole;
 - (b) consist of approximately one (1) sample annually;
 - (c) have tests performed to include at least the following parameters:

ltem 62	Total Metals, Industrial Wastewater		
Parameters		Units	MDL
Aluminum		mg/L	1.0
Antimony		mg/L	1.0
Arsenic		mg/L	0.5
Cadmium		mg/L	0.4
Chromium		mg/L	1.0
Cobalt		mg/L	1.0

Copper	mg/L	1.0
Lead	mg/L	0.5
Manganese	mg/L	1.0
Molybdenum	mg/L	1.0
Nickel	mg/L	1.0
Selenium	mg/L	0.5
Silver	mg/L	1.0
Tin	mg/L	1.0
Titanium	mg/L	1.0
Zinc	mg/L	1.0

E8.2 Item 63, Total Mercury in Industrial Wastewater shall:

(a) consist of approximately one (1) sample annually;

(b) have tests performed to include the following parameter:

Item 63	m 63 Total Mercury, Industrial Wastewater		
Parameters Units MDL		MDL	
Total Mercury	У	mg/L	0.005

- E8.3 Item 64, Chromium, Hexavalent in Industrial Wastewater shall:
 - (a) consist of approximately one (1) sample annually;
 - (b) have tests performed to include the following parameter:

Item 64	Chromium Hexavalent, Industrial Wastewater		
Parameters Units MDL		MDL	
Chromium H	exavalent	mg/L	1.0

- E8.4 Item 65, Total Cyanide in Industrial Wastewater shall:
 - (a) consist of approximately one (1) sample annually;
 - (b) have tests performed to include the following parameter:

Item 65	Total Cyanide, Industrial Wastewater		
Parameters	Parameters Units MDL		MDL
Total Cyanide	9	mg/L	1.0

- E8.5 Item 66, Biochemical Oxygen Demand in Industrial Wastewater shall:
 - (a) consist of approximately one (1) sample annually;
 - (b) have tests performed to include the following parameter:

Item 66	Biochemical Oxygen Demand, Industrial Wastewater		
Parameters Units MDL			MDL
Biochemical	Oxygen Demand	mg/L	3.0

- E8.6 Item 67, Total Suspended Solids in Industrial Wastewater shall:
 - (a) consist of approximately one (1) sample annually;
 - (b) have tests performed to include the following parameter:

ltem 67	Total Suspended Solids, Industrial Wastewater		
Parameters Units MDL		MDL	
Total Susper	ided Solids	mg/L	4.0

- E8.7 Item 68, Fluoride in Industrial Wastewater shall:
 - (a) consist of approximately one (1) sample annually;
 - (b) have tests performed to include the following parameter:

Item 68	Fluoride, Industrial Wastewater		
Parameters Units MDL		MDL	
Fluoride		mg/L	1.0

- E8.8 Item 69, Total Nitrogen in Industrial Wastewater shall:
 - (a) consist of approximately one (1) sample annually;
 - (b) have tests performed to include the following parameter:

Item 69	69 Total Nitrogen, Industrial Wastewater		
Parameters Units MDL		MDL	
Total Nitroge	n	mg/L	1.0

- E8.9 Item 70, Total Phosphorus in Industrial Wastewater shall:
 - (a) consist of approximately one (1) sample annually;
 - (b) have tests performed to include the following parameter:

Item 70	Total Phosphorus, Industrial Wastewater		
Parameters	Parameters Units MDL		
Total Phosph	Total Phosphorusmg/L1.0		1.0

- E8.10 Item 71, Total Sulphate in Industrial Wastewater shall:
 - (a) consist of approximately one (1) sample annually;
 - (b) have tests performed to include the following parameter:

Item 71	Total Sulphate, Industrial Wastewater		
Parameters	Parameters Units MDL		MDL
Total Sulphate r		mg/L	5.0

- E8.11 Item 72, Total Sulphide in Industrial Wastewater shall:
 - (a) consist of approximately one (1) sample annually;
 - (b) have tests performed to include the following parameter:

Item 72	Total Sulphide, Industrial Wastewater		
Parameters	Parameters Units MDL		MDL
Total Sulphide		mg/L	0.5

- E8.12 Item 73, Organochlorine Pesticides in Industrial Wastewater shall:
 - (a) consist of approximately one (1) sample annually;
 - (b) have tests performed to include the following parameter:

Item 73	Organochlorine Pesticides, Industrial Wastewater		
Parameters		Units	MDL
Aldrin/Dieldri	n	mg/L	0.0001
Chlordane (cis plus trans isomers) mg/L		mg/L	0.01
DDT		mg/L	0.00005
Hexachlorocyclo-hexane (Lindane)		mg/L	0.05
Mirex		mg/L	0.05
Hexachlorob	enzene	mg/L	0.00005

E8.13 Item 74, Total Polychlorinated Biphenols (PCBs) in Industrial Wastewater shall:

- (a) consist of approximately one (1) sample annually;
- (b) have tests performed to include the following parameter:

Item 74	Total Polychlorinated Biphenols (PCBs), Industrial Wastewater		
Parameters Units MI		MDL	
Total Polychlorinated biphenols (PCBs)		mg/L	0.0005

- E8.14 Item 75, Volatile Organic Compounds in Industrial Wastewater shall:
 - (a) consist of approximately one (1) sample annually;
 - (b) have tests performed to include the following parameter:

Item 75	Volatile Organic Compounds, Industrial Wastewater		
Parameters		Units	MDL
Benzene		mg/L	0.01
1,1,2,2 Tetra	chloroethane	mg/L	0.7
1,2-dichlorob	enzene	mg/L	0.01
1,4-dichlorobenzene		mg/L	0.01
Cis-1,2-dichloroethylene		mg/L	1.0
Ethyl benzene		mg/L	0.01
Methylene chloride		mg/L	1.0
Tetrachloro-e	Tetrachloro-ethylene		0.5
Toluene		mg/L	0.01
Trichloroethy	lene	mg/L	0.1
Total Xylene	5	mg/L	0.5

- E8.15 Item 76, 3,3-Dichlorobenzidine in Industrial Wastewater shall:
 - (a) consist of approximately one (1) sample annually;
 - (b) have tests performed to include the following parameter:

Item 76	3,3-Dichlorobenzidine, Industrial Wastewater		
Parameters Units MDL		MDL	
3,3-Dichlorob	penzidine	mg/L	0.001

E8.16 Item 77, Pentachlorophenol (PCP) in Industrial Wastewater shall:

- (a) consist of approximately one (1) sample annually;
- (b) have tests performed to include the following parameter:

Item 77	Pentachlorophenol (PCP) in Industrial Wastewater		
Parameters Units MDL		MDL	
Pentachlorop	henol (PCP)	mg/L	0.005

- E8.17 Item 78, Total Polycyclic Aromatic Hydrocarbons (PAHs) in Industrial Wastewater shall:
 - (a) consist of approximately one (1) sample annually;
 - (b) have tests performed to include the total of the following parameters: acenaphthene, acenaphtylene, anthracene, benzo(a)anthracene, benzo(a)pyrene, benzo(b)fluoranthene, benzo(g,h,i)perylene, benzo(k)fluoranthene, chrysene, dibenzo(a,h)anthracene, fluoranthene, fluorene, indeno(1,2,3-cd)pyrene, 1-methylnaphthalene,2-methylnapthalene, naphthalene, phenanthrene, and pyrene.
 - (c) Report the parameters in E8.17(b) as the following;

Item 78	Total Polycyclic Aromatic Hydrocarbons (PAHs) in Industrial Wastewater	
Parameters Units MD		MDL
Total Polycyclic Aromatic Hydrocarbons (PAHs) mg/L		0.001

- E8.18 Item 79, Nonylphenol and Nonylphenol Ethoxylates in Industrial Wastewater shall:
 - (a) consist of approximately one (1) sample annually;
 - (b) have tests performed to include the following parameter:

Item 79	Nonylphenol and Nonylphenol Ethoxylates in Industrial Wastewater		
Parameters Units MDL		MDL	
Nonylphenol		mg/L	0.01
Nonylphen	Nonylphenol Ethoxylates mg/L 0.1		0.1

- E8.19 Item 80, Total Phenolics (4AAP) in Industrial Wastewater shall:
 - (a) consist of approximately one (1) sample annually;
 - (b) have tests performed to include the following parameter:

Item 80	Total Phenolics (4AAP), Industrial Wastewater		
Parameters Units MDL		MDL	
Total Phenolics (4AAP)		mg/L	0.5

- E8.20 Item 81, Total Oil and Grease in Industrial Wastewater shall:
 - (a) consist of approximately one (1) sample annually;
 - (b) have tests performed to include the following parameter:

Item 81	Total Oil and Grease, Industrial Wastewater		
Parameters Units MDL			MDL
Animal or Vegetable		mg/L	5.0
Mineral or Synthetic		mg/L	5.0
Total Oil and	l Grease	mg/L	5.0

- E8.21 Item 82, Hydrocarbons in Industrial Wastewater shall:
 - (a) consist of approximately one (1) sample annually;
 - (b) have tests performed to include the following parameter:

Item 82	Hydrocarbons, Industrial Wastewater		
Parameters Units MDL		MDL	
Total Purgeable Hydrocarbons, C6-C10 mg/L 1.		1.0	
Total Extract	able Hydrocarbons (TEH), C11-C30+	mg/L	1.0

Or

Item 82	Hydrocarbons, Industrial Wastewater		
Parameters		Units	MDL
BTEX		mg/L	1.0
F1-F4		mg/L	1.0

- E8.22 Item 83, Schedule B Testing Complete shall:
 - (a) consist of a complete set of tests to include items 62 to 82;
 - (b) consist of approximately one hundred (100) sample annually.
- E8.23 Item 84, Escherichia Coliform (E. Coli) in Land Drainage shall:
 - (a) consist of approximately one (1) sample annually;
 - (b) the range or "pre-defined endpoint" shall be around twenty four hundred and nineteen (2419), and reported as "greater than" >2,419;
 - (c) have tests performed to include the following parameter;:

Item 84	ESCHERICIA COLIFORM IN WASTEWATER		
Parameters	Units MDL		
Escherichia Coliform by Quanti-Tray 97 to (pre-			
defined) end	point	MPN/100 mL	<1

- E8.24 Item 85, Ammonia in Land Drainage shall:
 - (a) consist of approximately one (1) sample annually;
 - (b) have tests performed to include the following parameter:

Item 85	Ammonia by colour, Land Drainage Wastewater		
Parameters Units MDL		MDL	
Ammonia, Total (as N)		mg/L	0.01
Ammonia, ur	n-ionized	mg/L	0.01

- E8.25 Item 86, Biochemical Oxygen Demand in Land Drainage shall:
 - (a) consist of approximately one (1) sample annually;
 - (b) have tests performed to include the following parameter:

Item 86	Biochemical Oxygen Demand, Land Drainage Wastewater		
Parameters Units MDL		MDL	
Biochemical	Oxygen Demand	mg/L	3

- E8.26 Item 87, Chromium, Hexavalent in Land Drainage shall:
 - (a) consist of approximately one (1) sample annually;
 - (b) have tests performed to include the following parameter:

Item 87 Chromium, Hexavalent, Land Drainage Wastewater

Parameters	Units	MDL
Chromium, Hexavalent	mg/L	0.005

E8.27 Item 88, Cyanide, Weak Acid Dissociable in Land Drainage shall:

- (a) consist of approximately one (1) sample annually;
- (b) have tests performed to include the following parameter:

Item 88	Cyanide, Weak Acid Dissociable, Land Drainage Wastewater	
Parameters Units M		MDL
Cyanide, Weak Acid Diss mg/L 0.0		0.002

E8.28 Item 89, Extractables in Land Drainage shall:

- (a) consist of approximately one (1) sample annually;
- (b) have tests performed to include the following parameter:

Item 89	n 89 Extractables, Land Drainage Wastewater		
Parameters		Units	MDL
1,2-Dichloro	benzene	mg/L	0.002
1,4-Dichloro	benzene	mg/L	0.003
3,3'-Dichlorobenzidine		mg/L	0.0004
Di-n-butylph	thalate	mg/L	0.008
Bis(2-ethylh	exyl)phthalate	mg/L	0.004
Hexachlorobenzene		mg/L	0.00002
Pentachloro	phenol	mg/L	0.001

- E8.29 Item 90, Total Mercury in Land Drainage shall:
 - (a) consist of approximately one (1) sample annually;
 - (b) have tests performed to include the following parameter:

Item 90	Mercury Total, Land Drainage Wastewater		
Parameters Units MDL		MDL	
Mercury (Hg)	-Total	mg/L	0.0002

- E8.30 Item 91, Nonylphenols and Ethoxylates in Land Drainage shall:
 - (a) consist of approximately one (1) sample annually;
 - (b) have tests performed to include the following parameter:

Item 91	Nonylphenols and Ethoxylates, Land Drainage Wastewater		
Parameters Units MDL		MDL	
Nonylphenol		mg/L	0.0005
Total Nonylp	Total Nonylphenol Ethoxylates mg/L 0.005		0.005

- E8.31 Item 92, Pesticides in Land Drainage shall:
 - (a) consist of approximately one (1) sample annually;
 - (b) have tests performed to include the following parameter:

Item 92 Pesticides, OC, Low Level, Land Drainage Wastewater

Parameters	Units	MDL
Aldrin + Dieldrin	mg/L	0.00005
a-Chlordane (cis plus trans isomers)	mg/L	0.02
DDT	mg/L	0.00002
Hexachlorocyclohexane (Lindane)	mg/L	0.01
Mirex	mg/L	0.01

- E8.32 Item 93, Phenols in Land Drainage shall:
 - (a) consist of approximately one (1) sample annually;
 - (b) have tests performed to include the following parameter:

Item 93	Phenols (4AAP), Land Drainage Wastewater		
Parameters Units MDL		MDL	
Phenols (4A	AP)	mg/L	0.001

- E8.33 Item 94, Phosphorus in Land Drainage shall:
 - (a) consist of approximately one (1) sample annually;
 - (b) have tests performed to include the following parameter:

Item 94	Phosphorus, Total, Land Drainage Wastewater		
Parameters	Parameters Units MDL		MDL
Phosphorus	(P)-Total	mg/L	0.01

- E8.34 Item 95; Total Polycyclic Aromatic Hydrocarbons (PAHs) in Land Drainage shall:
 - (a) consist of approximately one (1) sample annually;
 - (b) have tests performed to include the total of the following parameters: acenaphthene, acenaphtylene, anthracene, benzo(a)anthracene, benzo(a)pyrene, benzo(b)fluoranthene, benzo(g,h,i)perylene, benzo(k)fluoranthene, chrysene, dibenzo(a,h)anthracene, fluoranthene, fluorene, indeno(1,2,3-cd)pyrene, 1-methylnaphthalene,2-methylnapthalene, naphthalene, phenanthrene, and pyrene.
 - (c) Report the parameters listed in E8.36(b) as;

Item 95	Total Polycyclic Aromatic Hydrocarbons (PAHs) in Land Drainage Wastewater		
Parameters	Parameters Units MD		MDL
Total Polycyclic Aromatic Hydrocarbons (PAHs)		mg/L	0.001

- E8.35 Item 96, Total Metals in Land Drainage shall:
 - (a) consist of approximately one (1) sample annually;
 - (b) have tests performed to include the following parameter:

ltem 96	tem 96 Total Metals, Land Drainage Wastewater		
Parameters Units		MDL	
Arsenic (As)-Total		mg/L	0.01
Cadmium (Cd)-Total		mg/L	0.004
Chromium (Cr)-Total		mg/L	0.01
Copper (Cu	J)-Total	mg/L	0.02
Lead (Pb)-Total		mg/L	0.04
Manganes	e (Mn)-Total	mg/L	0.1
Nickel (Ni)	Total	mg/L	0.04

Selenium (Se)-Total	mg/L	0.01
Silver (Ag)-Total	mg/L	0.02
Zinc (Zn)-Total	mg/L	0.02

E8.36 Item 97, Total Polychlorinated Biphenyls in Land Drainage shall:

- (a) consist of approximately one (1) sample annually;
- (b) have tests performed to include the following parameter:

ltem 97	Total Polychlorinated Biphenyls (PCBs), Land Drainage Wastewater		
Parameters		Units	MDL
Total Polychlorinated Biphenyls		mg/L	0.0002

- E8.37 Item 98, Total Suspended Solids in Land Drainage shall:
 - (a) consist of approximately one (1) sample annually;
 - (b) have tests performed to include the following parameter:

Item 98	Total Suspended Solids, Land Drainage Wastewater		
Parameters	Parameters Units MDL		
Total Suspen	ded Solids	mg/L	4

- E8.38 Item 99, VOC in Land Drainage shall:
 - (a) consist of approximately one (1) sample annually;
 - (b) have tests performed to include the following parameter:

ltem 99	VOC, Land Drainage Wastewater		
Parameters		Units	MDL
Benzene		mg/L	0.001
cis-1,2-Dichl	oroethene	mg/L	0.002
trans-1,3-Dichloropropene		mg/L	0.002
Ethylbenzene		mg/L	0.001
Methylene Chloride		mg/L	0.002
1,1,2,2-Tetrachloroethane		mg/L	0.005
Tetrachloroethene		mg/L	0.002
Toluene		mg/L	0.001
Trichloroethe	ene	mg/L	0.004
Xylenes (tota	al)	mg/L	0.002

- E8.39 Item 100, Total Oil and Grease in Land Drainage Wastewater shall:
 - (a) consist of approximately one (1) sample annually;
 - (b) have tests performed to include the following parameter:

Item 100	Total Oil and Grease, Land Drainage Wastewater		
Parameters Units MD		MDL	
Animal or Vegetable		mg/L	5.0
Mineral or Synthetic		mg/L	5.0
Total Oil and	Grease	mg/L	5.0

E8.40 Item 101, Hydrocarbons in Land Drainage Wastewater shall:

- (a) consist of approximately one (1) sample annually;
- (b) have tests performed to include the following parameter:

Item 101	Hydrocarbons, Land Drainage Wastewater		
Parameters Units MDL			
Total Purgeable Hydrocarbons, C6-C10		mg/L	1.0
Total Extrac	table Hydrocarbons (TEH), C11-C30+	mg/L	1.0

Or

Item 101	Hydrocarbons, Land Drainage Wastewater		
Parameters Units MDL		MDL	
BTEX		mg/L	1.0
F1-F4 mg/L 1.0		1.0	

- E8.41 Item 102, Schedule D Testing Complete shall:
 - (a) consist of a complete set of tests to include items 84 to 101;
 - (b) consist of approximately ten (10) sample annually.
- E8.42 Item 103, Carbon Oxygen Demand in Industrial Wastewater shall:
 - (a) consist of approximately one (1) sample annually;
 - (b) have tests performed to include the following parameter:

Item 103	Carbon Oxygen Demand (COD), Industrial Wastewater		
Parameters	ters Units MDL		
COD		mg/L	20.0

E8.43 Item 104, Surcharge fee for rush analysis shall:

(a) consist of the unit cost for rush analysis of any sample tested under items E8.

E9. SECTION G (WATER AND SOILS, FROM LANDFILLS)

LANDFILL WATER

- E9.1 Item 105, Total Cyanide in landfill water shall:
 - (a) consist of approximately ninety six (96) samples annually;
 - (b) consist of samples from surface water, ground water and leachate locations
 - (c) part of Section 1, Section 2, Section 3
 - (d) have tests performed to include the following parameters:

Item 105	5 Total Cyanide, Landfill Water		
Parameters Units MDL		MDL	
Total Cyanide	9	mg/L	0.005

- E9.2 Item 106, Microbiological parameters in landfill water shall:
 - (a) consist of approximately two hundred and five (205) samples annually;
 - (b) consist of samples from ground water, surface water, and leachate locations
 - (c) part of section 1, section 2, section 3, section 4, section 5, and section 6
 - (d) have tests performed to include the following parameters:

Item 106	Microbiological Parameters, Landfill Water		
Parameters Units MDL		MDL	
E. Coli		MPN/100 mL	0
Fecal Coliform		MPN/100 mL	0
Total coliform	าร	MPN/100 mL	0

E9.3 Item 107, Anions in landfill water shall:

- (a) consist of approximately two hundred and five (205) samples annually;
- (b) consist of samples from Ground water, surface water, and leachate locations
- (c) part of section 1, section 2, section 3, section 4, section 5, and section 6
- (d) have tests performed to include the following parameters:

Item 107	Anions, Landfill Water		
Parameters		Units	MDL
Chloride		mg/L	2
Sulfate		mg/L	5

E9.4 Item 108, Anions and Nutrients in landfill water shall:

- (a) consist of approximately one hundred and twenty (120) samples annually;
- (b) consist of samples from Ground water, surface water, and leachate locations
- (c) part of section 1, section 2, and section 3
- (d) have tests performed to include the following parameters;

Item 108	Anions, Landfill Water		
Parameters		Units	MDL
Alkalinity, Total (as CaCO3)		mg/L	20
Ammonia, Total (as N)		mg/L	0.01
Bicarbonate (H	ICO3)	mg/L	24
Carbonate (CO3)		mg/L	12
Hydroxide (OH)	mg/L	6.8

- E9.5 Item 109, Organic/Inorganic Carbon in landfill water shall:
 - (a) consist of approximately one hundred and twenty (120) samples annually;
 - (b) consist of samples from Ground water, surface water, and leachate locations
 - (c) part of section 1, section 2, and section 3
 - (d) have tests performed to include the following parameters:

Item 109	Organic/Inorganic Carbon, Landfill Water		
Parameters Units MDL			
Dissolved Inorganic Carbon		mg/L	1
Dissolved Organic Carbon		mg/L	1
Total Dissolv	ed Carbon	mg/L	1

E9.6 Item 110, Dissolved Metals in landfill water shall:

- (a) consist of approximately one hundred and twenty (120) samples annually;
- (b) consist of samples from Ground water, surface water, and leachate locations
- (c) part of section 1, section 2, and section 3

Item 110 Dissolved Me	tals, Landfill Water	
Parameters	Units	MDL
Aluminum Dissolved	mg/L	0.002
Antimony Dissolved	mg/L	0.002
Arsenic Dissolved	mg/L	0.002
Barium Dissolved	mg/L	0.002
Beryllium Dissolved	mg/L	0.002
Bismuth Dissolved	mg/L	0.002
Boron Dissolved	mg/L	0.002
Cadmium Dissolved	mg/L	0.00001
Calcium Dissolved	mg/L	0.05
Cesium Dissolved	mg/L	0.0001
Chromium Dissolved	mg/L	0.002
Cobalt Dissolved	mg/L	0.0002
Copper Dissolved	mg/L	0.0002
Iron Dissolved	mg/L	0.1
Lead Dissolved	mg/L	0.00009
Lithium Dissolved	mg/L	0.002
Magnesium Dissolved	mg/L	0.01
Manganese Dissolved	mg/L	0.0001
Molybdenum Dissolved	mg/L	0.0001
Nickel Dissolved	mg/L	0.001
Phosphorus Dissolved	mg/L	0.03
Potassium Dissolved	mg/L	0.02
Rubidium Dissolved	mg/L	0.0002
Selenium Dissolved	mg/L	0.001
Silicon Dissolved	mg/L	0.05
Silver Dissolved	mg/L	0.0001
Sodium Dissolved	mg/L	0.02
Strontium Dissolved	mg/L	0.0001
Tellurium Dissolved	mg/L	0.0002
Thorium Dissolved	mg/L	0.0001
Tin Dissolved	mg/L	0.0002
Titanium Dissolved	mg/L	0.0002
Tungsten Dissolved	mg/L	0.0002
Uranium Dissolved	mg/L	0.0001
Vanadium Dissolved	mg/L	0.0002
Zinc Dissolved	mg/L	0.002
Zirconium Dissolved	mg/L	0.0004

(d) have tests performed to include the following parameters:

E9.7 Item 111, Dissolved Mercury in landfill water shall:

- (a) consist of approximately fifty eight (58) samples annually;
- (b) consist of samples from Ground water and leachate locations
- (c) part of section 1, and section 3
- (d) have tests performed to include the following parameters:

Item 111	Dissolved Mercury, Landfill Water		
Parameters Units		MDL	

Dissolved Mercury	ma/l	0.00005
	mg/L	0.00005

- E9.8 Item 112, Speciated Metals in landfill water shall:
 - (a) consist of approximately two hundred and five (205) samples annually;
 - (b) consist of samples from Ground water, surface water, and leachate locations
 - (c) part of section 1, section 2, section 3, section 4, section5, section 6
 - (d) have tests performed to include the following parameters:

Item 112	em 112 Speciated Metal, Landfill Water		
Parameters Units MDL		MDL	
Hexavalent Chromium		mg/L	0.01

- E9.9 Item 113, Specific OC Pesticide in landfill water shall:
 - (a) consist of approximately thirty nine (39) samples annually;
 - (b) consist of samples from a ground water locations
 - (c) part of section 2
 - (d) have tests performed to include the following parameters:

Item 113	Specific OC Pesticide, Landfill Water		
Parameters	Parameters Units MDL		
Diazinion		µg/L	2

- E9.10 Item 114, Phenoxy Acid Herbicides in landfill water shall:
 - (a) consist of approximately fifty one (51) samples annually;
 - (b) consist of samples from Ground water and leachate locations
 - (c) part of section 2, and section 3
 - (d) have tests performed to include the following parameters:

Item 114	tem 114 Phenoxy Acid Herbicides, Landfill Water		
Parameters		Units	MDL
Dicamba		µg/L	1
Picloram		µg/L	5
MCPB		µg/L	2
2, 4 D (BEE)		µg/L	2
MCPP		µg/L	2
MCPA		µg/L	2
2,4 D		µg/L	1
2, 4, 5 TP		µg/L	1
2, 4, 5 T		µg/L	1
2, 4 DB		µg/L	1

- E9.11 Item 115, Total Mercury in landfill water shall:
 - (a) consist of approximately seventy four (74) samples annually;
 - (b) consist of samples from ground water, and leachate locations
 - (c) part of section 2, and section 3
 - (d) have tests performed to include the following parameters:

Item 115 Total Mercury, Landfill Water			
Parameters Units MDL		MDL	
Total Mercury	у	mg/L	0.00005

- E9.12 Item 116, Phenol in landfill water shall:
 - (a) consist of approximately one hundred and thirty six (136) samples annually;
 - (b) consist of samples from ground water, surface water and leachate locations
 - (c) part of section 2, section 3, section 4, section 5, and section 6
 - (d) have tests performed to include the following parameters:

Item 116	Phenol (4AAP), Landfill Water		
Parameters Units MDL		MDL	
Phenol		mg/L	0.001

- E9.13 Item 117, Petroleum Hydrocarbons in landfill water shall:
 - (a) consist of approximately one hundred and twenty one (121) samples annually;
 - (b) consist of samples from ground water, surface water and leachate locations
 - (c) part of section 2, section 3, section 4, section 5, and section 6
 - (d) have tests performed to include the following parameters:

Item 117	Item 117 Hydrocarbon Scan, Landfill Water		
Parameters	Parameters Units MDL		
BTEX		µg/L	100
F1 (C6-C10)		µg/L	100
F2 (C10-C16)	µg/L	100
F3 (C16-C34)	µg/L	100
F4 (C34-C50)	µg/L	100
F4G (Grav. H	leavy Hydrocarbons)	μg/L	800

- E9.14 Item 118, Volatile Organic Compounds in landfill water shall:
 - (a) consist of approximately one hundred and thirty six (136) samples annually;
 - (b) consist of samples from ground water, surface water and leachate locations
 - (c) part of section 2, section 3, section 4, section 5, and section 6
 - (d) have tests performed to include the following parameters:

Item 118	Item 118 Volatile Organic Compounds, Landfill Water		
Parameters	;	Units	MDL
1,1,1,2-Tetra	achloroethane	µg/L	0.5
1,1,1-Trichlo	proethane	µg/L	0.5
1,1,2,2-Tetra	achloroethane	µg/L	0.5
1,1,2-Trichlo	proethane	µg/L	0.5
1,1-Dichloro	ethane	µg/L	0.5
1,1-Dichloro	ethylene	µg/L	0.5
1,2-Dichloro	benzene	µg/L	0.5
1,2-Dichloro	ethane	µg/L	0.5
1,2-Dichloro	propane	µg/L	0.5
1,3-Dichloro	benzene	µg/L	0.5
1,4-Dichloro	benzene	µg/L	0.5

2-Hexanone	µg/L	20
	μg/L	20
Acetone		0.5
Benzene	μg/L	0.5
Bromodichloromethane	μg/L	
Bromoform	µg/L	0.5
Bromomethane	μg/L	1
Carbon Disulfide	µg/L	0.5
Carbon tetrachloride	µg/L	0.5
Chlorobenzene	µg/L	0.5
Dibromochloromethane	µg/L	0.5
Chloroethane	µg/L	1
Chloroform	µg/L	0.5
Chloromethane	μg/L	1
cis-1,2-Dichloroethylene	μg/L	0.5
cis-1,3-Dichloropropene	µg/L	0.5
Dichlorodifluoromethane	µg/L	1
Ethyl Benzene	μg/L	0.5
1,2-Dibromoethane	µg/L	0.5
m+p-Xylenes	µg/L	1
Methyl Ethyl Ketone	μg/L	20
Methyl Isobutyl Ketone	μg/L	20
MTBE	μg/L	0.5
Dichloromethane	µg/L	0.5
o-Xylene	µg/L	0.5
Styrene	µg/L	0.5
Tetrachloroethylene	µg/L	0.5
Trihalomethanes (total)	µg/L	2
Toluene	µg/L	0.5
trans-1,2-Dichloroethylene	µg/L	0.5
trans-1,3-Dichloropropene	µg/L	0.5
Trichloroethylene	µg/L	0.5
Trichlorofluoromethane	µg/L	1
Vinyl chloride	µg/L	0.5
Xylenes (Total)	µg/L	1.5

- E9.15 Item 119, Polycyclic Aromatic Hydrocarbons in landfill water shall:
 - (a) consist of approximately fifty one (51) samples annually;
 - (b) consist of samples from ground water, and leachate locations
 - (c) part of section 2, and section 3
 - (d) have tests performed to include the following parameters:

Item 119	Polycyclic Aromatic Hydrocarbons, Landfill Water		
Parameters		Units	MDL
1-Methyl Nap	ohthalene	mg/L	0.00002
2-Methyl Nap	ohthalene	mg/L	0.00002
Acenaphther	ne	mg/L	0.00002
Acenaphthyle	ene	mg/L	0.00002
Acridine		mg/L	0.00002
Anthracene		mg/L	0.00001
B(a)P Total F	Potency Equivalent	mg/L	0.00003

Benzo(a)anthracene	mg/L	0.00001
Benzo(a)pyrene	mg/L	0.000005
Benzo(b&j)fluoranthene	mg/L	0.00001
Benzo(g,h,i)perylene	mg/L	0.00002
Benzo(k)fluoranthene	mg/L	0.00001
Chrysene	mg/L	0.00002
Dibenzo(a,h)anthracene	mg/L	0.000005
Fluoranthene	mg/L	0.00002
Fluorene	mg/L	0.00002
Indeno(1,2,3-cd)pyrene	mg/L	0.00001
Naphthalene	mg/L	0.00005
Phenanthrene	mg/L	0.00005
Pyrene	mg/L	0.00001
Quinoline	mg/L	0.00002

E9.16 Item 120, Total Metals in landfill water shall:

- (a) consist of approximately twelve (12) samples annually;
- (b) consist of samples from ground water, and leachate locations
- (c) part of section 3
- (d) have tests performed to include the following parameters:

Item 120 Total Metals, Landfill Water		
Parameters	Units	MDL
Aluminum	mg/L	0.005
Antimony	mg/L	0.0005
Arsenic	mg/L	0.001
Barium	mg/L	0.005
Beryllium	mg/L	0.0005
Bismuth	mg/L	0.001
Boron	mg/L	0.01
Cadmium	mg/L	0.0001
Calcium	mg/L	0.2
Chromium	mg/L	0.005
Cobalt	mg/L	0.0005
Copper	mg/L	0.001
Iron	mg/L	0.1
Lead	mg/L	0.0005
Lithium	mg/L	0.005
Magnesium	mg/L	0.05
Manganese	mg/L	0.002
Molybdenum	mg/L	0.001
Nickel	mg/L	0.001
Phosphorus	mg/L	0.1
Potassium	mg/L	0.2
Rubidium	mg/L	0.0002
Selenium	mg/L	0.2
Silicon	mg/L	0.05
Silver	mg/L	0.0001
Sodium	mg/L	0.1
Strontium	mg/L	0.001

Tellurium	mg/L	0.001
Thorium	mg/L	0.001
Tin	mg/L	0.001
Titanium	mg/L	0.005
Tungsten	mg/L	0.001
Uranium	mg/L	0.0001
Vanadium	mg/L	0.001
Zinc	mg/L	0.005
Zirconium	mg/L	0.001

E9.17 Item 121, Oil and Grease in landfill water shall:

- (a) consist of approximately twelve (12) samples annually;
- (b) consist of samples from a leachate locations
- (c) part of section 3
- (d) have tests performed to include the following parameters:

Item 121	21 Oil and Grease, Landfill Water		
Parameters Units MDL			MDL
Oil and Grea	se	mg/L	5

- E9.18 Item 122, Specific Polycyclic Aromatic Hydrocarbons in landfill water shall:
 - (a) consist of approximately twelve (12) samples annually;
 - (b) consist of samples from a leachate locations
 - (c) part of section 3
 - (d) have tests performed to include the following parameters:

Item 122	Polycyclic Aromatic Hydrocarbons, Landfill Water		
Parameters		Units	MDL
3,3'- Dichloro	benzidine	mg/L	0.0008
4,4' – Methyl	enebis (2 – chloroaniline)	mg/L	0.0005
Dinitropyrene	9	mg/L	0.002
Perylene		mg/L	0.0008

- E9.19 Item 123, OC/OP Pesticides and PCB in landfill water shall:
 - (a) consist of approximately twelve (12) samples annually;
 - (b) consist of samples from a leachate locations
 - (c) part of section 3
 - (d) have tests performed to include the following parameters:

Item 123	OC/OP Pesticides (Selected) & PCB, Landfill Water			
Parameters	Parameters Units MDL			
Hexachloroe	thane	µg/L	0.01	
Hexachlorob	utadiene	µg/L	0.009	
Hexachloroc	yclopentadiene	µg/L	0.02	
Aldrin + Diel	drin	µg/L	0.005	
Aldrin		µg/L	0.005	
A – BHC		µg/L	0.005	
B - BHC		µg/L	0.005	

B = Chiordane $\mu g/L$ 0.005 G = Chiordane $\mu g/L$ 0.005 Chiordane (total) $\mu g/L$ 0.005 O, p DDD $\mu g/L$ 0.005 P,p DDD $\mu g/L$ 0.005 O, p DDD + p,p DDD $\mu g/L$ 0.005 O, p DDE $\mu g/L$ 0.005 P,p DDE $\mu g/L$ 0.005 O, p DD $\mu g/L$ 0.005 O, p DD $\mu g/L$ 0.005 O,p DDT $\mu g/L$ 0.005 O,p DT $\mu g/L$ 0.005 O,p DT + p,p DDT $\mu g/L$ 0.005 DDT + Metabolites $\mu g/L$ 0.005 Endosulfan I $\mu g/L$ 0.005 Endosulfan I $\mu g/L$ 0.005 Endrin $\mu g/L$ 0.005 Endrin Aldehyde $\mu g/L$ 0.005 Endrin Netone $\mu g/L$ 0.005 Endrin Netone $\mu g/L$ 0.005 Heptachlor Epoxide $\mu g/L$ 0.005 <	G – BHC	µg/L	0.005
G - Chlordane $\mu g/L$ 0.005 Chlordane (total) $\mu g/L$ 0.005 O, p DDD $\mu g/L$ 0.005 O, p DDD $\mu g/L$ 0.005 O, p DDD $\mu g/L$ 0.005 O, p DD + p, p DDD $\mu g/L$ 0.005 O, p DDE $\mu g/L$ 0.005 O, p DDE $\mu g/L$ 0.005 O, p DDT $\mu g/L$ 0.005 O, p DDT $\mu g/L$ 0.005 O, p DT $\mu g/L$ 0.005 O, p DT + p, p DT $\mu g/L$ 0.005 DDT + Metabolites $\mu g/L$ 0.005 Endosulfan I $\mu g/L$ 0.005 Endosulfan I $\mu g/L$ 0.005 Endrin Aldehyde $\mu g/L$ 0.005 Endrin Aldehyde $\mu g/L$ 0.005 Heptachlor $\mu g/L$ 0.005 Heptachlor $\mu g/L$ 0.005 Heptachlor $\mu g/L$ 0.005 Heptachlor $\mu g/L$ 0.005 <t< td=""><td></td><td></td><td></td></t<>			
Chlordane (total) $\mu g/L$ 0.005 O, p DDD $\mu g/L$ 0.005 P, p DDD $\mu g/L$ 0.005 O, p DDD + p, p DDD $\mu g/L$ 0.005 O, p DDE $\mu g/L$ 0.005 P, p DDE $\mu g/L$ 0.005 O, p + p, DDE $\mu g/L$ 0.005 O, p DDT + p, p DDT $\mu g/L$ 0.005 DDT + Metabolites $\mu g/L$ 0.005 Endosulfan I $\mu g/L$ 0.005 Endosulfan I $\mu g/L$ 0.005 Endrin $\mu g/L$ 0.005 Endrin Aldehyde $\mu g/L$ 0.005 Endrin Ketone $\mu g/L$ 0.005 Heptachlor $\mu g/L$ 0.005 Heptachlor Epoxide $\mu g/L$ 0.005 Heptachlor Epoxide $\mu g/L$ 0.005 Heptachlor D16 $\mu g/$			
O, p DDD $\mu g/L$ 0.005 P,p DD $\mu g/L$ 0.005 O, p DDD + p, p DDD $\mu g/L$ 0.005 O, p DDE $\mu g/L$ 0.005 P,p DDE $\mu g/L$ 0.005 O, p DDT + p, p DDT $\mu g/L$ 0.005 DDT + Metabolites $\mu g/L$ 0.005 Endosulfan I $\mu g/L$ 0.005 Endosulfan II $\mu g/L$ 0.005 Endrin $\mu g/L$ 0.005 Endrin Aldehyde $\mu g/L$ 0.005 Endrin Aldehyde $\mu g/L$ 0.005 Heptachlor $\mu g/L$ 0.005 Heptachlor $\mu g/L$ 0.005 Heptachlor Epoxide $\mu g/L$ 0.005 Heptachlor Styrene $\mu g/L$ 0.005 Octachlorostyrene $\mu g/L$ 0.014			
P,p DDD μg/L 0.005 O,p DDD + p,p DDD μg/L 0.005 O,p DDE μg/L 0.005 P,p DDE μg/L 0.005 O,p + p,p DDE μg/L 0.005 O,p DDT μg/L 0.005 O,p DDT μg/L 0.005 O,p DDT μg/L 0.005 O,p DDT + p,p DDT μg/L 0.005 DDT + Metabolites μg/L 0.005 Dieldrin μg/L 0.005 Endosulfan I μg/L 0.005 Endosulfan II μg/L 0.005 Endrin Aldehyde μg/L 0.005 Endrin Aldehyde μg/L 0.005 Endrin Aldehyde μg/L 0.005 Heptachlor μg/L 0.005 Heptachlor μg/L 0.005 Heptachlor Epoxide μg/L 0.005 Heptachlor Depoxide μg/L 0.005 Indane μg/L 0.005 Octachlorostyrene μg/L			
O,p DDD + p,p DDD µg/L 0.005 O,p DDE µg/L 0.005 P,p DDE µg/L 0.005 O,p DT µg/L 0.005 O,p DT µg/L 0.005 P,p DDT µg/L 0.005 O,p DT + p,p DDT µg/L 0.005 DDT + hetabolites µg/L 0.005 DDT + Metabolites µg/L 0.005 Endosulfan I µg/L 0.005 Endosulfan II µg/L 0.005 Endrin Aldehyde µg/L 0.005 Endrin Aldehyde µg/L 0.005 Endrin Aldehyde µg/L 0.005 Heptachlor µg/L 0.005 Heptachlor Epoxide µg/L 0.005 Hexachlorobenzene µg/L 0.005 Lindane µg/L 0.005 Methoxychlor µg/L 0.005 Total PCB µg/L 0.005 Aroclor 1016 µg/L 0.005 Aroclor 1221 µg/L			
O,p DDE $\mu g/L$ 0.005 P,p DDE $\mu g/L$ 0.005 O,p + p,p DDE $\mu g/L$ 0.005 O,p DDT $\mu g/L$ 0.005 P,p DDT $\mu g/L$ 0.005 O,p DDT + p,p DDT $\mu g/L$ 0.005 DDT + Metabolites $\mu g/L$ 0.005 Dieldrin $\mu g/L$ 0.005 Endosulfan I $\mu g/L$ 0.005 Total Endosulfan $\mu g/L$ 0.005 Endrin Aldehyde $\mu g/L$ 0.005 Endrin Aldehyde $\mu g/L$ 0.005 Heptachlor $\mu g/L$ 0.005 Heptachlor $\mu g/L$ 0.005 Heptachlor Epoxide $\mu g/L$ 0.005 Hexachlorobenzene $\mu g/L$ 0.005 Lindane $\mu g/L$ 0.005 Nethoxychlor $\mu g/L$ 0.005 Aroclor 1016 $\mu g/L$ 0.005 Aroclor 1221 $\mu g/L$ 0.05 Aroclor 1232 $\mu g/L$ 0.05 A			
P,p DDE μg/L 0.005 O,p + p,p DDE μg/L 0.005 O,p DDT μg/L 0.005 P,p DDT μg/L 0.005 O,p DDT + p,p DDT μg/L 0.005 DDT + Metabolites μg/L 0.005 Dieldrin μg/L 0.005 Endosulfan I μg/L 0.005 Endosulfan I μg/L 0.005 Endrin Aldehyde μg/L 0.005 Endrin Aldehyde μg/L 0.005 Endrin Ketone μg/L 0.005 Heptachlor μg/L 0.005 Heptachlor Epoxide μg/L 0.005 Hexachlorobenzene μg/L 0.005 Lindane μg/L 0.005 Octachlorostyrene μg/L 0.005 Aroclor 1016 μg/L 0.005 Aroclor 1221 μg/L 0.05 Aroclor 1242 μg/L 0.05 Aroclor 1248 μg/L 0.05 Aroclor 1248 μg/L			
O,p + p,p DDE µg/L 0.005 O,p DDT µg/L 0.005 P,p DDT µg/L 0.005 O,p DDT + p,p DDT µg/L 0.005 DDT + Metabolites µg/L 0.005 Dieldrin µg/L 0.005 Endosulfan I µg/L 0.005 Endosulfan II µg/L 0.005 Endrin µg/L 0.005 Endrin Aldehyde µg/L 0.005 Endrin Ketone µg/L 0.005 Heptachlor µg/L 0.005 Heptachlor Epoxide µg/L 0.005 Hexachlorobenzene µg/L 0.005 Lindane µg/L 0.005 Octachlorostyrene µg/L 0.005 Octachlorostyrene µg/L 0.005 Aroclor 1221 µg/L 0.05 Aroclor 1232 µg/L 0.05 Aroclor 1248 µg/L 0.05 Aroclor 1248 µg/L 0.05 Aroclor 1254 µg/L			
O,p DDT µg/L 0.005 P,p DDT µg/L 0.005 O,p DDT + p,p DDT µg/L 0.005 DDT + Metabolites µg/L 0.005 Dieldrin µg/L 0.005 Endosulfan I µg/L 0.005 Endosulfan II µg/L 0.005 Total Endosulfan II µg/L 0.005 Endrin µg/L 0.005 Endrin Aldehyde µg/L 0.005 Endrin Ketone µg/L 0.005 Heptachlor µg/L 0.005 Heptachlor Epoxide µg/L 0.005 Hexachlorobenzene µg/L 0.005 Lindane µg/L 0.005 Octachlorostyrene µg/L 0.005 Octachlorostyrene µg/L 0.005 Aroclor 1016 µg/L 0.05 Aroclor 1221 µg/L 0.05 Aroclor 1242 µg/L 0.05 Aroclor 1248 µg/L 0.05 Aroclor 1254 µg/L </td <td></td> <td></td> <td></td>			
P,p DDT μg/L 0.005 O,p DDT + p,p DDT μg/L 0.005 DDT + Metabolites μg/L 0.005 Dieldrin μg/L 0.005 Endosulfan I μg/L 0.005 Endosulfan II μg/L 0.005 Total Endosulfan μg/L 0.005 Endrin μg/L 0.005 Endrin Aldehyde μg/L 0.005 Endrin Ketone μg/L 0.005 Heptachlor μg/L 0.005 Heptachlor Epoxide μg/L 0.005 Hexachlorobenzene μg/L 0.005 Lindane μg/L 0.005 Octachlorostyrene μg/L 0.005 Total PCB μg/L 0.005 Aroclor 1016 μg/L 0.05 Aroclor 1221 μg/L 0.05 Aroclor 1242 μg/L 0.05 Aroclor 1248 μg/L 0.05 Aroclor 1254 μg/L 0.05 Aroclor 1260 μg/L			
O,p DDT + p,p DDT µg/L 0.005 DDT + Metabolites µg/L 0.005 Dieldrin µg/L 0.005 Endosulfan I µg/L 0.005 Endosulfan II µg/L 0.005 Total Endosulfan µg/L 0.005 Endrin µg/L 0.005 Endrin µg/L 0.005 Endrin Aldehyde µg/L 0.005 Endrin Ketone µg/L 0.005 Heptachlor µg/L 0.005 Heptachlor Epoxide µg/L 0.005 Hexachlorobenzene µg/L 0.005 Lindane µg/L 0.005 Mirex µg/L 0.005 Octachlorostyrene µg/L 0.005 Total PCB µg/L 0.014 Aroclor 1221 µg/L 0.05 Aroclor 1232 µg/L 0.05 Aroclor 1242 µg/L 0.05 Aroclor 1248 µg/L 0.05 Aroclor 1254 µg/L <td< td=""><td></td><td></td><td></td></td<>			
DDT + Metabolites μg/L 0.005 Dieldrin μg/L 0.005 Endosulfan I μg/L 0.005 Endosulfan II μg/L 0.005 Total Endosulfan μg/L 0.005 Endrin μg/L 0.005 Endrin Aldehyde μg/L 0.005 Endrin Ketone μg/L 0.005 Heptachlor μg/L 0.005 Heptachlor Epoxide μg/L 0.005 Lindane μg/L 0.005 Methoxychlor μg/L 0.005 Octachlorostyrene μg/L 0.005 Total PCB μg/L 0.005 Aroclor 1221 μg/L 0.1 Aroclor 1232 μg/L 0.05 Aroclor 1248 μg/L 0.05 Aroclor 1254 μg/L 0.05 Aroclor 1260 μg/L 0.05			0.005
Dieldrin µg/L 0.005 Endosulfan I µg/L 0.005 Endosulfan II µg/L 0.005 Total Endosulfan µg/L 0.005 Endrin µg/L 0.005 Endrin µg/L 0.005 Endrin Aldehyde µg/L 0.005 Endrin Ketone µg/L 0.005 Heptachlor µg/L 0.005 Heptachlor Epoxide µg/L 0.005 Hexachlorobenzene µg/L 0.005 Lindane µg/L 0.005 Octachlorostyrene µg/L 0.005 Total PCB µg/L 0.005 Aroclor 1016 µg/L 0.05 Aroclor 1221 µg/L 0.1 Aroclor 1232 µg/L 0.05 Aroclor 1248 µg/L 0.05 Aroclor 1254 µg/L 0.05 Aroclor 1260 µg/L 0.05 Toxaphene µg/L 0.05			0.005
Endosulfan I μg/L 0.005 Endosulfan II μg/L 0.005 Total Endosulfan μg/L 0.005 Endrin μg/L 0.005 Endrin Aldehyde μg/L 0.005 Endrin Aldehyde μg/L 0.005 Endrin Ketone μg/L 0.005 Heptachlor μg/L 0.005 Heptachlor Epoxide μg/L 0.005 Hexachlorobenzene μg/L 0.005 Lindane μg/L 0.005 Mirex μg/L 0.005 Octachlorostyrene μg/L 0.005 Total PCB μg/L 0.014 Mirex μg/L 0.005 Octachlorostyrene μg/L 0.01 Aroclor 1016 μg/L 0.05 Aroclor 1221 μg/L 0.05 Aroclor 1242 μg/L 0.05 Aroclor 1248 μg/L 0.05 Aroclor 1254 μg/L 0.05 Aroclor 1260 μg/L <td< td=""><td>Dieldrin</td><td></td><td>0.005</td></td<>	Dieldrin		0.005
Endosulfan II μg/L 0.005 Total Endosulfan μg/L 0.005 Endrin μg/L 0.005 Endrin Aldehyde μg/L 0.005 Endrin Aldehyde μg/L 0.005 Endrin Ketone μg/L 0.005 Heptachlor μg/L 0.005 Heptachlor Epoxide μg/L 0.005 Hexachlorobenzene μg/L 0.005 Lindane μg/L 0.005 Methoxychlor μg/L 0.005 Octachlorostyrene μg/L 0.005 Total PCB μg/L 0.014 Mirex μg/L 0.005 Octachlorostyrene μg/L 0.005 Total PCB μg/L 0.01 Aroclor 121 μg/L 0.05 Aroclor 1221 μg/L 0.05 Aroclor 1242 μg/L 0.05 Aroclor 1248 μg/L 0.05 Aroclor 1254 μg/L 0.05 Aroclor 1260 μg/L	Endosulfan I		0.005
Total Endosulfan μg/L 0.005 Endrin μg/L 0.005 Endrin Aldehyde μg/L 0.005 Endrin Ketone μg/L 0.005 Heptachlor μg/L 0.005 Heptachlor Epoxide μg/L 0.005 Hexachlorobenzene μg/L 0.005 Lindane μg/L 0.005 Mirex μg/L 0.005 Octachlorostyrene μg/L 0.005 Total PCB μg/L 0.005 Aroclor 1221 μg/L 0.05 Aroclor 1232 μg/L 0.05 Aroclor 1248 μg/L 0.05 Aroclor 1248 μg/L 0.05 Aroclor 1254 μg/L 0.05 Aroclor 1260 μg/L 0.05 Aroclor 1260 μg/L 0.05	Endosulfan II		0.005
Endrin μg/L 0.005 Endrin Aldehyde μg/L 0.005 Endrin Ketone μg/L 0.005 Heptachlor μg/L 0.005 Heptachlor Epoxide μg/L 0.005 Heptachlor benzene μg/L 0.005 Lindane μg/L 0.005 Mirex μg/L 0.005 Octachlorostyrene μg/L 0.005 Total PCB μg/L 0.014 Aroclor 1221 μg/L 0.01 Aroclor 1232 μg/L 0.05 Aroclor 1248 μg/L 0.05 Aroclor 1254 μg/L 0.05 Aroclor 1260 μg/L 0.05 Aroclor 1260 μg/L 0.05	Total Endosulfan		0.005
Endrin Ketone μg/L 0.005 Heptachlor μg/L 0.005 Heptachlor Epoxide μg/L 0.005 Hexachlorobenzene μg/L 0.005 Lindane μg/L 0.003 Methoxychlor μg/L 0.005 Octachlorostyrene μg/L 0.005 Total PCB μg/L 0.005 Aroclor 1016 μg/L 0.01 Aroclor 1221 μg/L 0.05 Aroclor 1242 μg/L 0.05 Aroclor 1242 μg/L 0.05 Aroclor 1248 μg/L 0.05 Aroclor 1254 μg/L 0.05 Aroclor 1260 μg/L 0.05 Aroclor 1260 μg/L 0.05	Endrin		0.005
Heptachlor μg/L 0.005 Heptachlor Epoxide μg/L 0.005 Hexachlorobenzene μg/L 0.005 Lindane μg/L 0.003 Methoxychlor μg/L 0.014 Mirex μg/L 0.005 Octachlorostyrene μg/L 0.005 Total PCB μg/L 0.01 Aroclor 1016 μg/L 0.05 Aroclor 1221 μg/L 0.1 Aroclor 1232 μg/L 0.05 Aroclor 1242 μg/L 0.05 Aroclor 1248 μg/L 0.05 Aroclor 1254 μg/L 0.05 Aroclor 1260 μg/L 0.05 Aroclor 1260 μg/L 0.05	Endrin Aldehyde	µg/L	0.005
Heptachlor Epoxide μg/L 0.005 Hexachlorobenzene μg/L 0.005 Lindane μg/L 0.003 Methoxychlor μg/L 0.014 Mirex μg/L 0.005 Octachlorostyrene μg/L 0.005 Total PCB μg/L 0.005 Aroclor 1016 μg/L 0.05 Aroclor 1221 μg/L 0.05 Aroclor 1232 μg/L 0.05 Aroclor 1242 μg/L 0.05 Aroclor 1248 μg/L 0.05 Aroclor 1254 μg/L 0.05 Aroclor 1260 μg/L 0.05	Endrin Ketone		0.005
Hexachlorobenzene μg/L 0.005 Lindane μg/L 0.003 Methoxychlor μg/L 0.014 Mirex μg/L 0.005 Octachlorostyrene μg/L 0.005 Total PCB μg/L 0.1 Aroclor 1016 μg/L 0.05 Aroclor 1221 μg/L 0.1 Aroclor 1232 μg/L 0.1 Aroclor 1242 μg/L 0.05 Aroclor 1242 μg/L 0.05 Aroclor 1248 μg/L 0.05 Aroclor 1254 μg/L 0.05 Aroclor 1260 μg/L 0.05 Toxaphene μg/L 0.2	Heptachlor	µg/L	0.005
Lindane µg/L 0.003 Methoxychlor µg/L 0.014 Mirex µg/L 0.005 Octachlorostyrene µg/L 0.005 Total PCB µg/L 0.1 Aroclor 1016 µg/L 0.05 Aroclor 1221 µg/L 0.1 Aroclor 1232 µg/L 0.1 Aroclor 1232 µg/L 0.05 Aroclor 1242 µg/L 0.05 Aroclor 1248 µg/L 0.05 Aroclor 1254 µg/L 0.05 Aroclor 1260 µg/L 0.05 Toxaphene µg/L 0.2	Heptachlor Epoxide	µg/L	0.005
Methoxychlor μg/L 0.014 Mirex μg/L 0.005 Octachlorostyrene μg/L 0.005 Total PCB μg/L 0.1 Aroclor 1016 μg/L 0.05 Aroclor 1221 μg/L 0.1 Aroclor 1232 μg/L 0.05 Aroclor 1242 μg/L 0.05 Aroclor 1248 μg/L 0.05 Aroclor 1254 μg/L 0.05 Aroclor 1260 μg/L 0.05 Toxaphene μg/L 0.2	Hexachlorobenzene	µg/L	0.005
Mirex μg/L 0.005 Octachlorostyrene μg/L 0.005 Total PCB μg/L 0.1 Aroclor 1016 μg/L 0.05 Aroclor 1221 μg/L 0.1 Aroclor 1232 μg/L 0.1 Aroclor 1242 μg/L 0.05 Aroclor 1242 μg/L 0.05 Aroclor 1248 μg/L 0.05 Aroclor 1254 μg/L 0.05 Aroclor 1260 μg/L 0.05 Toxaphene μg/L 0.2	Lindane	μg/L	0.003
Octachlorostyrene µg/L 0.005 Total PCB µg/L 0.1 Aroclor 1016 µg/L 0.05 Aroclor 1221 µg/L 0.1 Aroclor 1232 µg/L 0.1 Aroclor 1232 µg/L 0.05 Aroclor 1242 µg/L 0.05 Aroclor 1248 µg/L 0.05 Aroclor 1254 µg/L 0.05 Aroclor 1260 µg/L 0.05 Toxaphene µg/L 0.2	Methoxychlor	μg/L	0.014
Total PCB μg/L 0.1 Aroclor 1016 μg/L 0.05 Aroclor 1221 μg/L 0.1 Aroclor 1232 μg/L 0.1 Aroclor 1232 μg/L 0.05 Aroclor 1242 μg/L 0.05 Aroclor 1242 μg/L 0.05 Aroclor 1248 μg/L 0.05 Aroclor 1254 μg/L 0.05 Aroclor 1260 μg/L 0.05 Toxaphene μg/L 0.2	Mirex	μg/L	0.005
Aroclor 1016 μg/L 0.05 Aroclor 1221 μg/L 0.1 Aroclor 1232 μg/L 0.05 Aroclor 1242 μg/L 0.05 Aroclor 1242 μg/L 0.05 Aroclor 1248 μg/L 0.05 Aroclor 1254 μg/L 0.05 Aroclor 1260 μg/L 0.05 Toxaphene μg/L 0.2	Octachlorostyrene	µg/L	0.005
Aroclor 1221 μg/L 0.1 Aroclor 1232 μg/L 0.05 Aroclor 1242 μg/L 0.05 Aroclor 1248 μg/L 0.05 Aroclor 1254 μg/L 0.05 Aroclor 1260 μg/L 0.05 Toxaphene μg/L 0.2	Total PCB	μg/L	
Aroclor 1232 μg/L 0.05 Aroclor 1242 μg/L 0.05 Aroclor 1248 μg/L 0.05 Aroclor 1254 μg/L 0.05 Aroclor 1260 μg/L 0.05 Toxaphene μg/L 0.2		μg/L	0.05
Aroclor 1242 μg/L 0.05 Aroclor 1248 μg/L 0.05 Aroclor 1254 μg/L 0.05 Aroclor 1260 μg/L 0.05 Toxaphene μg/L 0.2	Aroclor 1221	µg/L	0.1
Aroclor 1248 μg/L 0.05 Aroclor 1254 μg/L 0.05 Aroclor 1260 μg/L 0.05 Toxaphene μg/L 0.2			0.05
Aroclor 1254 μg/L 0.05 Aroclor 1260 μg/L 0.05 Toxaphene μg/L 0.2	Aroclor 1242	µg/L	0.05
Aroclor 1260 μg/L 0.05 Toxaphene μg/L 0.2		μg/L	0.05
Toxaphene µg/L 0.2			
		µg/L	
Diazinion µg/L 2	•		0.2
	Diazinion	μg/L	2

E9.20 Item 124, Dioxins and Furans in landfill water shall:

- (a) consist of approximately one (1) samples annually;
- (b) consist of a sample from a leachate locations
- (c) part of section 3
- (d) have tests performed to include the following parameters:

Item 124	Dioxins and Furans, Landfill Water		
Parameters Units MDL			MDL
2,3,7,8-Tetra CDD pg/L 11.4		11.4	
1,2,3,7,8-Per	nta CDD	pg/L	11.4
1,2,3,4,7,8-H	exa CDD	pg/L	11.4

1,2,3,6,7,8-Hexa CDD	pg/L	11.4
1,2,3,7,8,9-Hexa CDD	pg/L	11.4
1,2,3,4,6,7,8-Hepta CDD	pg/L	11.4
Octa CDD	pg/L	11.4
Total Tetra CDD	pg/L	11.4
Total Penta CDD	pg/L	11.4
Total Hexa CDD	pg/L	11.4
Total Hepta CDD	pg/L	11.4
2,3,7,8-Tetra CDF	pg/L	11.4
1,2,3,7,8-Penta CDF	pg/L	11.4
2,3,4,7,8-Penta CDF	pg/L	11.4
1,2,3,4,7,8-Hexa CDF	pg/L	11.4
1,2,3,6,7,8-Hexa CDF	pg/L	11.4
2,3,4,6,7,8-Hexa CDF	pg/L	11.4
1,2,3,7,8,9-Hexa CDF	pg/L	11.4
1,2,3,4,6,7,8-Hepta CDF	pg/L	11.4
1,2,3,4,7,8,9-Hepta CDF	pg/L	11.4
Octa CDF	pg/L	11.4
Total Tetra CDF	pg/L	11.4
Total Penta CDF	pg/L	11.4
Total Hexa CDF	pg/L	11.4
Total Hepta CDF	pg/L	11.4

E9.21 Item 125, Low Level Total Mercury in landfill water shall:

- (a) consist of approximately thirty five (35) samples annually;
- (b) consist of a sample from a surface water and leachate locations
- (c) part of section 4 and section 6
- (d) have tests performed to include the following parameters:

Item 125	Total Mercury, Landfill Water		
Parameters		Units	MDL
Mercury		µg/L	0.002

- E9.22 Item 126, Low Level Dissolved Mercury in landfill water shall:
 - (a) consist of approximately fifty (50) samples annually;
 - (b) consist of a sample from ground water locations
 - (c) part of section 5
 - (d) have tests performed to include the following parameters:

Item 126	6 Dissolved Mercury, Landfill Water		
Parameters	Parameters Units MDL		MDL
Dissolved Mercury µg/L 0.002		0.002	

- E9.23 Item 127, Dissolved Organic Carbon in landfill water shall:
 - (a) consist of approximately ten (10) samples annually;
 - (b) consist of a sample from leachate locations
 - (c) part of section 6
 - (d) have tests performed to include the following parameters:

Item 127 Organic Carbon, Landfill Water			
Parameters Units MDL			
Dissolved Or	Dissolved Organic Carbon mg/L 1		1

FABRICATED SOIL

- E9.24 Item 128, Nutrients in landfill water shall:
 - (a) consist of approximately twenty (20) samples annually;
 - (b) landfill surface water from area with fabricated soil
 - (c) part of section 7
 - (d) have tests performed to include the following parameters:

Item 128	Nutrients, Landfill Water		
Parameters		Units	MDL
Dissolved Ni	trate (NO3)	mg/L	0.044
Nitrate plus N	Nitrite (N)	mg/L	0.014
Dissolved Ni	trite (NO2)	mg/L	0.033
Dissolved Ar	nmonia (N)	mg/L	0.15
Orthophosph	ate (P)	mg/L	0.03
Total Kjeldahl Nitrogen		mg/L	1.3
Dissolved Ni	trate (NO3)	mg/L	0.044

- E9.25 Item 129, Calculated Carbon and Nitrogen parameters in landfill soil shall:
 - (a) consist of approximately six (6) samples annually;
 - (b) fabricated soil feedstock sample
 - (c) part of section 8
 - (d) have tests performed to include the following parameters:

Item 129 Calculated Parameters, Landfill Soil			
Parameters Units MDL			MDL
C:N Ratio	C:N Ratio		
Nitrogen (N) % 0.01			

- E9.26 Item 130, Anions in landfill soil shall:
 - (a) consist of approximately six (6) samples annually;
 - (b) fabricated soil feedstock sample
 - (c) part of section 8
 - (d) have tests performed to include the following parameters:

Item 130	Anions, Landfill Soil		
Parameters Units MDL			MDL
Soluble Chlo	Soluble Chloride mg/L 10		10

- E9.27 Item 131, Hexavalent Chromium in landfill soil shall:
 - (a) consist of approximately six (6) samples annually;
 - (b) fabricated soil feedstock sample
 - (c) part of section 8

(d) have tests performed to include the following parameters:

Item 131	em 131 Hexavalent Chromium, Landfill Soil		
Parameters	Parameters Units MDL		
Hexavalent Chromium mg/kg 0.08		0.08	

- E9.28 Item 132, Nutrients in landfill soil shall:
 - (a) consist of approximately twenty six (26) samples annually;
 - (b) fabricated soil feedstock and fabricated soil sample
 - (c) part of section 8, and section 9
 - (d) have tests performed to include the following parameters:

Item 132	Nutrients, Landfill Soil		
Parameters		Units	MDL
Available (KC	CL) Ammonia (N)	mg/kg	2
Available (NH	14F) Nitrogen (N)	mg/kg	10
Available (NH	14F) Phosphorus (P)	mg/kg	5
Available (NH	14OAc) Potassium (K)	mg/kg	10
Available (CaCl2) Sulphur (S)		mg/kg	20
Total Kjeldah	l Nitrogen	mg/kg	600

- E9.29 Item 133, Physical properties in landfill soil shall:
 - (a) consist of approximately six (6) samples annually;
 - (b) fabricated soil feedstock sample
 - (c) part of section 8
 - (d) have tests performed to include the following parameters:

Item 133 Physical Properties, Landfill Soil			
Parameters		Units	MDL
% sand by h	ydrometer	%	-
% silt by hyd	rometer	%	-
Clay Conten	t	%	-
Soluble (2:1)) pH	pН	-
Loss on Igni	tion	%	1
Texture		-	-
Bulk Density		kg/m³	1

- E9.30 Item 134, Soluble parameters in landfill soil shall:
 - (a) consist of approximately six (6) samples annually;
 - (b) fabricated soil feedstock sample
 - (c) part of section 8
 - (d) have tests performed to include the following parameters:

Item 134	em 134 Soluble Parameters, Landfill Soil		
Parameters Units MDL		MDL	
Soluble Calcium (Ca)		mg/L	5
Soluble Magnesium (Mg)		mg/L	5
Soluble Pota	ssium (K)	mg/L	20

Soluble Sodium (Na)	mg/L	5
Soluble Sulphur (S)	mg/L	30
Sodium Adsorption Ratio	-	0.1

E9.31 Item 135, Total metals in landfill soil shall:

- (a) consist of approximately six (6) samples annually;
- (b) fabricated soil feedstock sample
- (c) part of section 8
- (d) have tests performed to include the following parameters:

Item 135 Total Metals, Landfill Soil					
Parameters	Units	MDL			
Total Aluminum (Al)	mg/kg	100			
Total Antimony (Sb)	mg/kg	0.1			
Total Arsenic (As)	mg/kg	0.5			
Total Barium (Ba)	mg/kg	0.1			
Total Beryllium (Be)	mg/kg	0.2			
Total Bismuth (Bi)	mg/kg	0.1			
Total Cadmium (Cd)	mg/kg	0.05			
Total Calcium (Ca)	mg/kg	100			
Total Chromium (Cr)	mg/kg	1			
Total Cobalt (Co)	mg/kg	0.3			
Total Copper (Cu)	mg/kg	0.5			
Total Iron (Fe)	mg/kg	100			
Total Lead (Pb)	mg/kg	0.1			
Total Magnesium (Mg)	mg/kg	100			
Total Manganese (Mn)	mg/kg	0.2			
Total Mercury (Hg)	mg/kg	0.05			
Total Molybdenum (Mo)	mg/kg	0.1			
Total Nickel (Ni)	mg/kg	0.8			
Total Phosphorus (P)	mg/kg	10			
Total Potassium (K)	mg/kg	100			
Total Selenium (Se)	mg/kg	0.5			
Total Silver (Ag)	mg/kg	0.05			
Total Sodium (Na)	mg/kg	100			
Total Strontium (Sr)	mg/kg	0.1			
Total Thallium (TI)	mg/kg	0.05			
Total Tin (Sn)	mg/kg	0.1			
Total Titanium (Ti)	mg/kg	1 2			
Total Vanadium (V)	Total Vanadium (V) mg/kg				
Total Zinc (Zn)	tal Zinc (Zn) mg/kg				
Total Zirconium (Zr)	mg/kg	0.5			

E9.32 Item 136, Organics in landfill soil shall:

- (a) consist of approximately twenty (20) samples annually;
- (b) fabricated soil sample
- (c) part of section 9
- (d) have tests performed to include the following parameters:

Item 136	Organics, Landfill Soil			
Parameters Units MDL				
Organic Matt	er	%	0.35	

- E9.33 Item 137, Total Organic in landfill soil shall:
 - (a) consist of approximately twenty six (26) samples annually;
 - (b) fabricated soil feedstock and fabricated soil sample
 - (c) part of section 8, and section 9
 - (d) have tests performed to include the following parameters:

Item 137	Total Organic, Landfill Soil			
Parameters Units MDL				
Total Organic	c Carbon (C)	%	0.2	

- E9.34 Item 138, Soluble parameters in landfill soil shall:
 - (a) consist of approximately twenty six (26) samples annually;
 - (b) fabricated soil feedstock and fabricated soil sample
 - (c) part of section 8, and section 9
 - (d) have tests performed to include the following parameters:

Item 138	Soluble Parameters, Landfill Soil					
Parameters Units MDI						
Soluble Conductivity		dS/m	0.02			
Soluble pH		рН	-			
Saturation %		%	-			

- E9.35 Item 139, Moisture Content in landfill soil shall:
 - (a) consist of approximately twenty six (26) samples annually;
 - (b) fabricated soil feedstock and fabricated soil sample
 - (c) part of section 8, and section 9
 - (d) have tests performed to include the following parameters:

Item 139	Moisture Content, Landfill Soil				
Parameters Units MDL					
Moisture		%	0.3		

- E9.36 Item 140, Selected Metals in landfill soil shall:
 - (a) consist of approximately twenty (20) samples annually;
 - (b) fabricated soil sample
 - (c) part of section 9
 - (d) have tests performed to include the following parameters:

Item 140	Selected Metals, Landfill Soil					
Parameters Units MI						
Total Antimo	ny (Sb)	mg/kg	1			
Total Arsenic (As)		mg/kg	2			
Total Barium	(Ba)	mg/kg	2			

Total Beryllium (Be)	mg/kg	0.8
Total Cadmium (Cd)	mg/kg	0.1
Total Chromium (Cr)	mg/kg	2
Total Cobalt (Co)	mg/kg	1
Total Copper (Cu)	mg/kg	2
Total Lead (Pb)	mg/kg	1
Total Molybdenum (Mo)	mg/kg	0.8
Total Nickel (Ni)	mg/kg	2
Total Selenium (Se)	mg/kg	1
Total Silver (Ag)	mg/kg	0.1
Total Thallium (TI)	mg/kg	0.2
Total Tin (Sn)	mg/kg	2
Total Uranium (U)	mg/kg	0.4
Total Vanadium (V)	mg/kg	2
Total Zinc (Zn)	mg/kg	20

E10. TURN AROUND TIME

- E10.1 The Turn Around Time shall be:
 - (a) Based on the data that the samples were received (at the testing laboratory) and the reporting date.
 - (b) Fulfilled by submitting an official report or preliminary report accordance with the specification outlined under E2.2 to E2.11.
- E10.2 The Contractor shall not exceed the "extraction time", "hold time" or "analysis time" written in their own standard operating procedure regardless of the listed Turn-around Times.

Item	Description	Spec. Ref	Routine Turn- around Time (Calendar Days)	Rush Turn- around Time (Calendar Days)
SECT	ION A (Water)			
1.	Taste and Odour Compounds in water	E3.1	21	10
2.	Volatile Organic Compounds in water	E3.2	21	10
3.	NDMA in water	E3.3	21	10
4.	Total Microcystin in water	E3.4	21	10
5.	Total Mercury in water	E3.5	21	2
6.	COW Test #12 (Pesticides) in water	E3.6	21	14
7.	Chromium, Hexavalent in water	E3.7	21	3
8.	Perchlorate in water	E3.8	21	10
9.	Total Metals in water	E3.9	21	5
10.	Total Kjeldahl Nitrogen in water	E3.10	30	14
11.	Total Phosphorus in water	E3.11	30	14
12.	Total Reactive Phosphorus in water	E3.12	30	14
13.	Blue-Green Algae in water	E3.13	21	2
14.	Microtoxicity in water	E3.14	21	1
15.	Zebra Mussel Identification in water	E3.15	10	2
16.	Alcohol and Glycols in water	E3.16	21	2
17.	Algae Toxins in water	E3.17	21	5

Item	Description	Spec. Ref	Routine Turn- around Time (Calendar Days)	Rush Turn- around Time (Calendar Days)
SECT	TION B (Wastewater)			
19.	Fecal Coliform in wastewater	E4.1	3	NA
20.	Fecal Coliform in wastewater to true endpoint	E4.2	3	NA
21.	Escherichia Coliform in wastewater	E4.3	3	NA
22.	Escherichia Coliform in wastewater to true end point	E4.4	3	NA
23.	Total & Escherichia Coliforms in wastewater	E4.5	3	NA
24.	Total & Escherichia Coliforms in wastewater to true endpoint	E4.6	3	NA
25.	Total Mercury in wastewater	E4.7	21	2
26.	Total Mercury in Dewatered Sludge	E4.8	21	10
27.	Total Organic Carbon in Dewatered Sludge	E4.9	21	10
28.	Moisture in Dewatered Sludge	E4.10	21	10
29.	Total Nitrogen in wastewater	E4.11	7	3
30.	Total Organic Carbon in wastewater	E4.12	7	3
31.	Dissolved Organic Carbon in wastewater	E4.13	7	3
32.	Ammonia in wastewater	E4.14	7	3
33.	Total Metals in wastewater	E4.15	21	10
34.	Total Nitrogen in wastewater sludge	E4.16	21	10
35.	Available Nutrients in Dewatered Sludge	E4.17	21	10
36.	Available Ammonia in Dewatered Sludge	E4.18	21	10
37.	Loss on Ignition	E4.19	21	10
SECT	ION C (Schedule A, Wastewater)			
39.	Total Metals in wastewater	E5.1	30	14
40.	Miscellaneous Compounds in wastewater	E5.2	30	14
41.	Volatile Organic Compounds in wastewater	E5.3	30	14
42.	Target Compounds (by GC/MS) in wastewater	E5.4	30	14
43.	Phenoxyacid Herbicides (by GC/MS) in wastewater	E5.5	30	14
44.	Organochlorine Pesticides in wastewater	E5.6	30	14
45.	Polychlorinated Biphhenyls (PCBs) in wastewater	E5.7	30	14
46.	PCDD (Dioxins) and PCDF (Furans) in wastewater	E5.8	30	14
47.	EPA 8270 Extractables in wastewater	E5.9	30	14
48.	Nonylphenols and Nonylphenol Ethoxylates in wastewater	E5.10	30	14
49.	Schedule A Testing (Complete set, items 39 to 48)	E5.11	30	14
50.	Trout Bioassay-Pass/Fail in wastewater	E5.12	14	5
51.	Trout Bioassay-Pass/Fail with pH Stabilization in wastewater	E5.13	14	5
52.	Nitrate in wastewater	E5.14	30	14
SECT	TION D (Giardia & Cryptosporidium)			
54.	Testing of Giardia & Cryptosporidium in water	E6.1	14	10
55.	Testing of Giardia & Cryptosporidium in wastewater	E6.2	14	10
56.	Filta-Max Filter Modules (delivery)	E6.3	7	3

Item	Description	Spec. Ref	Routine Turn- around Time (Calendar Days)	Rush Turn- around Time (Calendar Days)
SECT	ION E (REGULATORY TESTING, Water)			
	Manitoba Conservation Test 54 PWS (General			
58.	Chemistry)	E7.1	20	10
59.	Bromate	E7.2	20	10
60.	Total Metals	E7.3	20	10
	TON F (Schedule B, Industrial Waste & Schedule D, Drainage)			
62.	Total Metals in Industrial Wastewater	E8.1	30	14
63.	Total Mercury in Industrial Wastewater	E8.2	30	14
64.	Chromium (hexavalent) in Industrial Wastewater	E8.3	30	14
65.	Total Cyanide in Industrial Wastewater	E8.4	30	14
66.	Biochemical Oxygen Demand in Industrial Wastewater	E8.5	30	14
67.	Total Suspended Solids in Industrial Wastewater	E8.6	30	14
68.	Fluoride in Industrial Wastewater	E8.7	30	14
69.	Total Nitrogen in Industrial Wastewater	E8.8	30	14
70.	Total Phosphorus in Industrial Wastewater	E8.9	30	14
71.	Total Sulphate in Industrial Wastewater	E8.10	30	14
72.	Total Sulphide in Industrial Wastewater	E8.11	30	14
73.	Organochorine Pesticides in Industrial Wastewater	E8.12	30	14
74.	Total Polychlorinated Biphenols (PCBs) in Industrial Wastewater	E8.13	30	14
75.	Volatile Organic Compounds in Industrial Wastewater	E8.14	30	14
76.	3,3-Dichlorobenzidine in Industrial Wastewater	E8.15	30	14
77.	Pentachlorophenol (PCP) in Industrial Wastewater	E8.16	30	14
78.	Total Polycyclic aromatic hydrocarbons (PAHs) in Industrial Wastewater	E8.17	30	14
79.	Nonylphenol and Nonylphenol Ethoxylates in Industrial Wastewater	E8.18	30	14
80.	Total Phenolics (4AAP) in Industrial Wastewater	E8.19	30	14
81.	Oil and Grease in Industrial Wastewater	E8.20	30	14
82.	Hydrocarbons in Industrial Wastewater	E8.21	30	14
83.	Schedule B Testing (Complete set, items 62 to 82)	E8.22	30	14
84.	Escherichia Coliform in Land Drainage Wastewater	E8.23	7	NA
85.	Ammonia in Land Drainage Wastewater	E8.24	30	14
86.	Biochemical Oxygen Demand in Land Drainage Wastewater	E8.25	30	14
87.	Chromium (hexavalent) in Land Drainage Wastewater	E8.26	30	14
88.	Total Cyanide in Land Drainage Wastewater	E8.27	30	14
89.	Extractables in Land Drainage Wastewater	E8.28	30	14
90.	Total Mercury in Land Drainage Wastewater	E8.29	30	14
91.	Nonylphenol and Nonylphenol Ethoxylates in Land Drainage Wastewater	E8.30	30	14

Item	Description	Spec. Ref	Routine Turn- around Time (Calendar Days)	Rush Turn- around Time (Calendar Days)
	Organochlorine Pesticides in Land Drainage			
92.	Wastewater	E8.31	30	14
93.	Phenols (4AAP) in Land Drainage Wastewater	E8.32	30	14
94.	Total Phosphorus in Land Drainage Wastewater	E8.33	30	14
95.	Total Polycyclic aromatic hydrocarbons (PAHs) in Land Drainage Wastewater	E8.34	30	14
96.	Total Metals in Land Drainage Wastewater	E8.35	30	14
97.	Total Polychlorinated Biphenols (PCBs) in Land Drainage Wastewater	E8.36	30	14
98.	Total Suspended Solids in Land Drainage Wastewater	E8.37	30	14
99.	Volatile Organic Compounds in Land Drainage Wastewater	E8.38	30	14
100.	Oil and Grease in Land Drainage Wastewater	E8.39	30	14
101.	Hydrocarbons in in Land Drainage Wastewater	E8.40	30	14
102.	Schedule D Testing (Complete set, 84 to 101)	E8.41	30	14
103.	Carbon Oxygen Demand in Industrial waste	E8.42	30	14
SECT	ION G (Water and Soils, from Landfills)			
105.	Total Cyanide in landfill water	E9.1	21	10
106.	Microbiological parameters in landfill water	E9.2	3	NA
107.	Anions in landfill water	E9.3	21	10
108.	Anions and Nutrients in landfill water	E9.4	21	10
109.	Organic/Inorganic Carbon in landfill water	E9.5	21	10
110.	Dissolved Metals in landfill water	E9.6	21	10
111.	Dissolved Mercury in landfill water	E9.7	21	10
112.	Speciated Metals in landfill water	E9.8	21	10
113.	Specific OC Pesticide in landfill water	E9.9	21	10
114.	Phenoxy Acid Herbicides in landfill water	E9.10	21	10
115.	Total Mercury in landfill water	E9.11	21	10
116.	Phenol in landfill water	E9.12	21	10
117.	Petroleum Hydrocarbons in landfill water	E9.13	21	10
118.	Volatile Organic Compounds in landfill water	E9.14	21	10
119.	Polycyclic Aromatic Hydrocarbons in landfill water	E9.15	21	10
120.	Total Metals in landfill water	E9.16	21	10
121.	Oil and Grease in landfill water	E9.17	21	10
122.	Specific Polycyclic Aromatic Hydrocarbons in landfill water	E9.18	21	10
123.	OC/OP Pesticides and PCB in landfill water	E9.19	21	10
124.	Dioxins and Furans in landfill water	E9.20	21	10
125.	Low Level Total Mercury in landfill water	E9.21	21	10
126.	Low Level Dissolved Mercury in landfill water	E9.22	21	10
127.	Dissolved Organic Carbon in landfill water	E9.23	21	10
128.	Nutrients in landfill water	E9.24	21	10

ltem	Description	Spec. Ref	Routine Turn- around Time (Calendar Days)	Rush Turn- around Time (Calendar Days)
129.	Calculated Carbon and Nitrogen parameters in landfill soil	E9.25	21	10
130.	Anions in landfill soil	E9.26	21	10
131.	Hexavalent Chromium in landfill soil	E9.27	21	10
132.	Nutrients in landfill soil	E9.28	21	10
133.	Physical properties in landfill soil	E9.29	21	10
134.	Soluble parameters in landfill soil	E9.30	21	10
135.	Total metals in landfill soil	E9.31	21	10
136.	Organics in landfill soil	E9.32	21	10
137.	Total Organic in landfill soil	E9.33	21	10
138.	Soluble parameters in landfill soil	E9.34	21	10
139.	Moisture Content in landfill soil	E9.35	21	10
140.	Selected Metals in landfill soil	E9.36	21	10