

DRAWING INDEX

SHEET NUMBER	CITY OF WINNIPEG DRAWING NUMBER	DRAWING TITLE
1	D-15838	DRAWING INDEX, DESIGN NOTES, LEGEND, & ABBREVIATIONS
2	D-15839	MUNROE AVENUE - HENDERSON HIGHWAY TO 142.5 E OF HENDERSON HIGHWAY
3	D-15840	MUNROE AVENUE - 142.5 E OF HENDERSON HIGHWAY TO 33.9 W OF BRAZIER STREET
4	D-15841	MUNROE AVENUE - 33.9 W OF BRAZIER STREET TO 56.0 E OF BRAZIER STREET
5	D-15842	MUNROE AVENUE - 56.1 E OF BRAZIER STREET TO 164.4 E OF BRAZIER STREET
6	D-15843	BRAZIER STREET - MUNROE AVENUE TO DONALDA AVENUE

ABBREVIATIONS

WWS	WASTE WATER SEWER
CS	COMBINED SEWER
LDS	LAND DRAINAGE SEWER
R	PROPERTY LINE
℄	CENTER LINE
G.I.S.	GEOGRAPHIC INFORMATION SYSTEM
B.M.	BENCH MARK
TH	TEST HOLE
ELEV	ELEVATION
INV	INVERT
MIN	MINIMUM
MAX	MAXIMUM
SL	STREET LIGHTING
TS	TRAFFIC SIGNALS
ABAND	ABANDONED
BLDG	BUILDING
HSE	HOUSE
CRN	CORNER
OPP	OPPOSITE
C/S OR S/C	CURB STOP
MTS	MANITOBA TELEPHONE SYSTEM
R.O.W.	RIGHT-OF-WAY
WM	WATERMAIN
CULV	CULVERT
MH	MANHOLE
CB	CATCH BASIN
CI	CURB INLET
VERT.	VERTICAL
HORZ.	HORIZONTAL
I.B.	IRON BAR
FIBRE	FIBRE OPTIC
TYP	TYPICAL
X-ING	CROSSING
HYD	HYDRANT
EXIST	EXISTING
N	NORTH
E	EAST
S	SOUTH
W	WEST
W/	WITH
C/W	CONSTRUCTED WITH
CONC	CONCRETE
AC	ASBESTOS CEMENT
VC OR CLAY	VITRIFIED CLAY
CI	CAST IRON
DI	DUCTILE IRON
PVC	POLYVINYL CHLORIDE
HDPE	HIGH DENSITY POLYETHYLENE
PCCP	PRESTRESSED CONCRETE CYLINDER PIPE

LEGEND

DESCRIPTION	EXISTING	PROPOSED
WATER PIPE	—	—
FIRE HYDRANT	⊕	⊕
VALVE	⊗	⊗
CURB STOP	⊕	⊕
REDUCER	◁	▷
COUPLING OR SLIDDER	X	X
CROSS	⊕	⊕
BEND - 11.25°, 22.5°, 45°, 90°	⋈	⋈
TEE	⋈	⋈
VERTICAL BEND	⋈	⋈
ANODE	⊕	⊕
REPAIR MARKER	⊕	⊕
PLUG	⊕	⊕
SEWER PIPE	—	—
MANHOLE	○	●
CATCH BASIN	□	■
CURB INLET	▽	▽
JUNCTION	⋈	⋈
℄ DITCH	—	—
CULVERT	—	—
SURVEY BAR	⊕	⊕
SURVEY MONUMENT	⊕	⊕
TREE - DECIDUOUS	⊕	⊕
TREE - CONIFEROUS	⊕	⊕
HYDRO	—	—
HYDRO POLE	⊕	⊕
LAMP STANDARD	⊕	⊕
HYDRO POLE W/STREET LIGHTING	⊕	⊕
POLE	⊕	⊕
GUY ANCHOR	⊕	⊕
M.T.S. POLE	⊕	⊕
PEDESTAL OR BOX	⊕	⊕
CABINET	⊕	⊕
M.T.S., SHAW, OR VIDEON	⊕	⊕
TRAFFIC SIGNALS	⊕	⊕
TRAFFIC LIGHT STANDARD	⊕	⊕
GAS	⊕	⊕
STEAM	⊕	⊕
FIBRE OPTIC	⊕	⊕
FENCE	⊕	⊕
EDGE OF PAVEMENT OR GUTTER	⊕	⊕
EDGE UNPAVED OR GRAVEL ROAD	⊕	⊕
PROJECTED ℄	⊕	⊕
LOT LINE	⊕	⊕
SIDEWALK - PATHWAY	⊕	⊕
EASEMENT	⊕	⊕
EDGE OF BUILDING	⊕	⊕
MAILBOX	⊕	⊕
PARKING METER	⊕	⊕
TEST HOLE	⊕	⊕
TREE LINE OR BUSH	⊕	⊕

PROFILE

DESCRIPTION	EXISTING	PROPOSED
WATER PIPE	—	—
HYDRANT TOP	+	+
VALVE	X	X
TEE OR CROSS	⋈	⋈
COUPLING OR BEND	⋈	⋈
REDUCER	◁	▷
END OF PIPE	⊕	⊕
SEWER PIPE	—	—
UNPAVED GROUND SURFACE	⊕	⊕
PAVED GROUND SURFACE - ℄ PIPE	⊕	⊕
GUTTER (NORTH AND WEST)	⊕	⊕
GUTTER (SOUTH AND EAST)	⊕	⊕
℄ DITCH (NORTH AND WEST)	⊕	⊕
℄ DITCH (SOUTH AND EAST)	⊕	⊕
STRUCTURE	⊕	⊕
MANHOLE OR CATCH BASIN	⊕	⊕

CONSTRUCTION NOTES

1. EXPOSE EXISTING WATERMAIN & CONFIRM INVERTS PRIOR TO CONSTRUCTION.
2. LOCATION OF ALL SERVICES TO BE CONFIRMED IN THE FIELD.
3. INSTALL WATERMAIN BY TRENCHLESS METHODS.
4. TRENCHES AND EXCAVATIONS WITHIN 1 METRE OF A PAVED AREA INCLUDING SIDEWALKS SHALL BE CLASS 3 BACKFILL.
5. ALL MATERIALS SHALL CONFORM TO THE CITY OF WINNIPEG STANDARD CONSTRUCTION SPECIFICATIONS.
6. MINIMUM COVER TO TOP OF WATERMAIN SHALL BE 2.4 m.
7. REPLACE ALL EXISTING LEAD SERVICES FROM PROPOSED WATERMAIN TO ℄.
8. NOTIFY ALL AFFECTED RESIDENTS AND BUSINESSES 24 HOURS IN ADVANCE OF ANY WATER SHUTDOWNS OR DISRUPTION OF SERVICE.

HATCH PATTERNS

EXISTING	PROPOSED	DESCRIPTION
		EARTH OR GROUND ABOVE PIPE
		SAND OR OTHER FINE MATERIAL
		CONCRETE
		WASHED STONE OR GRANULAR MATERIAL
		INTERLOCKING STONE
		METAL
		GRAVEL OR STONE

LOCATION APPROVED UNDERGROUND STRUCTURES SUPV. U/G STRUCTURES COMMITTEE DATE		B.M. ELEV.	ENGINEER'S SEAL	
NOTE: LOCATION OF UNDERGROUND STRUCTURES AS SHOWN ARE BASED ON THE BEST INFORMATION AVAILABLE. BUT NO GUARANTEE IS GIVEN THAT ALL EXISTING UTILITIES ARE SHOWN OR THAT THE GIVEN LOCATIONS ARE EXACT. CONFIRMATION OF EXISTENCE AND EXACT LOCATION OF ALL SERVICES MUST BE OBTAINED FROM THE INDIVIDUAL UTILITIES BEFORE PROCEEDING WITH CONSTRUCTION.		DESIGNED BY XX CHECKED BY XX DRAWN BY XX APPROVED BY XX SCALE: HORIZONTAL 1:250 VERTICAL 1:50 DATE 2021 02 08	RELEASED FOR CONSTRUCTION DATE	
NO. REVISIONS DATE BY		CONSULTANT DRAWING NUMBER		THE CITY OF WINNIPEG WATER AND WASTE DEPARTMENT ENGINEERING DIVISION 2021/2022 MUNROE AVENUE PAVEMENT & WATER MAIN RENEWALS INDEX PAGE
PLOT DATE: 2021 02 08		BID OPPORTUNITY: 917-2020		SHEET 1 OF 6 CITY DRAWING NUMBER D-15838