

DRAWING INDEX

SHEET NUMBER	CITY OF WINNIPEG DRAWING NUMBER	DRAWING TITLE
1	12673	COVER PAGE
2	12674	DRAWING INDEX, DESIGN NOTES, LEGEND, & ABBREVIATIONS
3	12676	ALPINE AVENUE (N LEG) - 2ND MH E OF SEAGRIM ROAD TO 1ST MH E OF SEAGRIM ROAD
4	12677	ARUNDEL ROAD (E LEG) - MH AT ELIZABETH ROAD TO MH AT ARUNDEL ROAD (S LEG)
5	12678	AUTUMWOOD DRIVE - MH AT DE BOURMONT BAY (E LEG) TO 1ST MH W OF TRAVERSE STREET
6	12679	BERNIER BAY S (N SIDE) - FIRST MH E OF SPEERS ROAD TO MH AT SPEERS ROAD
7	12680	BERTRAND STREET - MH AT TRAVERSE AVENUE TO 1ST MH W OF TRAVERSE AVENUE
8	12681	BETOURNEY STREET - MH AT JUBINVILLE BAY (E LEG) TO MH AT JUBINVILLE (W LEG)
9	12682	BETOURNEY STREET - MH AT SPEERS ROAD TO MH AT HUMBER ROAD (E LEG)
10	12683	BRAEMAR AVENUE - MH AT NIVERVILLE AVENUE TO 1ST MH N OR NIVERVILLE AVENUE
11	12684	BRAZIER STREET - MH AT CHELSEA AVENUE TO MH AT BRONX AVENUE
12	12685	BRONX AVENUE - 1ST MH E OF HENDERSON HIGHWAY TO 2ND MH E OF HENDERSON HIGHWAY
13	12686	BURNING BUSH BAY (S LEG) - 1ST MH W OF BURNING BUSH BAY (E LEG) TO MH AT DRAKE BOULEVARD
14	12687	CARMEN AVENUE - MH AT BEATRICE STREET TO 1ST MH W OF BEATRICE STREET
15	12688	CARRIERE AVENUE - 1ST MH E OF DES MEURONS STREET TO AT MH DES MEURONS STREET (W LEG)
16	12689	CASCADE BAY (N LEG) - 2ND MH W OF CASCADE BAY (E LEG) TO MH AT AUTUMWOOD DRIVE
17	12690	CHELSEA AVENUE - 1ST MH E OF HENDERSON HIGHWAY TO 2ND MH E OF HENDERSON HIGHWAY
18	12691	CLONARD AVENUE - 3RD MH E OF DES MEURONS STREET TO 2ND MH E OF DES MEURONS STREET
19	12692	CONIFER CRESCENT (S LEG) - 2ND MH E OF CONIFER DRIVE TO MH AT AUTUMWOOD DRIVE
20	12693	CORAL CRESCENT (S LEG) - 1ST MH E OF CORAL CRESCENT (W LEG) TO MH AT AUTUMWOOD DRIVE
21	12694	CRESTWOOD CRESCENT - 1ST MH W OF COVENT ROAD TO MH AT AUTUMWOOD DRIVE
22	12695	CRESTWOOD CRESCENT - MH AT DURHAM BAY (E LEG) TO MH AT DURHAM BAY (W LEG)
23	12696	CUSSON STREET - 1ST MH W OF ARCHIBALD STREET TO MH AT ARCHIBALD STREET
24	12697	DES MEURONS STREET - 1ST MH S OF HAIG AVENUE TO MH AT VIVIAN AVENUE
25	12698	DONEGAL BAY (S LEG) - MH AT DONEGAL BAY (E LEG) TO 1ST MH E OF LONDON STREET
26	12699	DUNROBIN AVENUE - 2ND MH E OF ROCH STREET TO MH AT WATT STREET
27	12702	ELM PARK ROAD 1ST MH E OF KILLARNEY STREET TO 2ND MH E OF KILLARNEY STREET
28	12703	FIFTH AVENUE - MH AT DES MEURONS STREET TO 1ST MH W OF YOUVILLE STREET
29	12704	FLYNN STREET - MH AT TALON BAY TO MH AT BARRINGTON AVENUE
30	12705	GLLIES CRESCENT - 2ND MH W OF HATCHER ROAD TO 3RD MH W OF HATCHER ROAD
31	12706	GLEN AVENUE - 1ST MH E OF KILLARNEY STREET TO 2ND MH W OF ST MARYS ROAD
32	12707	GLENLAWN AVENUE - 2ND MH W OF KILLARNEY STREET TO 1ST MH W OF KILLARNEY STREET
33	12708	HUMBOLDT AVENUE - 3RD MH W OF EGERTON ROAD TO 1ST MH W OF DES MEURONS
34	12709	KERNAGHAN AVENUE - 4TH MH W OF HOKA STREET TO 5TH MH W OF HOKA STREET
35	12710	KILDONAN DRIVE - 1ST MH S OF CANTERBURY PLACE TO 2ND MH S OF CANTERBURY PLACE
36	12711	KIMBERLY AVENUE - 2ND MH E OF ROCH STREET AT MH AT WATT STREET
37	12712	LANGEVIN STREET - 5TH MH S OF HAMEL AVENUE TO MH AT DOLLARD AVENUE
38	12713	MARTIN AVENUE W - 2ND MH E OF BRAZIER STREET TO 3RD MH E OF BRAZIER STREET
39	12714	MARTIN AVENUE W - 2ND MH W OF HENDERSON HIGHWAY TO MH AT BEATRICE STREET
40	12715	MCCALMAN AVENUE - 1ST MH E OF KEENLEYSIDE STREET TO MH AT KEENLEYSIDE STREET
41	12716	MELBOURNE AVENUE - 2ND MH E OF WATT STREET TO 1ST MH E OF WATT STREET
42	12717	MELROSE AVENUE W - 1ST MH E OF WINONA STREET TO MH AT WINONA STREET
43	12718	NEIL AVENUE - MH AT WATT STREET TO 1ST MH E OF WATT STREET
44	12719	NEWMAN AVENUE E - MH AT WABASHA STREET TO 1ST MH W OF WABASHA STREET
45	12720	NOTTINGHAM AVENUE - MH AT GREY STREET TO 1ST MH AT GREY STREET
46	12721	PLINGUET STREET - MH AT LAURIER STREET TO MH AT MCTAVISH STREET
47	12722	RIVERTON AVENUE - MH AT TALBOT AVENUE TO 1ST MH W OF TALBOT AVENUE
48	12723	SHERWOOD PLACE - 3RD MH W OF ST ANNES ROAD TO 1ST MH E OF ST MARYS ROAD
49	12724	SPEERS ROAD - MH AT WINAKWA ROAD TO 1ST MH S OF BETOURNAY STREET
50	12725	ST MICHAEL ROAD - INTERSECTION OF PULBERRY DRIVE TO 1ST MH W OF PULBERRY DRIVE
51	12726	SYDNEY AVENUE - 1ST MH E OF WATT STREET TO MH AT WATT STREET

ABBREVIATIONS

WWS	WASTE WATER SEWER
CS	COMBINED SEWER
LDS	LAND DRAINAGE SEWER
ℓ	PROPERTY LINE
ℓ	CENTER LINE
G.I.S.	GEOGRAPHIC INFORMATION SYSTEM
B.M.	BENCH MARK
TH	TEST HOLE
ELEV	ELEVATION
INV	INVERT
MIN	MINIMUM
MAX	MAXIMUM
SL	STREET LIGHTING
TS	TRAFFIC SIGNALS
ABAND	ABANDONED
BLDG	BUILDING
HSE	HOUSE
CRN	CORNER
OPP	OPPOSITE
C/S OR S/C	CURB STOP
MTS	MANITOBA TELEPHONE SYSTEM
R.O.W.	RIGHT-OF-WAY
WM	WATERMAIN
CULV	CULVERT
MH	MANHOLE
CB	CATCH BASIN
CI	CURB INLET
VERT.	VERTICAL
HORZ.	HORIZONTAL
I.B.	IRON BAR
FIBRE	FIBRE OPTIC
TYP	TYPICAL
X-ING	CROSSING
HYD	HYDRANT
EXIST	EXISTING
N	NORTH
E	EAST
S	SOUTH
W	WEST
W/	WITH
C/W	CONSTRUCTED WITH
CONC	CONCRETE
AC	ASBESTOS CEMENT
VC OR CLAY	VITRIFIED CLAY
CI	CAST IRON
DI	DUCTILE IRON
PVC	POLYVINYL CHLORIDE
HDPE	HIGH DENSITY POLYETHYLENE
PCCP	PRESTRESSED CONCRETE CYLINDER PIPE

LEGEND

DESCRIPTION	PLAN VIEW		
	ABANDONED	EXISTING	PROPOSED
WATER PIPE			
FIRE HYDRANT			
VALVE			
CURB STOP			
REDUCER			
COUPLING OR SLIDDER			
CROSS			
BEND - 11.25', 22.5', 45', 90'			
TEE			
VERTICAL BEND			
ANODE			
REPAIR MARKER			
PLUG			
SEWER PIPE			
MANHOLE			
CATCH BASIN			
CURB INLET			
JUNCTION			
ℓ DITCH			
CULVERT			
SURVEY BAR			
SURVEY MONUMENT			
TREE - DECIDUOUS			
TREE - CONIFEROUS			
HYDRO			
LAMP STANDARD			
HYDRO POLE W/STREET LIGHTING			
POLE			
GUY ANCHOR			
M.T.S. POLE			
PEDESTAL OR BOX			
CABINET			
M.T.S., SHAW, OR VIDEON			
TRAFFIC SIGNALS			
TRAFFIC LIGHT STANDARD			
GAS			
STEAM			
FIBRE OPTIC			
FENCE			
EDGE OF PAVEMENT OR GUTTER			
EDGE UNPAVED OR GRAVEL ROAD			
ℓ			
PROJECTED ℓ			
LOT LINE			
SIDEWALK - PATHWAY			
EASEMENT			
EDGE OF BUILDING			
MAILBOX			
PARKING METER			
TEST HOLE			
TREE LINE OR BUSH			

DESCRIPTION	PROFILE		
	ABANDONED	EXISTING	PROPOSED
WATER PIPE			
HYDRANT TOP			
VALVE			
TEE OR CROSS			
COUPLING OR BEND			
REDUCER			
END OF PIPE			
SEWER PIPE			
UNPAVED GROUND SURFACE			
PAVED GROUND SURFACE - ℓ PIPE			
GUTTER (NORTH AND WEST)			
GUTTER (SOUTH AND EAST)			
ℓ DITCH (NORTH AND WEST)			
ℓ DITCH (SOUTH AND EAST)			
STRUCTURE			
MANHOLE OR CATCH BASIN			

CONSTRUCTION NOTES

1. ALL PIPE SHALL HAVE CLASS B - TYPE 2 BEDDING
2. INSTALL SEWER BY TRENCHLESS METHODS.
3. CONFIRM THE LOCATION OF ALL SEWER SERVICES.
4. BACKFILL UNDER PAVEMENT, IN SIDEWALKS, & WITHIN 1.0 OF PAVEMENT TO BE CLASS 3.
5. BACKFILL IN BOULEVARD TO BE CLASS 5.
6. RENEW SEWER SERVICES TO ℓ.
7. INSTALL SEWER SERVICE RISERS TO ELEVATION WHERE MINIMUM SLOPE OF 1% IS MAINTAINED FOR ALL SERVICES.

HATCH PATTERNS

EXISTING	PROPOSED	DESCRIPTION
		EARTH OR GROUND ABOVE PIPE
		SAND OR OTHER FINE MATERIAL
		CONCRETE
		WASHED STONE OR GRANULAR MATERIAL
		INTERLOCKING STONE
		METAL
		GRAVEL OR STONE

CONSTRUCTION COMPLETION
DATE: YY/MM/DD

RECORD DRAWING

LOCATION APPROVED UNDERGROUND STRUCTURES SUPV. U/G STRUCTURES COMMITTEE _____ DATE _____ NOTE: LOCATION OF UNDERGROUND STRUCTURES AS SHOWN ARE BASED ON THE BEST INFORMATION AVAILABLE BUT NO GUARANTEE IS GIVEN THAT ALL EXISTING UTILITIES ARE SHOWN OR THAT THE GIVEN LOCATIONS ARE EXACT. CONFIRMATION OF EXISTENCE AND EXACT LOCATION OF ALL SERVICES MUST BE OBTAINED FROM THE INDIVIDUAL UTILITIES BEFORE PROCEEDING WITH CONSTRUCTION.	VERTICAL DATUM: CGVD28 (HT2.0 Geoid) HORIZONTAL DATUM: NAD83 (June 1990), Zone 14	ENGINEER'S SEAL ORIGINAL SIGNED BY S.R.J. COURNOYER 2021/04/16	THE CITY OF WINNIPEG WATER AND WASTE DEPARTMENT ENGINEERING DIVISION 2021 SEWER RENEWALS BY CIPP LINING CONTRACT No.9 INDEX PAGE	SHEET 2 OF 57 CITY DRAWING NUMBER 12674																											
	<table border="1"> <tr><td>DESIGNED BY</td><td>SC</td><td>CHECKED BY</td><td>SC</td></tr> <tr><td>DRAWN BY</td><td>AOM</td><td>APPROVED BY</td><td>KZ</td></tr> <tr><td>SCALE:</td><td></td><td>RELEASED FOR CONSTRUCTION</td><td></td></tr> <tr><td>HORIZONTAL</td><td>1:250</td><td></td><td></td></tr> <tr><td>VERTICAL</td><td>1:50</td><td></td><td></td></tr> <tr><td>DATE</td><td>2021 04 16</td><td>DATE</td><td>2021-04-16</td></tr> <tr><td>NO.</td><td>REVISIONS</td><td>DATE</td><td>BY</td></tr> </table>	DESIGNED BY		SC	CHECKED BY	SC	DRAWN BY	AOM	APPROVED BY	KZ	SCALE:		RELEASED FOR CONSTRUCTION		HORIZONTAL	1:250			VERTICAL	1:50			DATE	2021 04 16	DATE	2021-04-16	NO.	REVISIONS	DATE	BY	K.ZUREK DATE: 2021 04 16 PLOT DATE: 2021 04 16
DESIGNED BY	SC	CHECKED BY	SC																												
DRAWN BY	AOM	APPROVED BY	KZ																												
SCALE:		RELEASED FOR CONSTRUCTION																													
HORIZONTAL	1:250																														
VERTICAL	1:50																														
DATE	2021 04 16	DATE	2021-04-16																												
NO.	REVISIONS	DATE	BY																												