_	

ROOF TOP UNIT SCHEDULE														
TAG		E.S.P. ("W.C.)	HEATING INPUT (MBH)	HEATING OUTPUT	SUPPLY FAN	RETURN FAN	ELECTRICAL	MIN. CIRCUIT AMPACITY (AMPS) MAX WEIGHT	MAX WEIGHT (LBS)	MAY WEIGHT // BS)	COMMENTS			
IAG	DESCRIPTION	AIRI LOW (OF WI)	L.S.F. (VV.C.)	TIEATING INFOT (WIDIT)	(MBH)	MOTOR (HP)	MOTOR (HP)	(V./Ph./Hz.)	WIN. CIRCUIT AMPACITY (AMPS) WAX WEIGHT (LBS)		MIN. CINCOTT AMIT ACTT (AMITS)	WIN. CIRCUIT AMPACITT (AMPS)	MAKE / MODEL	COMMENTS
RTU-2	AIR HANDLING UNIT	8500	1	600	480	10	5	208/3/60	69.8	5800	ENGINEERED AIR / DJE60/C/O/R	REFER TO SPECIFICATION FOR REQUIRED OPTIONS AND ACCESSORIES		

CONDENSING UNIT SCHEDULE										
TAG	DESCRIPTION	SERVING UNIT NO.	TOTAL CAPACITY (TONS)	AIRFLOW (CFM)	ELECTRICAL (V./Ph./Hz.)	REFRIGERANT TYPE	MAX WEIGHT (LBS)	MAKE / MODEL	DESCRIPTION	
CU-2	CONDENSING UNIT	RT-2	20	8500	208/3/60	R-22	1584	ENGINEERED AIR / CU212	REFER TO SPECIFICATION FOR REQUIRED OPTIONS AND ACCESSORIES	

	ELECTRIC DUCT HEATER SCHEDULE									
TAG DESCRIPTION	HEATING CAPACITY (KW)	ELECTRICAL (V./Ph./Hz.)		DIMENSIONS		MAKE / MODEL	DESCRIPTION			
IAG	DESCRIPTION	TIEATING CAPACITT (RW)	LLLOTRIOAL (V./FII./IIZ.)	HEIGHT (in.)	WIDTH (in.)	LENGTH (in.)	WARE / WIODEL	DESCRIPTION		
EDH-1	ELECTRIC DUCT HEATER	10.0	600/3/60	24	12	6	PRICE / DF CI00H	REFER TO SPECIFICATION DRAWINGS FOR REQUIRED OPTIONS AND ACCESSORIES		
EDH-2	ELECTRIC DUCT HEATER	4.5	600/3/60	14	12	6	PRICE / DF CI00H	REFER TO SPECIFICATION DRAWINGS FOR REQUIRED OPTIONS AND ACCESSORIES		
EDH-3	ELECTRIC DUCT HEATER	5.0	600/3/60	10	8	10	PRICE / DF CI00H	REFER TO SPECIFICATION DRAWINGS FOR REQUIRED OPTIONS AND ACCESSORIES		
EDH-4	ELECTRIC DUCT HEATER	6.5	600/3/60	18	12	5	PRICE / DF CI00H	REFER TO SPECIFICATION DRAWINGS FOR REQUIRED OPTIONS AND ACCESSORIES		
EDH-5	ELECTRIC DUCT HEATER	4.0	600/3/60	12	11	6	PRICE / DF CI00H	REFER TO SPECIFICATION DRAWINGS FOR REQUIRED OPTIONS AND ACCESSORIES		
EDH-6	ELECTRIC DUCT HEATER	2.2	600/3/60	12	8	6	PRICE / DF CI00H	REFER TO SPECIFICATION DRAWINGS FOR REQUIRED OPTIONS AND ACCESSORIES		
EDH-7	ELECTRIC DUCT HEATER	3.0	600/3/60	12	10	6	PRICE / DF CI00H	REFER TO SPECIFICATION DRAWINGS FOR REQUIRED OPTIONS AND ACCESSORIES		
EDH-8	ELECTRIC DUCT HEATER	3.2	600/3/60	12	10	5	PRICE / DF CI00H	REFER TO SPECIFICATION DRAWINGS FOR REQUIRED OPTIONS AND ACCESSORIES		
EDH-9	ELECTRIC DUCT HEATER	8.0	600/3/60	20	12	5	PRICE / DF CI00H	REFER TO SPECIFICATION DRAWINGS FOR REQUIRED OPTIONS AND ACCESSORIES		

NOTES:

SHOWN ON DRAWINGS.

THESE DRAWINGS SHALL NOT BE SCALED.

THE CONTRACTOR SHALL VISIT THE SITE AND SATISFY ONESELF ALL DIMENSIONS, DATUM, AND DETAILED INFORMATION SHOWN ARE CORRECT.

THE CONTRACTOR IS TO REVIEW AND COORDINATE ALL ARCHITECTURAL, MECHANICAL, ELECTRICAL AND STRUCTURAL DRAWINGS FOR ADDITIONAL OPENINGS THROUGH FLOORS, WALLS, AND CEILINGS FOR DUCT, PIPE & ELECTRICAL RISERS AND ALL OPENINGS NOT


ALL OPENINGS THROUGH THE FIRE SEPARATIONS AS A RESULT OF THE WORK OF THIS CONTRACT ARE TO BE FIRE STOPPED AND SEALED WITH ULC APPROVED FIRE STOPPING TO MAINTAIN THE INTEGRITY OF THE FIRE SEPARATION, AND PROVIDE AND SMOKE-TIGHT


ALL PRODUCTS AND MATERIALS TO BE USED AND INSTALLED SHALL CONFORM WITH MANUFACTURER'S SPECIFICATIONS & APPLICABLE CODES.

THE CONTRACTOR SHALL BE RESPONSIBLE TO PATCH AND MAKE GOOD ALL EXISTING CONSTRUCTION AFFECTED BY THE REMOVAL OF ALL ITEMS FORMING THE PART OF THE RENOVATION WORK.

WHERE NEW FLOORING AND BASE IS TO BE INSTALLED IN EXISTING AREAS (REFER TO FLOOR PLAN AND ROOM SCHEDULE) THE EXISTING FLOORING SURFACE AND BASE MUST BE REMOVED, UNLESS OTHERWISE NOTED. ALL FLOOR SURFACES SHALL BE PREPARED IN ACCORDANCE TO MANUFACTURER'S RECOMMENDATIONS FOR INSTALLATION OF NEW

WHERE PAINTING OF EXISTING WALLS IS INDICATED ON THE ROOM SCHEDULE, THESE WALLS MUST BE CLEANED OF ANY EXISTING WALL COVERING, PATCHED & PREPARED TO ACCEPT NEW MATERIAL, UNLESS OTHERWISE NOTED.







THE CITY OF WINNIPEG
PLANNING, PROPERTY AND
DEVELOPMENT DEPARTMENT
MUNICIPAL ACCOMMODATIONS DIVISION
3-65 GARRY STREET, R3C 4K4

PROJECT
REPLACEMENT OF AIR HANDLING UNIT RTU-2 GLENWOOD COMMUNITY CENTRE

27 OVERTON STREET



No. 245

KGS

SHEET TITLE MECHANICAL SCHEDULES