



1
A1.0 SITE DEMOLITION PLAN
 SCALE: 1:150

SITE DEMOLITION GENERAL NOTES

1. CITY OF WINNIPEG ARBORIST TO BE ON SITE DURING EXCAVATION, DEMOLITION, AND REGRADING OF SITE. CONTRACTOR TO COORDINATE.
2. MINIMIZE DAMAGE TO ALL EXISTING TREE ROOTS, TRUNKS & CANOPIES. EXCAVATION, DEMOLITION, AND REGRADING OF THE SITE ARE TO OCCUR UNDER THE DIRECTION OF A CITY OF WINNIPEG ARBORIST.
3. EXISTING SITE EQUIPMENT IS TO BE REMOVED & RELOCATED BY CITY OF WINNIPEG (N.I.C.)
4. DEMOLISH ALL TREE STUMPS WITHIN CONSTRUCTION AREA THAT MAY IMPACT SITE WORK AND NEW BUILDING
5. MINIMIZE DAMAGE OF GRASS / SOD RESULTANT FROM CONSTRUCTION
6. GENERAL CONTRACTOR SHALL COORDINATE THE DISCONNECT AND REMOVAL OF WATER SERVICES BACK TO NEAREST ACTIVE MAINS. REFER TO CIVIL & MECHANICAL.

SITE DEMOLITION PLAN KEYNOTES

1. EXISTING FIRE HYDRANT TO BE DEMOLISHED - REFER TO SITE RENOVATION PLAN & CIVIL.
2. ALL EXISTING TREES, MULCH & GRASS OUTSIDE OF YARD TO REMAIN. PROTECT DURING CONSTRUCTION. PROVIDE TREE PROTECTION FOR ALL TREES GREATER THAN 200mm CALIPER WITHIN 3650mm OF EXISTING FENCE LINE.
3. EXISTING CHAIN LINK FENCE AROUND YARD TO BE DEMOLISHED IN ITS ENTIRETY INCLUDING ANY CONCRETE PILES BELOW POSTS - BY CITY OF WINNIPEG (N.I.C.)
4. EXISTING DIRT ROAD FOR SMALL PARK VEHICLES TO REMAIN. REFER TO CIVIL & A1.1.
5. DEMOLISH EXISTING ASPHALT ROADWAY AND PREPARE FOR NEW ASPHALT/GRAVEL SURFACE - REFER TO CIVIL.
6. EXISTING GROUND ASPHALT YARD TO BE DEMOLISHED - PREPARE FOR NEW STAFF HOUSE AND NEW ASPHALT/GRAVEL. REFER TO CIVIL, SITE RENOVATION PLAN, AND GEOTECH REPORT.
7. EXISTING WOOD CHIP, GARBAGE, SOIL, & GRAVEL STORAGE TO BE RELOCATED (N.I.C.). PREPARE SURFACE FOR NEW ASPHALT/GRAVEL - REFER TO RENOVATION PLAN & CIVIL.
8. EXISTING GRASS TO BE DEMOLISHED & SURFACE PREPARED FOR NEW ASPHALT - REFER TO CIVIL & SITE RENOVATION PLAN
9. DEMOLISH EXISTING STUMP - REFER TO CIVIL.
10. EXISTING ASPHALT ROAD TO REMAIN. PROTECT DURING CONSTRUCTION.
11. DEMOLISH EXISTING SIGN IN ENTIRETY.
12. REFERENCE POINT FOR SITING OF NEW BUILDING (INTERSECTION OF GRIDLINES S&O) - REFER TO SITE RENOVATION PLAN & FLOOR PLAN. FINALIZE REFERENCE POINT PRIOR TO DEMOLITION OF HYDRANT AND POST.
13. CITY OF WINNIPEG TO DEMOLISH EXISTING TREE - CONTRACTOR TO REMOVE STUMP IN ITS ENTIRETY.

SITE DEMOLITION LEGEND:

- DEMOLISH GROUND-UP ASPHALT
- DEMOLISH ASPHALT
- DEMOLISH GRASS/DIRT
- DEMOLISH DIRT/GRAVEL
- WM - EXISTING WATER MAIN
- EXISTING FENCE TO BE DEMOLISHED
- EDGE OF EXISTING TREE/BUSH LINE
- EXISTING TREE TO REMAIN
- EXISTING TREE TO BE DEMOLISHED BY CITY OF WINNIPEG - CONTRACTOR TO REMOVE STUMP ONLY
- SURVEY CONTROL POINT MARKED WITH LATHE ON SITE REFER TO SURVEY
- EXISTING HYDRANT TO BE DEMOLISHED - REFER TO CIVIL

NO.	DATE	REVISION / ISSUANCE
3	-	-
2	-	-
1	-	-
0	21.10.29	ISSUED FOR CONSTRUCTION

architecture inc.
120 Fort Street, Suite 103 Winnipeg, Manitoba R3C 1C7 204.318.2010

Project
**ST. VITAL PARK
 GARAGE & STAFF HOUSE
 190 RIVER ROAD**

Sheet Title
SITE DEMOLITION PLAN

Project No.	20105	Sheet	A1.0
Date	21.10.29		