

## DRAWING NOTES - SANITARY

- SANITARY DRAIN C/W BUILDING CLEANOUT AT BUILDING LINE.
  COORDINATE W/ OUTSIDE SERVICES CONTRACTOR FOR EXTENSION OF PIPING INTÓ BUILDING.
- OIL INTERCEPTOR BELOW SLAB; EXTEND DEDICATED UP/DOWNSTREAM VENTING UP THRU ROOF. COORDINATE UNDERSLAB MOUNTING WITH STRUCTURAL.
- SEDIMENT INTERCEPTORS BELOW SLAB, EXTEND TO OIL INTERCEPTOR. COORDINATE UNDERSLAB MOUNTING WITH STRUCTURAL.
- HWT-1/2 ON CONCRETE HOUSEKEEPING PAD; ROUTE T & P RELIEF TO ADJACENT FLOOR DRAIN.
- HRV SUSPENDED FROM STRUCTURE; ROUTE CONDENSATE DRAIN TO ADJACENT FLOOR DRAIN. PAD MOUNT AH-1; ROUTE CONDENSATE DRAINS ALONG EXTERIOR WALL AND SLOPE TO ADJACENT FLOOR DRAIN.
- PROVIDE PROTECTIVE GUARDS AROUND SANITARY RISERS WHERE EXPOSED PIPING PENETRATES CONCRETE FLOOR SLAB.
- PROVIDE HEAVY DUTY FERNCO STRONG BACK COUPLINGS ON SANITARY DRAINAGE PIPING BELOW GRADE, UPSTREAM AND DOWNSTREAM OF GRADE BEAM SEPARATING FLOOR AREAS OF STRUCTURAL-SLAB AND SLAB-ON-GRADE CONSTRUCTION METHODS, TO ALLOW FOR MINOR MOVEMENT OF STRUCTURE.

0 2021.11.01 - ISSUED FOR CONSTRUCTION



architecture inc.

NOVA 3 ENGINEERING LTD.
PROFESSIONAL ENGINEERS 201-120 FORT STREET TEL.: (204) 943-6142 WINNIPEG, MANITOBA R3C 1C7 FAX.: (204) 942-1276 WWW.NOVA3.CA JN.: 41-070 THIS DRAWING IS THE EXCLUSIVE PROPERTY OF NOVA 3 ENGINEERING LTD. AND MAY ONLY BE REPRODUCED WITH THE WRITTEN PERMISSION OF NOVA 3 ENGINEERING LTD.

THE CONCEPT AND DESIGN INCORPORATED INTO THIS DRAWING ARE BASED ON INFORMATION PROVIDED BY THE CLIENT AND OTHER RELATED SOURCES. PROFESSIONAL ENGINEER ACCEPTS NO RESPONSIBILITY FOR DRAWING AND DESIGN UNLESS DRAWING IS ACCOMPANIED BY ORIGINAL SEALED LETTER OF INTENT OR EQUIVALENT ACCEPTABLE FACSIMILE. PROFESSIONAL ENGINEER ACCEPTS NO RESPONSIBILITY FOR FINAL INSTALLATION CONFORMANCE WITHOUT ORIGINAL SEALED CERTIFICATE OF INSPECTION OR EQUIVALENT ACCEPTABLE FACSIMILE.

ST. VITAL PARK MAINTENANCE FACILITY

190 RIVER ROAD

MAIN FLOOR SANITARY

20105 21.11.01