

# THE CITY OF WINNIPEG

# **TENDER**

**TENDER NO. 146-2024** 

# **TABLE OF CONTENTS**

PART A	- BID	SUBMI	SSION
--------	-------	-------	-------

Form A: Bid/Proposal Form B: Prices

PART B -	BIDDING	<b>PROCEDI</b>	JRES
----------	---------	----------------	------

B2. B3. B4. B5. B6. B7. B8. B9. B10. B11. B12. B13. B14. B15. B16.	Contract Title Submission Deadline Site Investigation Enquiries Confidentiality Addenda Substitutes Bid Components Bid Prices Disclosure Conflict of Interest and Good Faith Qualification Opening of Bids and Release of Information Irrevocable Bid Withdrawal of Bids Evaluation of Bids Award of Contract	1 1 1 1 2 2 2 2 3 3 4 4 4 5 6 7 7 7 8 8
PART C	- GENERAL CONDITIONS	
C0.	General Conditions	1
PART D	- SUPPLEMENTAL CONDITIONS	
D2. D3. D4. D5. D6. D7.	General Conditions Scope of Work Site Investigation Due Diligence and Risk Definitions Contract Administrator Contractor's Supervisor Accessible Customer Service Requirements Unfair Labour Practices	1 1 1 2 2 2 2 2 3
D9. D10. D11. D12. D13.	Authority to Carry on Business Safe Work Plan Insurance Contract Security Subcontractor List Detailed Work Schedule	3 4 4 4 5 6
D15. D16. D17. D18. D19.	Edule of Work Commencement Substantial Performance Total Performance Liquidated Damages Supply Chain Disruption Schedule Delays Scheduled Maintenance	6 7 7 7 7 8
D21.	Job Meetings  Prime Contractor The Workplace Safety and Health Act (Manitoha)	8

D23. The Workplace Safety and Health Act (Manitoba) – Qualifications	8
Measurement and Payment D24. Payment	9
<b>Warranty</b> D25. Warranty	9
Dispute Resolution D26. Dispute Resolution	9
Indemnity D27. Indemnity	10
Third Party Agreements D28. Funding and/or Contribution Agreement Obligations	11
Form H1: Performance Bond Form H2: Labour and Material Payment Bond Form H3: Irrevocable Standby Letter of Credit Form J: Subcontractor List Form L: Detailed Work Schedule Form L: Detailed Work Schedule	14 16 18 20 21 22
PART E - SPECIFICATIONS	
<ul> <li>General</li> <li>E1. Applicable Specifications and Drawings</li> <li>E2. Hazardous Materials</li> <li>E3. Existing Services and Utilities</li> <li>E4. Access To Site</li> <li>E5. Permits, Notices, Licenses, Certificates, Laws and Rules</li> <li>E6. Damage to Existing Structures, Trees and Property</li> <li>E7. Pedestrian Safety And Traffic Management</li> <li>E8. Protection of the Survey Infrastructure</li> <li>E9. Site Enclosures</li> </ul>	1 1 1 2 2 2 2 3 3 3
Site Development E10. Excavation and Grading E11. Asphalt Pathway and Seating Areas E12. CIP Concrete Edging E13. Protective Surfacing - Engineered Wood Fibre E14. Sub-Surface Drainage of Protective Surfacing Areas E15. Site Furnishings E16. Topsoil and Sodding E17. Shade Structure	4 6 9 9 11 14 16
Play Equipment E18. Play Equipment E19. Swing Sets E20. Cast-In-Place Concrete Foundations E21. Maintenance Kits	18 22 24 26

#### **PART B - BIDDING PROCEDURES**

#### **B1.** CONTRACT TITLE

B1.1 AMBER GATES COMMUNITY PLAYGROUND AND SHELTER

#### **B2. SUBMISSION DEADLINE**

- B2.1 The Submission Deadline is 4:00 p.m. Winnipeg time, April 29, 2024.
- B2.2 The Contract Administrator or the Manager of Materials may extend the Submission Deadline by issuing an addendum at any time prior to the time and date specified in B2.1.

#### **B3.** SITE INVESTIGATION

- B3.1 Further to C3.1, the Bidder may view the Site without making an appointment.
- B3.2 The Bidder is advised that:
  - (a) the location of any utility which can be determined from the records or other information available at the offices of any public authority or person, including a municipal corporation and any board or commission thereof, having jurisdiction or control over the utility;
  - (b) the nature of the surface and subsurface conditions at the Site;
  - (c) the location, nature, quality or quantity of the materials to be removed or to be employed in the performance of the Work;
  - (d) the nature, quality or quantity of the Plant needed to perform the Work;
  - (e) all matters concerning access to the Site, power supplies, location of existing services, utilities or materials necessary for the completion of the Work; and
  - (f) all other matters which could in any way affect their Proposal or the performance of the Work.

#### **B4.** ENQUIRIES

- B4.1 All enquiries shall be directed to the Contract Administrator identified in D5.1.
- B4.2 If the Bidder finds errors, discrepancies or omissions in the Tender, or is unsure of the meaning or intent of any provision therein, the Bidder shall notify the Contract Administrator of the error, discrepancy or omission, or request a clarification as to the meaning or intent of the provision at least five (5) Business Days prior to the Submission Deadline.
- B4.3 Responses to enquiries which, in the sole judgment of the Contract Administrator, require a correction to or a clarification of the Tender will be provided by the Contract Administrator to all Bidders by issuing an addendum.
- B4.4 Responses to enquiries which, in the sole judgment of the Contract Administrator, do not require a correction to or a clarification of the Tender will be provided by the Contract Administrator only to the Bidder who made the enquiry.
- B4.5 The Bidder shall not be entitled to rely on any response or interpretation received pursuant to B4 unless that response or interpretation is provided by the Contract Administrator in writing.
- B4.6 Any enquiries concerning submitting through MERX should be addressed to:

MERX Customer Support Phone: 1-800-964-6379 Email: merx@merx.com

Bidding Procedures Page 2 of 9

The City of Winnipeg Tender No. 146-2024

Template Version: 2023 07 27 - Const noBidSecurity

#### **B5.** CONFIDENTIALITY

- B5.1 Information provided to a Bidder by the City or acquired by a Bidder by way of further enquiries or through investigation is confidential. Such information shall not be used or disclosed in any way without the prior written authorization of the Contract Administrator. The use and disclosure of the confidential information shall not apply to information which:
  - (a) was known to the Bidder before receipt hereof; or
  - (b) becomes publicly known other than through the Bidder; or
  - (c) is disclosed pursuant to the requirements of a governmental authority or judicial order.
- B5.2 The Bidder shall not make any statement of fact or opinion regarding any aspect of the Tender to the media or any member of the public without the prior written authorization of the Contract Administrator.

#### B6. ADDENDA

- B6.1 The Contract Administrator may, at any time prior to the Submission Deadline, issue addenda correcting errors, discrepancies or omissions in the Tender, or clarifying the meaning or intent of any provision therein.
- B6.2 The Contract Administrator will issue each addendum at least two (2) Business Days prior to the Submission Deadline, or provide at least two (2) Business Days by extending the Submission Deadline.
- B6.3 Addenda will be available on the MERX website at <a href="www.merx.com">www.merx.com</a>.
- B6.4 The Bidder is responsible for ensuring that they have received all addenda and is advised to check the MERX website for addenda regularly and shortly before the Submission Deadline, as may be amended by addendum.
- B6.5 The Bidder shall acknowledge receipt of each addendum in Paragraph 10 of Form A: Bid/Proposal. Failure to acknowledge receipt of an addendum may render a Bid non-responsive
- B6.6 Notwithstanding B4, enquiries related to an Addendum may be directed to the Contract Administrator indicated in D5.

#### **B7.** SUBSTITUTES

- B7.1 The Work is based on the Plant, Materials and methods specified in the Tender.
- B7.2 Substitutions shall not be allowed unless application has been made to and prior approval has been granted by the Contract Administrator in writing.
- B7.3 Requests for approval of a substitute will not be considered unless received in writing by the Contract Administrator at least five (5) Business Days prior to the Submission Deadline.
- B7.4 The Bidder shall ensure that any and all requests for approval of a substitute:
  - (a) provide sufficient information and details to enable the Contract Administrator to determine the acceptability of the Plant, Material or method as either an approved equal or alternative:
  - (b) identify any and all changes required in the applicable Work, and all changes to any other Work, which would become necessary to accommodate the substitute;
  - (c) identify any anticipated cost or time savings that may be associated with the substitute;
  - (d) certify that, in the case of a request for approval as an approved equal, the substitute will fully perform the functions called for by the general design, be of equal or superior substance to that specified, is suited to the same use and capable of performing the same

Bidding Procedures Page 3 of 9

The City of Winnipeg Tender No. 146-2024

Template Version: 2023 07 27 - Const noBidSecurity

- function as that specified and can be incorporated into the Work, strictly in accordance with the proposed work schedule and the dates specified in the Supplemental Conditions for Substantial Performance and Total Performance;
- (e) certify that, in the case of a request for approval as an approved alternative, the substitute will adequately perform the functions called for by the general design, be similar in substance to that specified, is suited to the same use and capable of performing the same function as that specified and can be incorporated into the Work, strictly in accordance with the proposed work schedule and the dates specified in the Supplemental Conditions for Substantial Performance and Total Performance.
- B7.5 The Contract Administrator, after assessing the request for approval of a substitute, may in their sole discretion grant approval for the use of a substitute as an "approved equal" or as an "approved alternative", or may refuse to grant approval of the substitute.
- B7.6 The Contract Administrator will provide a response in writing, at least two (2) Business Days prior to the Submission Deadline, to the Bidder who requested approval of the substitute.
- B7.6.1 The Contract Administrator will issue an Addendum, disclosing the approved materials, equipment, methods and products to all potential Bidders. The Bidder requesting and obtaining the approval of a substitute shall be responsible for disseminating information regarding the approval to any person or persons they wish to inform.
- B7.7 If the Contract Administrator approves a substitute as an "approved equal", any Bidder may use the approved equal in place of the specified item.
- B7.8 If the Contract Administrator approves a substitute as an "approved alternative", any Bidder bidding that approved alternative may base their Total Bid Price upon the specified item but may also indicate an alternative price based upon the approved alternative. Such alternatives will be evaluated in accordance with B17.
- B7.9 No later claim by the Contractor for an addition to the Total Bid Price because of any other changes in the Work necessitated by the use of an approved equal or an approved alternative will be considered.

#### **B8. BID COMPONENTS**

- B8.1 The Bid shall consist of the following components:
  - (a) Form A: Bid/Proposal;
  - (b) Form B: Prices.
- B8.2 All components of the Bid shall be fully completed or provided, and submitted by the Bidder no later than the Submission Deadline, with all required entries made clearly and completely.
- B8.3 The Bid shall be submitted electronically through MERX at <a href="https://www.merx.com">www.merx.com</a>.
- B8.3.1 Bids will **only** be accepted electronically through MERX.
- B8.4 Bidders are advised that inclusion of terms and conditions inconsistent with the Tender document, including the General Conditions, will be evaluated in accordance with B17.1(a).

#### B9. BID

- B9.1 The Bidder shall complete Form A: Bid/Proposal, making all required entries.
- B9.2 Paragraph 2 of Form A: Bid/Proposal shall be completed in accordance with the following requirements:
  - (a) if the Bidder is a sole proprietor carrying on business in their own name, their name shall be inserted;
  - (b) if the Bidder is a partnership, the full name of the partnership shall be inserted;

Bidding Procedures Page 4 of 9

Template Version: 2023 07 27 - Const noBidSecurity

- (c) if the Bidder is a corporation, the full name of the corporation shall be inserted;
- (d) if the Bidder is carrying on business under a name other than their own, the business name and the name of every partner or corporation who is the owner of such business name shall be inserted.
- B9.2.1 If a Bid is submitted jointly by two or more persons, each and all such persons shall identify themselves in accordance with B9.2.
- B9.3 In Paragraph 3 of Form A: Bid/Proposal, the Bidder shall identify a contact person who is authorized to represent the Bidder for purposes of the Bid.
- B9.4 Paragraph 13 of Form A: Bid/Proposal shall be signed in accordance with the following requirements:
  - (a) if the Bidder is a sole proprietor carrying on business in their own name, it shall be signed by the Bidder;
  - (b) if the Bidder is a partnership, it shall be signed by the partner or partners who have authority to sign for the partnership;
  - (c) if the Bidder is a corporation, it shall be signed by their duly authorized officer or officers;
  - (d) if the Bidder is carrying on business under a name other than their own, it shall be signed by the registered owner of the business name, or by the registered owner's authorized officials if the owner is a partnership or a corporation.
- B9.4.1 The name and official capacity of all individuals signing Form A: Bid/Proposal should be entered below such signatures.
- B9.4.2 All signatures shall be original.
- B9.5 If a Bid is submitted jointly by two or more persons, the word "Bidder" shall mean each and all such persons, and the undertakings, covenants and obligations of such joint Bidders in the Bid and the Contract, when awarded, shall be both joint and several.

#### B10. PRICES

- B10.1 The Bidder shall state a price in Canadian funds for each item of the Work identified on Form B:
- B10.1.1 Prices stated on Form B: Prices shall not include any costs which may be incurred by the Contractor with respect to any applicable funding agreement obligations as outlined in D28. Any such costs shall be determined in accordance with D28.
- B10.2 The quantities listed on Form B: Prices are to be considered approximate only. The City will use said quantities for the purpose of comparing Bids.
- B10.3 The quantities for which payment will be made to the Contractor are to be determined by the Work actually performed and completed by the Contractor, to be measured as specified in the applicable Specifications.
- B10.4 Payments to Non-Resident Contractors are subject to Non-Resident Withholding Tax pursuant to the Income Tax Act (Canada).
- B10.5 The Bidder shall enter the Total Bid Price from Form B: Prices into the Total Bid Price field in MERX.
- B10.5.1 Bidders are advised that the calculation indicated in B17.5 will prevail over the Total Bid Price entered in MERX.

#### B11. DISCLOSURE

B11.1 Various Persons provided information or services with respect to this Work. In the City's opinion, this relationship or association does not create a conflict of interest because of this full

Bidding Procedures Page 5 of 9

The City of Winnipeg Tender No. 146-2024

Template Version: 2023 07 27 - Const noBidSecurity

disclosure. Where applicable, additional material available as a result of contact with these Persons is listed below.

#### B11.2 The Persons are:

(a) Playgrounds R Us: Provided playground concept, equipment & part numbers, and shade structure information.

#### **B12.** CONFLICT OF INTEREST AND GOOD FAITH

- B12.1 Further to C3.2, Bidders, by responding to this Tender, declare that no Conflict of Interest currently exists, or is reasonably expected to exist in the future.
- B12.2 Conflict of Interest means any situation or circumstance where a Bidder or employee of the Bidder proposed for the Work has:
  - (a) other commitments;
  - (b) relationships;
  - (c) financial interests; or
  - (d) involvement in ongoing litigation;

that could or would be seen to:

- exercise an improper influence over the objective, unbiased and impartial exercise of the independent judgment of the City with respect to the evaluation of Bids or award of the Contract; or
- (ii) compromise, impair or be incompatible with the effective performance of a Bidder's obligations under the Contract.
- (e) has contractual or other obligations to the City that could or would be seen to have been compromised or impaired as a result of their participation in the Tender process or the Work; or
- (f) has knowledge of confidential information (other than confidential information disclosed by the City in the normal course of the Tender process) of strategic and/or material relevance to the Tender process or to the Work that is not available to other bidders and that could or would be seen to give that Bidder an unfair competitive advantage.
- B12.3 In connection with their Bid, each entity identified in B12.2 shall:
  - (a) avoid any perceived, potential or actual Conflict of Interest in relation to the procurement process and the Work;
  - (b) upon discovering any perceived, potential or actual Conflict of Interest at any time during the Tender process, promptly disclose a detailed description of the Conflict of Interest to the City in a written statement to the Contract Administrator; and
  - (c) provide the City with the proposed means to avoid or mitigate, to the greatest extent practicable, any perceived, potential or actual Conflict of Interest and shall submit any additional information to the City that the City considers necessary to properly assess the perceived, potential or actual Conflict of Interest.
- B12.4 Without limiting B12.3, the City may, in their sole discretion, waive any and all perceived, potential or actual Conflicts of Interest. The City's waiver may be based upon such terms and conditions as the City, in their sole discretion, requires to satisfy itself that the Conflict of Interest has been appropriately avoided or mitigated, including requiring the Bidder to put into place such policies, procedures, measures and other safeguards as may be required by and be acceptable to the City, in their sole discretion, to avoid or mitigate the impact of such Conflict of Interest.
- B12.5 Without limiting B12.3, and in addition to all contractual or other rights or rights at law or in equity or legislation that may be available to the City, the City may, in their sole discretion:

Bidding Procedures Page 6 of 9

The City of Winnipeg Tender No. 146-2024

Template Version: 2023 07 27 - Const noBidSecurity

- (a) disqualify a Bidder that fails to disclose a perceived, potential or actual Conflict of Interest of the Bidder or any of their employees proposed for the Work:
- (b) require the removal or replacement of any employees proposed for the Work that has a perceived, actual or potential Conflict of Interest that the City, in their sole discretion, determines cannot be avoided or mitigated;
- (c) disqualify a Bidder or employees proposed for the Work that fails to comply with any requirements prescribed by the City pursuant to B12.4 to avoid or mitigate a Conflict of Interest; and
- (d) disqualify a Bidder if the Bidder, or one of their employees proposed for the Work, has a perceived, potential or actual Conflict of Interest that, in the City's sole discretion, cannot be avoided or mitigated, or otherwise resolved.
- B12.6 The final determination of whether a perceived, potential or actual Conflict of Interest exists shall be made by the City, in their sole discretion.

#### **B13. QUALIFICATION**

- B13.1 The Bidder shall:
  - (a) undertake to be in good standing under The Corporations Act (Manitoba), or properly registered under The Business Names Registration Act (Manitoba), or otherwise properly registered, licensed or permitted by law to carry on business in Manitoba; and
  - (b) be financially capable of carrying out the terms of the Contract; and
  - (c) have all the necessary experience, capital, organization, and equipment to perform the Work in strict accordance with the terms and provisions of the Contract.
- B13.2 The Bidder and any proposed Subcontractor (for the portion of the Work proposed to be subcontracted to them) shall:
  - (a) be responsible and not be suspended, debarred or in default of any obligations to the City. A list of suspended or debarred individuals and companies is available on the Information Connection page at The City of Winnipeg, Corporate Finance, Materials Management Division website at https://www.winnipeg.ca/matmgt/Templates/files/debar.pdf
- B13.3 The Bidder and/or any proposed Subcontractor (for the portion of the Work proposed to be subcontracted to them) shall:
  - (a) have successfully carried out work similar in nature, scope and value to the Work;
  - (b) be fully capable of performing the Work required to be in strict accordance with the terms and provisions of the Contract;
  - (c) have a written workplace safety and health program if required pursuant to The Workplace Safety and Health Act (Manitoba);
  - (d) have completed the Accessible Customer Service online training required by the Accessibility for Manitobans Act (AMA) (see B13.5 and D7);
  - (e) have a valid Canadian Certified Playground Inspector.
- B13.4 Further to B13.3(c), the Bidder shall, within five (5) Business Days of a request by the Contract Administrator, provide proof satisfactory to the Contract Administrator that the Bidder/Subcontractor has a workplace safety and health program meeting the requirements of The Workplace Safety and Health Act (Manitoba), by providing:
  - (a) Written confirmation of a safety and health certification meeting SAFE Work Manitoba's SAFE Work Certified Standard (e.g., COR™ and SECOR™) or
    - (i) a copy of their valid Manitoba COR certificate and Letter of Good Standing (or Manitoba equivalency) as issued under the Certificate of Recognition (COR)
       Program administered by the Construction Safety Association of Manitoba or by the Manitoba Heavy Construction Association's WORKSAFELY™ COR™ Program; or

Bidding Procedures Page 7 of 9

The City of Winnipeg Tender No. 146-2024

Template Version: 2023 07 27 - Const noBidSecurity

- (ii) a copy of their valid Manitoba SECOR™ certificate and Letter of Good Standing (or Manitoba equivalency) as issued under the Small Employer Certificate of Recognition Program (SECOR™) administered by the Construction Safety Association of Manitoba or by the Manitoba Heavy Construction Association's WORKSAFELY™ COR™ Program; or
- (b) a report or letter to that effect from an independent reviewer acceptable to the City. (A list of acceptable reviewers and the review template are available on the Information Connection page at The City of Winnipeg, Corporate Finance, Materials Management Division website at <a href="http://www.winnipeg.ca/matmgt/">http://www.winnipeg.ca/matmgt/</a>.
- B13.5 Further to B13.3(d), the Bidder acknowledges they and all Subcontractors have obtained training required by the Accessibility for Manitobans Act (AMA) available at <a href="http://www.accessibilitymb.ca/training.html">http://www.accessibilitymb.ca/training.html</a> for anyone that may have any interaction with the public on behalf of the City of Winnipeg.
- B13.6 The Bidder shall submit, within three (3) Business Days of a request by the Contract Administrator, proof satisfactory to the Contract Administrator of the qualifications of the Bidder and of any proposed Subcontractor.
- B13.7 The Bidder shall provide, on the request of the Contract Administrator, full access to any of the Bidder's equipment and facilities to confirm, to the Contract Administrator's satisfaction, that the Bidder's equipment and facilities are adequate to perform the Work.

#### B14. OPENING OF BIDS AND RELEASE OF INFORMATION

- B14.1 Bids will not be opened publicly.
- B14.2 Following the submission deadline, the names of the Bidders and their Total Bid Prices (unevaluated, and pending review and verification of conformance with requirements) will be available on the MERX website at <a href="https://www.merx.com">www.merx.com</a>.
- B14.3 After award of Contract, the name(s) of the successful Bidder(s) and their Contract amount(s) will be available on the MERX website at www.merx.com.
- B14.4 The Bidder is advised that any information contained in any Bid may be released if required by The Freedom of Information and Protection of Privacy Act (Manitoba), by other authorities having jurisdiction, or by law or by City policy or procedures (which may include access by members of City Council).
- B14.4.1 To the extent permitted, the City shall treat as confidential information, those aspects of a Bid Submission identified by the Bidder as such in accordance with and by reference to Part 2, Section 17 or Section 18 or Section 26 of The Freedom of Information and Protection of Privacy Act (Manitoba), as amended.

#### **B15.** IRREVOCABLE BID

- B15.1 The Bid(s) submitted by the Bidder shall be irrevocable for the time period specified in Paragraph 11 of Form A: Bid/Proposal.
- B15.2 The acceptance by the City of any Bid shall not release the Bids of the next two lowest evaluated responsive Bidders and these Bidders shall be bound by their Bids on such Work for the time period specified in Paragraph 11 of Form A: Bid/Proposal.

#### **B16. WITHDRAWAL OF BIDS**

B16.1 A Bidder may withdraw their Bid without penalty prior to the Submission Deadline.

Bidding Procedures Page 8 of 9

Template Version: 2023 07 27 - Const noBidSecurity

#### **B17.** EVALUATION OF BIDS

- B17.1 Award of the Contract shall be based on the following bid evaluation criteria:
  - (a) compliance by the Bidder with the requirements of the Tender or acceptable deviation there from (pass/fail);
  - (b) qualifications of the Bidder and the Subcontractors, if any, pursuant to B13 (pass/fail);
  - (c) Total Bid Price;
  - (d) economic analysis of any approved alternative pursuant to B7.
- B17.2 Further to B17.1(a), the Award Authority may reject a Bid as being non-responsive if the Bid is incomplete, obscure or conditional, or contains additions, deletions, alterations or other irregularities. The Award Authority may reject all or any part of any Bid, or waive technical requirements or minor informalities or irregularities, if the interests of the City so require.
- B17.3 Further to B17.1(b), the Award Authority shall reject any Bid submitted by a Bidder who does not demonstrate, in their Bid or in other information required to be submitted, that they are qualified.
- B17.4 Further to B17.1(c) the Award Authority may reject a Bid as being non-responsive if it exceeds the funds available as shown in D2.3.
- B17.5 Further to B17.1(c), the Total Bid Price shall be the sum of the quantities multiplied by the unit prices for each item shown on Form B: Prices.
- B17.5.1 Further to B17.1(a), in the event that a unit price is not provided on Form B: Prices, the City may determine the unit price by dividing the Amount (extended price) by the approximate quantity, for the purposes of evaluation and payment.
- B17.5.2 Bidders are advised that the calculation indicated in B17.5 will prevail over the Total Bid Price entered in MERX.

#### **B18.** AWARD OF CONTRACT

- B18.1 The City will give notice of the award of the Contract or will give notice that no award will be made
- B18.2 The City will have no obligation to award a Contract to a Bidder, even though one or all of the Bidders are determined to be qualified, and the Bids are determined to be responsive.
- B18.2.1 Without limiting the generality of B18.2, the City will have no obligation to award a Contract where:
  - (a) the prices exceed the available City funds for the Work;
  - (b) the prices are materially in excess of the prices received for similar work in the past;
  - (c) the prices are materially in excess of the City's cost to perform the Work, or a significant portion thereof, with their own forces;
  - (d) only one Bid is received; or
  - (e) in the judgment of the Award Authority, the interests of the City would best be served by not awarding a Contract.
- B18.3 If funding for the Work is provided to the City of Winnipeg by the Government of Manitoba and/or the Government of Canada, Bidders are advised that the terms of D28 shall immediately take effect upon confirmation of such funding, regardless of when funding is confirmed.
- B18.4 Where an award of Contract is made by the City, the award shall be made to the qualified Bidder submitting the lowest evaluated responsive Bid, in accordance with B17.

The City of Winnipeg
Tender No. 146-2024
Bidding Procedures
Page 9 of 9

Template Version: 2023 07 27 - Const noBidSecurity

B18.5 Further to Paragraph 7 of Form A: Bid/Proposal and C4, the City may issue a purchase order to the successful Bidder in lieu of the execution of a Contract.

- B18.5.1 The Contract Documents, as defined in C1.1(p), in their entirety shall be deemed to be incorporated in and to form a part of the purchase order notwithstanding that they are not necessarily attached to or accompany said purchase order.
- B18.6 Following the award of contract, a Bidder will be provided with information related to the evaluation of their Bid upon written request to the Contract Administrator.

#### **PART C - GENERAL CONDITIONS**

#### CO. GENERAL CONDITIONS

- C0.1 The *General Conditions for Construction* (Revision 2020-01-31) are applicable to the Work of the Contract.
- C0.1.1 The General Conditions for Construction are available on the Information Connection page at The City of Winnipeg, Corporate Finance, Materials Management Division website at <a href="http://www.winnipeg.ca/matmgt/gen.cond.stm">http://www.winnipeg.ca/matmgt/gen.cond.stm</a>
- C0.2 A reference in the Tender to a section, clause or subclause with the prefix "C" designates a section, clause or subclause in the *General Conditions for Construction*.

#### **PART D - SUPPLEMENTAL CONDITIONS**

#### **GENERAL**

#### D1. GENERAL CONDITIONS

D1.1 In addition to the *General Conditions for Construction*, these Supplemental Conditions are applicable to the Work of the Contract.

#### D2. SCOPE OF WORK

- D2.1 The Work to be done under the Contract shall consist of supply and install of play equipment c/w Engineered Wood Fiber safety surface and concrete edging, supply and install of picnic shelter, installation of site furniture, and scraping and resurfacing existing granular path with asphalt.
- D2.2 The major components of the Work are as follows:
  - (a) Excavation and site grading;
  - (b) Poligon picnic structure;
  - (c) CIP concrete play edging;
  - (d) Specified play equipment;
  - (e) Engineered wood fibre safety surfacing;
  - (f) Asphalt pathway;
  - (g) Site furniture, and;
  - (h) Soil and sod.
- D2.3 The funds available for this contract are \$383,000.

#### D3. SITE INVESTIGATION DUE DILIGENCE AND RISK

- D3.1 Notwithstanding C3.1, the Contractor acknowledges that the site investigation reports and other site information included in this Tender have been provided to it and may be relied upon by the Contractor to the extent that the Contractor uses Good Industry Practice in interpreting such report(s) and site information and carries out the Work in accordance with Good Industry Practice based upon such report(s) and the information contained in them and such other site information. In the event that a site condition related to:
  - (a) the location of any utility which can be determined from the records or other information available at the offices of any public authority or person, including a municipal corporation and any board or commission thereof, having jurisdiction or control over the utility;
  - (b) the Site conditions, including but not limited to subsurface hazardous materials or other concealed physical conditions;
  - (c) the location, nature, quality or quantity of the materials to be removed or to be employed in the performance of the Work;
  - (d) the nature, quality or quantity of the Plant needed to perform the Work;
  - (e) all matters concerning access to the Site, power supplies, location of existing services, utilities or materials necessary for the completion of the Work; and
  - (f) all other matters which could in any way affect the performance of the Work;

that could not have been "properly inferable", "readily apparent" and readily discoverable" using Good Industry Practice by the Contractor, results in additional Work which is a direct result of this newly discovered site condition, such additional Work will be considered by the City under Changes in Work.

Supplemental Conditions Page 2 of 22

The City of Winnipeg Tender No. 146-2024

Template Version: 2023 07 27 - Const noBidSecurity

#### D4. DEFINITIONS

- D4.1 When used in this Tender:
  - (a) "Supply Chain Disruption" means an inability by the Contractor to obtain goods or services from third parties necessary to perform the Work of the Contract within the schedule specified therein, despite the Contractor making all reasonable commercial efforts to procure same. Contractors are advised that increased costs do not, in and of themselves, amount to a Supply Chain Disruption;
  - (b) "CW" means current City of Winnipeg Standard Construction Specification;
  - (c) "SD" means current City of Winnipeg Standard Construction Detail; and
  - (d) **"SCD"** means current City of Winnipeg Parks Planning Standard Construction Detail Drawings.

#### D5. CONTRACT ADMINISTRATOR

D5.1 The Contract Administrator is:

lan Macdonald Urban Designer

Telephone No. 204 451-3069

Email Address imacdonald@winnipeg.ca

D5.2 At the pre-construction meeting, the Contract Administrator will identify additional personnel representing the Contract Administrator and their respective roles and responsibilities for the Work.

#### D6. CONTRACTOR'S SUPERVISOR

D6.1 At the pre-construction meeting, the Contractor shall identify their designated supervisor and any additional personnel representing the Contractor and their respective roles and responsibilities for the Work.

#### D7. ACCESSIBLE CUSTOMER SERVICE REQUIREMENTS

- D7.1 The Accessibility for Manitobans Act (AMA) imposes obligations on The City of Winnipeg to provide accessible customer service to all persons in accordance with the Customer Service Standard Regulation ("CSSR") to ensure inclusive access and participation for all people who live, work or visit Winnipeg regardless of their abilities.
- D7.1.1 The Contractor agrees to comply with the accessible customer service obligations under the CSSR and further agrees that when providing the Goods or Services or otherwise acting on the City of Winnipeg's behalf, shall comply with all obligations under the AMA applicable to public sector bodies.
- D7.1.2 The accessible customer service obligations include, but are not limited to:
  - (a) providing barrier-free access to goods and services;
  - (b) providing reasonable accommodations;
  - (c) reasonably accommodating assistive devices, support persons, and support animals;
  - (d) providing accessibility features e.g. ramps, wide aisles, accessible washrooms, power doors and elevators;
  - (e) inform the public when accessibility features are not available;
  - (f) providing a mechanism or process for receiving and responding to public feedback on the accessibility of all goods and services; and
  - (g) providing adequate training of staff and documentation of same.

#### D8. UNFAIR LABOUR PRACTICES

- D8.1 Further to C3.2, the Contractor declares that in bidding for the Work and in entering into this Contract, the Contractor and any proposed Subcontractor(s) conduct their respective business in accordance with established international codes embodied in United Nations Universal Declaration of Human Rights (UDHR) <a href="https://www.un.org/en/about-us/universal-declaration-of-human-rights">https://www.un.org/en/about-us/universal-declaration-of-human-rights</a> International Labour Organization (ILO) <a href="https://www.ilo.org/global/lang-en/index.htm">https://www.ilo.org/global/lang-en/index.htm</a> conventions as ratified by Canada.
- D8.2 The City of Winnipeg is committed and requires its Contractors and their Subcontractors, to be committed to upholding and promoting international human and labour rights, including fundamental principles and rights at work covered by ILO eight (8) fundamental conventions and the United Nations Universal Declaration of Human Rights which includes child and forced labour.
- D8.3 Upon request from the Contract Administrator, the Contractor shall provide disclosure of the sources (by company and country) of the raw materials used in the Work and a description of the manufacturing environment or processes (labour unions, minimum wages, safety, etc.).
- D8.4 Failure to provide the evidence required under D8.3, may be determined to be an event of default in accordance with C18.
- D8.5 In the event that the City, in its sole discretion, determines the Contractor to have violated the requirements of this section, it will be considered a fundamental breach of the Contract and the Contractor shall pay to the City a sum specified by the Contract Administrator in writing ("Unfair Labour Practice Penalty"). Such a violation shall also be considered an Event of Default, and shall entitle the City to pursue all other remedies it is entitled to in connection with same pursuant to the Contract.
- D8.5.1 The Unfair Labour Practice Penalty shall be such a sum as determined appropriate by the City, having due regard to the gravity of the Contractor's violation of the above requirements, any cost of obtaining replacement goods/ services or rectification of the breach, and the impact upon the City's reputation in the eyes of the public as a result of same.
- D8.5.2 The Contractor shall pay the Unfair Labour Practice Penalty to the City within thirty (30) Calendar Days of receiving a demand for same in accordance with D8.5. The City may also hold back the amount of the Unfair Labour Practice Penalty from payment for any amount it owes the Contractor.
- D8.5.3 The obligations and rights conveyed by this clause survive the expiry or termination of this Contract, and may be exercised by the City following the performance of the Work, should the City determine, that a violation by the Contractor of the above clauses has occurred following same. In no instance shall the Unfair Labour Practice Penalty exceed the total of twice the Contract value.

#### **SUBMISSIONS**

#### D9. AUTHORITY TO CARRY ON BUSINESS

D9.1 The Contractor shall be in good standing under The Corporations Act (Manitoba), or properly registered under The Business Names Registration Act (Manitoba), or otherwise properly registered, licensed or permitted by law to carry on business in Manitoba, or if the Contractor does not carry on business in Manitoba, in the jurisdiction where the Contractor does carry on business, throughout the term of the Contract, and shall provide the Contract Administrator with evidence thereof upon request.

#### D10. SAFE WORK PLAN

- D10.1 The Contractor shall provide the Contract Administrator with a Safe Work Plan at least five (5) Business Days prior to the commencement of any Work on the Site but in no event later than the date specified in C4.1 for the return of the executed Contract Documents, if applicable.
- D10.2 The Safe Work Plan should be prepared and submitted in the format shown in the City's template which is available on the Information Connection page at The City of Winnipeg, Corporate Finance, Materials Management Division website at <a href="http://www.winnipeg.ca/matmgt/Safety/default.stm">http://www.winnipeg.ca/matmgt/Safety/default.stm</a>
- D10.3 Notwithstanding B13.4 at any time during the term of the Contract, the City may, at their sole discretion and acting reasonably, require an updated COR Certificate or Annual Letter of good Standing. A Contractor, who fails to provide a satisfactory COR Certificate or Annual Letter of good Standing, will not be permitted to continue to perform any Work.

#### D11. INSURANCE

- D11.1 The Contractor shall provide and maintain the following insurance coverage:
  - (a) commercial general liability insurance, in the amount of at least two million dollars (\$2,000,000.00) inclusive, with The City of Winnipeg, Manitoba, its Ministers, officers, employees and agents to be added as additional insureds, with a cross-liability clause, such liability policy to also contain contractual liability, unlicensed motor vehicle liability, non-owned automobile liability and products and completed operations, to remain in place at all times during the performance of the Work and throughout the warranty period;
  - (b) Automobile Liability Insurance covering all motor vehicles, owned and operated and used or to be used by the Contractor directly or indirectly in the performance of the Work. The Limit of Liability shall not be less than \$5,000,000 inclusive for loss or damage including personal injuries and death resulting from any one accident or occurrence;
  - (c) all risks installation floater, carrying adequate limits to cover all machinery, equipment, supplies and/or materials intended to enter into and form part of any installation.
- D11.2 Deductibles shall be borne by the Contractor.
- D11.3 All policies shall be taken out with insurers licensed in the Province of Manitoba.
- D11.4 The Contractor shall provide the Contract Administrator with a certificate(s) of insurance, referencing the Tender number and/or the Scope of Work D2 and Specifications PART E to be performed, in a form satisfactory to the City Solicitor, at least two (2) Business Days prior to the commencement of any Work but in no event later than seven (7) Calendar Days from notification of the award of Contract by Purchase Order.
- D11.5 The Contractor shall not cancel, materially alter, or cause each policy to lapse without providing at least thirty (30) Calendar Days prior written notice to the Contract Administrator.

#### D12. CONTRACT SECURITY

- D12.1 If the Contract Price exceeds twenty-five thousand dollars (\$25,000.00), the Contractor shall provide and maintain contract security until the expiration of the warranty period in the form of:
  - (a) a performance bond of a company registered to conduct the business of a surety in Manitoba, in the form attached to these Supplemental Conditions (Form H1: Performance Bond), in the amount of fifty percent (50%) of the Contract Price; and
  - (b) a labour and material payment bond of a company registered to conduct the business of a surety in Manitoba, in the form attached to these Supplemental Conditions (Form H2: Labour and Material Payment Bond), in an amount equal to fifty percent (50%) of the Contract Price; or

- (c) an irrevocable standby letter of credit issued by a bank or other financial institution registered to conduct business in Manitoba and drawn on a branch located in Winnipeg, in the form attached to these Supplemental Conditions (Form H3: Irrevocable Standby Letter of Credit), in the amount of fifty percent (50%) of the Contract Price; or
- (d) a certified cheque or draft payable to "The City of Winnipeg", drawn on a bank or other financial institution registered to conduct business in Manitoba, in the amount of fifty percent (50%) of the Contract Price.
- D12.1.1 Where the contract security is a performance bond, it may be submitted in hard copy or digital format. If submitted in digital format the contract security must meet the following criteria:
  - (a) the version submitted by the Contractor must have valid digital signatures and seals;
  - (b) the version submitted by the Contractor must be verifiable by the City with respect to the totality and wholeness of the bond form, including: the content; all digital signatures and digital seals; with the surety company, or an approved verification service provider of the surety company.
  - (c) the version submitted must be viewable, printable and storable in standard electronic file formats compatible with the City, and in a single file. Allowable formats include pdf.
  - (d) the verification may be conducted by the City immediately or at any time during the life of the bond and at the discretion of the City with no requirement for passwords or fees.
  - (e) the results of the verification must provide a clear, immediate and printable indication of pass or fail regarding D12.1.1(b).
- D12.1.2 Digital bonds failing the verification process will not be considered to be valid and may be determined to be an event of default in accordance with C18.1. If a digital bond fails the verification process, the Contractor may provide a replacement bond (in hard copy or digital format) within seven (7) Calendar Days of the City's request or within such greater period of time as the City in their discretion, exercised reasonably, allows.
- D12.1.3 Digital bonds passing the verification process will be treated as original and authentic.
- D12.1.4 Where the contract security is in the form of a certified cheque or draft, it will be deposited by the City. The City will not pay any interest on certified cheques or drafts furnished as contract security.
- D12.2 The Contractor shall provide the Contract Administrator identified in D5 with the required contract security within seven (7) Calendar Days of notification of the award of the Contract by way of Purchase Order or an award letter and prior to the commencement of any Work on the Site but in no event later than the date specified in C4.1 for the return of the executed Contract Documents, if applicable.
- D12.3 Where the Contract Security is provided in accordance with D12.1(a) and D12.1(b), the Contractor shall, as soon as practicable after entering into a contract with a Subcontractor:
  - (a) give the Subcontractor written notice of the existence of the labour and material payment bond in D12.1(b); and
  - (b) post a notice of the bond and/or a copy of that bond in a conspicuous location at the Site of the Work.

#### D13. SUBCONTRACTOR LIST

D13.1 The Contractor shall provide the Contract Administrator with a complete list of the Subcontractors whom the Contractor proposes to engage (Form J: Subcontractor List) at least two (2) Business Days prior to the commencement of any Work on the Site but in no event later than seven (7) Calendar Days from notification of the award of Contract.

Supplemental Conditions Page 6 of 22

Template Version: 2023 07 27 - Const noBidSecurity

#### D14. DETAILED WORK SCHEDULE

- D14.1 The Contractor shall provide the Contract Administrator with a detailed work schedule (Form L: Detailed Work Schedule) at least two (2) Business Days prior to the commencement of any Work on the Site but in no event later than the date specified in C4.1 for the return of the executed Contract Documents, if applicable.
- D14.2 The detailed work schedule shall consist of the following:
  - (a) Start date;
  - (b) Excavation for play area and pathways;
  - (c) Rough Grading;
  - (d) Installation of sub-surface drainage;
  - (e) Installation of play edging;
  - (f) Installation of play equipment;
  - (g) Installation of safety surfacing;
  - (h) Installation of pathways and seating areas;
  - (i) Installation of site furniture;
  - (j) Installation of piles;
  - (k) Installation of Shade Shelter;
  - (I) Installation of soil and sod; and
  - (m) Expected completion.

all acceptable to the Contract Administrator.

#### **SCHEDULE OF WORK**

#### D15. COMMENCEMENT

- D15.1 The Contractor shall not commence any Work until they are in receipt of a Purchase Order from the Award Authority authorizing the commencement of the Work.
- D15.2 The Contractor shall not commence any Work on the Site until:
  - (a) the Contract Administrator has confirmed receipt and approval of:
    - (i) evidence of authority to carry on business specified in D9;
    - (ii) evidence of the workers compensation coverage specified in C6.15;
    - (iii) the Safe Work Plan specified inD10;
    - (iv) evidence of the insurance specified in D11;
    - (v) the contract security specified in D12;
    - (vi) the Subcontractor list specified in D13;
    - (vii) the detailed work schedule specified in D14; and
    - (viii) the direct deposit application form specified in D24.
  - (b) the Contractor has attended a pre-construction meeting with the Contract Administrator, or the Contract Administrator has waived the requirement for a pre-construction meeting.
- D15.3 The Contractor shall order play equipment and shelter within seven (7) Working Days of receipt of the Purchase Order.
- D15.4 The Contractor shall commence the Work on the Site within forty-two (42) Working Days of receipt of the Purchase Order.

Supplemental Conditions Page 7 of 22

Template Version: 2023 07 27 - Const noBidSecurity

#### D16. SUBSTANTIAL PERFORMANCE

- D16.1 The Contractor shall achieve Substantial Performance within twenty-five (25) consecutive Working Days of the commencement of the Work as specified in D15.
- D16.2 When the Contractor considers the Work to be substantially performed, the Contractor shall arrange, attend and assist in the inspection of the Work with the Contract Administrator for purposes of verifying Substantial Performance. Any defects or deficiencies in the Work noted during that inspection shall be remedied by the Contractor at the earliest possible instance and the Contract Administrator notified so that the Work can be reinspected.
- D16.3 The date on which the Work has been certified by the Contract Administrator as being substantially performed to the requirements of the Contract through the issue of a certificate of Substantial Performance is the date on which Substantial Performance has been achieved.

#### D17. TOTAL PERFORMANCE

- D17.1 The Contractor shall achieve Total Performance within thirty (30) consecutive Working Days of the commencement of the Work as specified in D15.
- D17.2 When the Contractor or the Contract Administrator considers the Work to be totally performed, the Contractor shall arrange, attend and assist in the inspection of the Work with the Contract Administrator for purposes of verifying Total Performance. Any defects or deficiencies in the Work noted during that inspection shall be remedied by the Contractor at the earliest possible instance and the Contract Administrator notified so that the Work can be reinspected.
- D17.3 The date on which the Work has been certified by the Contract Administrator as being totally performed to the requirements of the Contract through the issue of a certificate of Total Performance is the date on which Total Performance has been achieved.

#### D18. LIQUIDATED DAMAGES

- D18.1 If the Contractor fails to achieve Substantial Performance in accordance with the Contract by the day fixed herein for Substantial Performance, the Contractor shall pay the City five-hundred dollars (\$500) per Working Day for each and every Working Day following the day fixed herein for Substantial Performance during which such failure continues.
- D18.2 The amount specified for liquidated damages in D18.1 is based on a genuine pre-estimate of the City's damages in the event that the Contractor does not achieve Substantial Performance by the day fixed herein for same.
- D18.3 The City may reduce any payment to the Contractor by the amount of any liquidated damages assessed.

#### D19. SUPPLY CHAIN DISRUPTION SCHEDULE DELAYS

- D19.1 The City acknowledges that the schedule for this Contract may be impacted by the Supply Chain Disruption. Commencement and progress of the Work shall be performed by the Contractor with due consideration to the delivery requirements and schedule identified in the Contract, in close consultation with the Contract Administrator.
- D19.2 If the Contractor is delayed in the performance of the Work by reason of the Supply Chain Disruption, the Work schedule may be adjusted by a period of time equal to the time lost due to such delay and costs related to such delay will be determined as identified herein.
- D19.3 A minimum of seven (7) Calendar Days prior to the commencement of Work, the Contractor shall declare whether a Supply Chain Disruption will affect the start date. The Contractor shall provide sufficient evidence that the delay is directly related to a Supply Chain Disruption, including but not limited to evidence related to ordering of Material or Goods, production and/or manufacturing schedules or availability of staff as appropriate.

Supplemental Conditions Page 8 of 22

The City of Winnipeg Tender No. 146-2024

Template Version: 2023 07 27 - Const noBidSecurity

- D19.4 For any delay related to Supply Chain Disruption and identified after Work has commenced, the Contractor shall within seven (7) Calendar Days of becoming aware of the anticipated delay declare the additional delay and shall provide sufficient evidence as indicated in D19.3. Failure to provide this notice will result in no additional time delays being considered by the City.
- D19.5 The Work schedule, including the durations identified in D16 to D17 where applicable, will be adjusted to reflect delays accepted by the Contract Administrator. No additional payment will be made for adjustment of schedules except where seasonal work, not previously identified in the Contract, is carried over to the following construction season.
- D19.6 Where Work not previously identified is being carried over solely as a result of delays related to Supply Chain Disruption, as confirmed by the Contract Administrator, the cost of temporary works to maintain the Work in a safe manner until Work recommences, will be considered by the Contract Administrator. Where the Work is carried over only partially due to Supply Chain Disruption, a partial consideration of the cost of temporary works will be considered by the Contract Administrator.
- D19.7 Any time or cost implications as a result of Supply Chain Disruption and in accordance with the above, as confirmed by the Contract Administrator, shall be documented in accordance with C7.

#### D20. SCHEDULED MAINTENANCE

- D20.1 The Contractor shall perform the following scheduled maintenance in the manner and within the time periods required by the Specifications:
  - (a) Sod as specified in E16.
- D20.2 Determination of Substantial Performance and Total Performance shall be exclusive of scheduled maintenance identified herein. All scheduled maintenance shall be completed prior to the expiration of the warranty period. Where the scheduled maintenance cannot be completed during the warranty period, the warranty period shall be extended for such period of time as it takes the Contractor to complete the scheduled maintenance.

#### **CONTROL OF WORK**

#### D21. JOB MEETINGS

- D21.1 Regular weekly job meetings will be held at the Site. These meetings shall be attended by a minimum of one representative of the Contract Administrator, one representative of the City and one representative of the Contractor. Each representative shall be a responsible person capable of expressing the position of the Contract Administrator, the City and the Contractor respectively on any matter discussed at the meeting including the Work schedule and the need to make any revisions to the Work schedule. The progress of the Work will be reviewed at each of these meetings.
- D21.2 The Contract Administrator reserves the right to cancel any job meeting or call additional job meetings whenever they deem it necessary.

#### D22. PRIME CONTRACTOR - THE WORKPLACE SAFETY AND HEALTH ACT (MANITOBA)

D22.1 Further to C6.26, the Contractor shall be the Prime Contractor and shall serve as, and have the duties of the Prime Contractor in accordance with The Workplace Safety and Health Act (Manitoba).

#### D23. THE WORKPLACE SAFETY AND HEALTH ACT (MANITOBA) - QUALIFICATIONS

D23.1 Further to B13.4, the Contractor/Subcontractor must, throughout the term of the Contract, have a Workplace Safety and Health Program meeting the requirements of The Workplace Safety

and Health Act (Manitoba). At any time during the term of the Contract, the City may, at their sole discretion and acting reasonably, require updated proof of compliance, as set out in B13.4.

#### **MEASUREMENT AND PAYMENT**

#### D24. PAYMENT

D24.1 Further to C12, the City shall make payments to the Contractor by direct deposit to the Contractor's banking institution, and by no other means. Payments will not be made until the Contractor has made satisfactory direct deposit arrangements with the City. Direct deposit application forms are at <a href="https://winnipeg.ca/finance/files/Direct\_Deposit\_Form.pdf">https://winnipeg.ca/finance/files/Direct\_Deposit\_Form.pdf</a>

#### **WARRANTY**

#### D25. WARRANTY

- D25.1 Warranty is as stated in C13.
- D25.1 Notwithstanding C13.2, the warranty period shall begin on the date of Total Performance and shall expire two (2) years thereafter unless extended pursuant to C13.2.1 or C13.2.2, in which case it shall expire when provided for thereunder.
- D25.2 Notwithstanding C13.2 or D25.1, the Contract Administrator may permit the warranty period for a portion or portions of the Work to begin prior to the date of Total Performance if:
  - (a) a portion of the Work cannot be completed because of unseasonable weather or other conditions reasonably beyond the control of the Contractor but that portion does not prevent the balance of the Work from being put to its intended use.
- D25.2.1 In such case, the date specified by the Contract Administrator for the warranty period to begin shall be substituted for the date specified in C13.2 for the warranty period to begin.

#### **DISPUTE RESOLUTION**

#### D26. DISPUTE RESOLUTION

- D26.1 If the Contractor disagrees with any opinion, determination, or decision of the Contract Administrator, the Contractor shall act in accordance with the Contract Administrator's opinion, determination, or decision unless and until same is modified by the process followed by the parties pursuant to D26.
- D26.2 The entire text of C21.4 is deleted, and amended to read: "Intentionally Deleted"
- D26.3 The entire text of C21.5 is deleted, and amended to read:
  - (a) If Legal Services has determined that the Disputed Matter may proceed in the Appeal Process, the Contractor must, within ten (10) Business Days of the date of the Legal Services Response Letter, submit their written Appeal Form, in the manner and format set out on the City's Materials Management Website, to the Chief Administrative Officer, and to the Contract Administrator. The Contractor may not raise any other disputes other than the Disputed Matter in their Appeal Form.
- D26.4 Further to C21, prior to the Contract Administrator's issuance of a Final Determination, the following informal dispute resolution process shall be followed where the Contractor disagrees with any opinion, determination, or decision of the Contract Administrator ("Dispute"):
  - (a) In the event of a Dispute, attempts shall be made by the Contract Administrator and the Contractor's equivalent representative to resolve Disputes within the normal course of project dealings between the Contract Administrator and the Contractor's equivalent representative.

Supplemental Conditions Page 10 of 22

Template Version: 2023 07 27 - Const noBidSecurity

- (b) Disputes which in the reasonable opinion of the Contract Administrator or the Contractor's equivalent representative cannot be resolved within the normal course of project dealings as described above shall be referred to a without prejudice escalating negotiation process consisting of, at a minimum, the position levels as shown below and the equivalent Contractor representative levels:
  - (i) The Contract Administrator;
  - (ii) Supervisory level between the Contract Administrator and applicable Department Head;
  - (iii) Department Head.
- D26.4.1 Names and positions of Contractor representatives equivalent to the above City position levels shall be determined by the Contractor and communicated to the City at the precommencement or kick off meeting.
- D26.4.2 As these negotiations are not an adjudicative hearing, neither party may have legal counsel present during the negotiations.
- D26.4.3 Both the City and the Contractor agree to make all reasonable efforts to conduct the above escalating negotiation process within twenty (20) Business Days, unless both parties agree, in writing, to extend that period of time.
- D26.4.4 If the Dispute is not resolved to the City and Contractor's mutual satisfaction after discussions have occurred at the final escalated level as described above, or the time period set out in D26.4.3, as extended if applicable, has elapsed, the Contract Administrator will issue a Final Determination as defined in C1.1(v), at which point the parties will be governed by the Dispute Resolution process set out in C21.

#### INDEMNITY

#### D27. INDEMNITY

- D27.1 Indemnity shall be as stated in C17.
- D27.2 Notwithstanding C17.1, the Contractor shall save harmless and indemnify the City in the amount of twice the Contract Price or five million dollars (\$5,000,000), whichever is greater, against all costs, damages or expenses arising from actions, claims, demands and proceedings, by whomsoever brought, made or taken as a result of negligent acts or negligent omissions of the Contractor, their Subcontractors, employees or agents in the performance or purported performance of the Work, and more particularly from:
  - (a) accidental injury to or death of any person whether retained by or in the employ of the contractor or not, arising directly or indirectly by reason of the performance of the Work, or by reason of any trespass on or damage to property;
  - (b) damage to any property owned in whole or in part by the City, or which the City by duty or custom is obliged, directly or indirectly, in any way or to any degree, to construct, repair or maintain:
  - (c) damage to, or trespass or encroachment upon, property owned by persons other than the City;
  - (d) any claim for lien or trust claim served upon the City pursuant to The Builders' Liens Act;
  - (e) failure to pay a Workers Compensation assessment, or Federal or Provincial taxes;
  - (f) unauthorized use of any design, device, material or process covered by letters patent, copyright, trademark or trade name in connection with the Work;
  - (g) inaccuracies in any information provided to the City by the Contractor.
- D27.3 Further to C17, The City shall save harmless and indemnify the Contractor in the amount of twice the Contract Price or five million dollars (\$5,000,000), whichever is greater, against all costs, damages or expenses arising from actions, claims, demands and proceedings, by

whomsoever brought, made or taken as a result of negligent acts or negligent omissions of the City, their employees or agents in the performance of its obligation under the Contract.

#### THIRD PARTY AGREEMENTS

#### D28. FUNDING AND/OR CONTRIBUTION AGREEMENT OBLIGATIONS

- D28.1 In the event that funding for the Work of the Contract is provided to the City of Winnipeg by the Government of Manitoba and/or the Government of Canada, the following terms and conditions shall apply, as required by the applicable funding agreements.
- D28.2 Further to D28.1, in the event that the obligations in D28 apply, actual costs legitimately incurred by the Contractor as a direct result of these obligations ("Funding Costs") shall be determined by the actual cost to the Contractor and not by the valuation method(s) outlined in C7.4. In all other respects Funding Costs will be processed in accordance with Changes in Work under C7.
- D28.3 For the purposes of D28:
  - (a) "Government of Canada" includes the authorized officials, auditors, and representatives of the Government of Canada; and
  - (b) "Government of Manitoba" includes the authorized officials, auditors, and representatives of the Government of Manitoba.
- D28.4 Modified Insurance Requirements
- D28.4.1 If not already required under the insurance requirements identified in D11, the Contractor will be required to provide wrap-up liability insurance in an amount of no less than two million dollars (\$2,000,000) inclusive per occurrence. Such policy will be written in the joint names of the City, Contractor, Consultants and all sub-contractors and sub-consultants and include twelve (12) months completed operations. The Government of Manitoba and their Ministers, officers, employees, and agents shall be added as additional insureds.
- D28.4.2 If not already required under the insurance requirements identified in D11, the Contractor will be required to provide builders' risk insurance (including boiler and machinery insurance, as applicable) providing all risks coverage at full replacement cost, or such lower level of insurance that the City may identify on a case-by-case basis, such as an installation floater.
- D28.4.3 The Contractor shall obtain and maintain third party liability insurance with minimum coverage of two million dollars (\$2,000,000.00) per occurrence on all licensed vehicles operated at the Site. In the event that this requirement conflicts with another licensed vehicle insurance requirement in this Contract, then the requirement that provides the higher level of insurance shall apply.
- D28.4.4 Further to D11.3, insurers shall provide satisfactory Certificates of Insurance to the Government of Manitoba prior to commencement of Work as written evidence of the insurance required. The Certificates of Insurance must provide for a minimum of thirty (30) days' prior written notice to the Government of Manitoba in case of insurance cancellation.
- D28.4.5 All policies must be taken out with insurers licensed to carry on business in the Province of Manitoba.
- D28.5 Indemnification By Contractor
- D28.5.1 In addition to the indemnity obligations outlined in C17 of the General Conditions for Construction, the Contractor agrees to indemnify and save harmless the Government of Canada and the Government of Manitoba and each of their respective Ministers, officers, servants, employees, and agents from and against all claims and demands, losses, costs, damages, actions, suit or other proceedings brought or pursued in any manner in respect of any matter caused by the Contractor or arising from this Contract or the Work, or from the goods or services provided or required to be provided by the Contractor, except those

resulting from the negligence of any of the Government of Canada's or the Government of Manitoba's Ministers, officers, servants, employees, or agents, as the case may be.

- D28.5.2 The Contractor agrees that in no event will Canada or Manitoba, their respective officers, servants, employees or agents be held liable for any damages in contract, tort (including negligence) or otherwise, for:
  - (a) any injury to any person, including, but not limited to, death, economic loss or infringement of rights;
  - (b) any damage to or loss or destruction of property of any person; or
  - (c) any obligation of any person, including, but not limited to, any obligation arising from a loan, capital lease or other long term obligation;

in relation to this Contract or the Work.

#### D28.6 Records Retention and Audits

- D28.6.1 The Contractor shall maintain and preserve accurate and complete records in respect of this Contract and the Work, including all accounting records, financial documents, copies of contracts with other parties and other records relating to this Contract and the Work during the term of the Contract and for at least six (6) years after Total Performance. Those records bearing original signatures or professional seals or stamps must be preserved in paper form; other records may be retained in electronic form.
- D28.6.2 In addition to the record keeping and inspection obligations outlined in C6 of the General Conditions for Construction, the Contractor shall keep available for inspection and audit at all reasonable times while this Contract is in effect and until at least six (6) years after Total Performance, all records, documents, and contracts referred to in D28.6.1 for inspection, copying and audit by the City of Winnipeg, the Government of Manitoba and/or the Government of Canada and their respective representatives and auditors, and to produce them on demand; to provide reasonable facilities for such inspections, copying and audits, to provide copies of and extracts from such records, documents, or contracts upon request by the City of Winnipeg, the Government of Manitoba, and/or the Government of Canada and their respective representatives and auditors, and to promptly provide such other information and explanations as may be reasonably requested by the City of Winnipeg, the Government of Manitoba, and/or the Government of Canada from time-to-time.

#### D28.7 Other Obligations

- D28.7.1 The Contractor consents to the City providing a copy of the Contract Documents to the Government of Manitoba and/or the Government of Canada upon request from either entity.
- D28.7.2 If the Lobbyists Registration Act (Manitoba) applies to the Contractor, the Contractor represents and warrants that it has filed a return and is registered and in full compliance with the obligations of that Act, and covenants that it will continue to comply for the duration of this Contract.
- D28.7.3 The Contractor shall comply with all applicable legislation and standards, whether federal, provincial, or municipal, including (without limitation) labour, environmental, and human rights laws, in the course of providing the Work.
- D28.7.4 The Contractor shall properly account for the Work provided under this Contract and payment received in this respect, prepared in accordance with generally accepted accounting principles in effect in Canada, including those principles and standards approved or recommended from time-to-time by the Chartered Professional Accountants of Canada or the Public Sector Accounting Board, as applicable, applied on a consistent basis.
- D28.7.5 The Contractor represents and warrants that no current or former public servant or public office holder, to whom the Value and Ethics Code for the Public Sector, the Policy on Conflict of Interest and Post Employment, or the Conflict of Interest Act applies, shall derive direct benefit from this Contract, including any employment, payments, or gifts,

unless the provision or receipt of such benefits is in compliance with such codes and the legislation.

D28.7.6 The Contractor represents and warrants that no member of the House of Commons or of the Senate of Canada or of the Legislative Assembly of Manitoba is a shareholder, director or officer of the Contractor or of a Subcontractor, and that no such member is entitled to any benefits arising from this Contract or from a contract with the Contractor or a Subcontractor concerning the Work.

# FORM H1: PERFORMANCE BOND (See D12)

KNO	W EVERYONE BY	THESE PRESENTS THAT
(here	inafter called the "F	incipal"), and
	inafter called the "S Obligee"), in the sur	urety"), are held and firmly bound unto <b>THE CITY OF WINNIPEG</b> (hereinafter called of of
		dollars (\$
sum	the Principal and th	la to be paid to the Obligee, or its successors or assigns, for the payment of which e Surety bind themselves, their heirs, executors, administrators, successors and ally, firmly by these presents.
WHE	REAS the Principal	has entered into a written contract with the Obligee for
TENE	DER NO. 146-2024	
AMBI	ER GATES COMM	INITY PLAYGROUND AND SHELTER
which	n is by reference ma	de part hereof and is hereinafter referred to as the "Contract".
NOW	THEREFORE the	condition of the above obligation is such that if the Principal shall:
(a) (b) (c) (d)	forth in the Cont perform the Wor make all the pay	rform the Contract and every part thereof in the manner and within the times se act and in accordance with the terms and conditions specified in the Contract; in a good, proper, workmanlike manner; ments whether to the Obligee or to others as therein provided; espect comply with the conditions and perform the covenants contained in the
(e)	indemnify and s demands of even claims, actions Compensation A performance or i	eve harmless the Obligee against and from all loss, costs, damages, claims, and ry description as set forth in the Contract, and from all penalties, assessments for loss, damages or compensation whether arising under "The Workers ct", or any other Act or otherwise arising out of or in any way connected with the on-performance of the Contract or any part thereof during the term of the Contract period provided for therein;
		N SHALL BE VOID, but otherwise shall remain in full force and effect. The Surety ble for a greater sum than the sum specified above.
of any	y kind or matter wha	LARED AND AGREED that the Surety shall be liable as Principal, and that nothing tsoever that will not discharge the Principal shall operate as a discharge or release ny law or usage relating to the liability of Sureties to the contrary notwithstanding.
IN W	ITNESS WHEREO	the Principal and Surety have signed and sealed this bond the
	dav of	. 20

The City of Winnipeg Tender No. 146-2024

Template Version: 2023 07 27 - Const noBidSecurity

#### Supplemental Conditions Page 15 of 22

SIGNED AND SEALED in the presence of:

(Witness as to Principal if no seal)

(Name of Principal)	
Per:	(Seal)
Per:	
(Name of Surety)	
By: (Attorney-in-Fact)	(Seal)

# FORM H2: LABOUR AND MATERIAL PAYMENT BOND (See D12)

#### KNOW EVERYONE BY THESE PRESENTS THAT

his/its heirs, executors, administrators, successors or assigns (hereinafter called the "Principal"), and	-
his/its heirs, executors, administrators, successors or assigns (hereinafter called the "Surety"), are held a firmly bound unto <b>THE CITY OF WINNIPEG</b> (hereinafter called the "Obligee"), for the use and benefit claimants as hereinbelow defined, in the amount of	
dollars (\$	- )

of lawful money of Canada, for the payment whereof we, the Principal and the Surety jointly and severally bind ourselves firmly by these presents.

WHEREAS the Principal has entered into a written contract with the Obligee for

TENDER NO. 146-2024

#### AMBER GATES COMMUNITY PLAYGROUND AND SHELTER

which is by reference made part hereof and is hereinafter referred to as the "Contract".

NOW THEREFORE the condition of the above obligation is such that if the Principal shall promptly make payment to all claimants as hereinafter defined, for all labour, service and material used or reasonably required for use in the performance of the Contract, then this obligation shall be void, otherwise it shall remain in full force and effect subject, however, to the following conditions:

- (a) A claimant is defined as one having a direct contract with the Principal for labour, service and material, or any of them, used or reasonably required for use in the performance of the contract, labour, service and material being construed to include that part of water, gas, power, light, heat, oil, gasoline, telephone service or rental of equipment (but excluding rent of equipment where the rent pursuant to an agreement is to be applied towards the purchase price thereof) directly applicable to the Contract;
- (b) The above-named Principal and Surety hereby jointly and severally agree with the Obligee that every claimant as herein defined, who has not been paid in full before the expiration of a period of ninety (90) days after the date on which the last of such claimant's work, labour or service was done or performed, or materials were furnished by such claimant, may sue on this bond, prosecute the suit to final judgment for such sum or sums as may be justly due claimant, and have execution thereon;
- (c) No suit or action shall be commenced hereunder by any claimant
  - (i) unless claimant shall have given written notice to the Principal and the Surety abovenamed, within one hundred and twenty (120) days after such claimant did or performed the last of the work, labour or service, or furnished the last of the materials for which said claim is made, stating with substantial accuracy the amount claimed and the name of the party to whom the materials were furnished, or for whom the work, labour or service was done or performed. Such notice shall be served by mailing the same by registered mail to the Principal, and Surety, at any place where an office is regularly maintained for the transaction of business, or served in any manner in which legal process may be served in the Province of Manitoba;

- (ii) after the expiration of one (1) year following the date on which Principal ceased work on said Contract; including work performed under the guarantees provided in the Contract;
- (iii) other than in a court of competent jurisdiction in the Province of Manitoba.
- (d) The amount of this bond shall be reduced by and to the extent of any payment or payments made in good faith hereunder, inclusive of the payment by Surety of mechanics liens which may be filed of record against said improvement, whether or not claim for the amount of such lien be presented under and against this bond.
- (e) The Surety shall not be liable for a greater sum than the specified penalty of this bond.

The Principal and Surety hereby agree that The Guarantors' Liability Act (Manitoba) shall apply to this Bond.

IN TESTIMONY WHEREOF, the Principal has hereunto set its hand affixed its seal, and the Surety has

caused these presents to be sealed ar its signing authority this	nd with its corporate seal duly attested by the autho	rized signature o
day of	, 20	
SIGNED AND SEALED in the presence of:  (Witness as to Principal if no seal)	(Name of Principal) Per: Per:	
	(Name of Surety)	
	By: (Attorney-in-Fact)	(Seal)

The City of Winnipeg Tender No. 146-2024

Template Version: 2023 07 27 - Const noBidSecurity

# FORM H3: IRREVOCABLE STANDBY LETTER OF CREDIT (CONTRACT SECURITY) (See D12)

(Date)	
Legal S 185 Kir	ty of Winnipeg Services Department ng Street, 3rd Floor eg MB R3B 1J1
RE:	CONTRACT SECURITY - TENDER NO. 146-2024
	AMBER GATES COMMUNITY PLAYGROUND AND SHELTER
Pursua	ant to the request of and for the account of our customer,
(Name o	f Contractor)
	EREBY ESTABLISH in your favour our irrevocable Standby Letter of Credit for a sum not exceeding aggregate
	Canadian dollars.
for pay for the inquirin	andby Letter of Credit may be drawn on by you at any time and from time to time upon written demand ment made upon us by you. It is understood that we are obligated under this Standby Letter of Credit payment of monies only and we hereby agree that we shall honour your demand for payment without go whether you have a right as between yourself and our customer to make such demand and without izing any claim of our customer or objection by the customer to payment by us.
	nount of this Standby Letter of Credit may be reduced from time to time only by amounts drawn upon bu or by formal notice in writing given to us by you if you desire such reduction or are willing that it be
	gage with you that all demands for payment made within the terms and currency of this Standby Letter dit will be duly honoured if presented to us at:
(Address	s)

and we confirm and hereby undertake to ensure that all demands for payment will be duly honoured by us.

The City of Winnipeg Tender No. 146-2024 Supplemental Conditions Page 19 of 22

Template Version: 2023 07 27 - Const noBidSecurity

	I specifically state that they are drawn under this Standby Letter of Cred	v are drawn und	ally state that the	ent shall specificall	payr	Il demands for	Αll
--	--	-----------------	---------------------	-----------------------	------	----------------	-----

Subject to the condition hereinafter set forth, this Standby Letter of Credit will expire on

(Date)			

It is a condition of this Standby Letter of Credit that it shall be deemed to be automatically extended from year to year without amendment from the present or any future expiry date, unless at least 30 days prior to the present or any future expiry date, we notify you in writing that we elect not to consider this Standby Letter of Credit to be renewable for any additional period.

This Standby Letter of Credit may not be revoked or amended without your prior written approval.

Except where they may conflict with the terms and conditions contained in this Letter of Credit, the International Standby Practices 1998 shall apply to this Letter of Credit. This Letter of Credit shall also be governed by and construed in accordance with the laws of the Province of Manitoba and of Canada as applicable therein, except to the extent that such laws are inconsistent with the International Standby Practices 1998. This Letter of Credit is subject to the exclusive jurisdiction of the courts in the Province of Manitoba and all courts competent to hear appeals therefrom.

(Name	of bank or financial institution)
Per:	
	(Authorized Signing Officer)
Per:	
	(Authorized Signing Officer)

# FORM J: SUBCONTRACTOR LIST

(See D13)

<u>Name</u>	Address
<u>Name</u>	<u>Addicas</u>
<u> </u>	
<u> </u>	

# FORM L: DETAILED WORK SCHEDULE

(See D14)

For each item of Work, indicate the cumulative percentage proposed to completion is achieved.	be comple	ted by the	end of eac	h time peri	od until 100	)%
Items of Work	Time Period in Working Days					
	0	10	20	30	40	50

### FORM L: DETAILED WORK SCHEDULE

(See D14)

For each item of Work, indicate the proposed date Items of Work	Percenta	Percentage of Work Completed						
	Start	25%	50%	75%	100%			
			1					
			1					
			1					
			+					
		1						

The City of Winnipeg Specifications
Tender No. 146-2024 Page 1 of 27

Template Version: 2023 07 27 - Const noBidSecurity

#### **PART E - SPECIFICATIONS**

#### **GENERAL**

#### E1. APPLICABLE SPECIFICATIONS AND DRAWINGS

- E1.1 These Specifications shall apply to the Work.
- E1.2 The City of Winnipeg Standard Construction Specifications in their entirety, whether or not specifically listed on Form B: Prices, shall apply to the Work.
- E1.2.1 The City of Winnipeg Standard Construction Specifications is available on the Information Connection page at The City of Winnipeg, Corporate Finance, Materials Management Division website at <a href="http://www.winnipeg.ca/matmgt/Spec/Default.stm">http://www.winnipeg.ca/matmgt/Spec/Default.stm</a>
- E1.2.2 The version in effect three (3) Business Days before the Submission Deadline shall apply.
- E1.2.3 Further to C2.4(d), Specifications included in the Tender shall govern over *The City of Winnipeg Standard Construction Specifications*.
- E1.3 Bidders are reminded that requests for approval of substitutes as an approved equal or an approved alternative shall be made in accordance with B7. In every instance where a brand name or design specification is used, the City will also consider approved equals and/or approved alternatives in accordance with B7.

E1.4 The following are applicable to the Work:

Specification No.	Specification Title
CW-1110	General Instructions
CW-1130	Site Requirements
CW-2160	Concrete Underground Structures and Works
CW-3110	Sub-Grade, Sub-Base and Base Course Construction
CW-3120	Installation of Sub Drains
CW-3130	Supply and Installation of Geotextile Fabrics
CW-3170	Earthwork and Grading
CW-3510	Sodding
CW-3520	Seeding
CW-3540	Topsoil and Finish Grading for Establishment of Turf Areas
<u>Drawing No.</u>	Drawing Name/Title
COVER SHEET	Context Plan
L1	Site Plan
L2	Layout Plan
L3	Grading Plan
L4	Details
SCD-122	Tache Style Metal Frame Picnic Table
SCD-122A	Tache Style Wheelchair Metal Frame Picnic Table Park Pathway Asphalt

#### E2. HAZARDOUS MATERIALS

E2.1 If asbestos or other hazardous materials are encountered during the Work of the Contract, the Contractor shall stop all work and notify the Contract Administrator immediately. Removal of hazardous materials shall be dealt with by the City and the Contractor shall await further instruction by the Contract Administrator.

#### E3. EXISTING SERVICES AND UTILITIES

E3.1 No responsibility will be assumed by the City for correctness or completeness of the Drawings, when provided, with respect to the existing utilities, pipes or other objects either underground or

The City of Winnipeg Specifications
Tender No. 146-2024 Page 2 of 27

Template Version: 2023 07 27 - Const noBidSecurity

on the surface; the City shall not be liable for the incorrectness and inadequacy thereof. It shall be the responsibility of the Contractor to determine the location of all such utilities, pipes and other objects and to make good any damage done to them.

### E4. ACCESS TO SITE

- E4.1 Access to the Site as required by the Contractor shall be provided and maintained by the Contractor at their own expense and approved by the Contract Administrator.
- E4.2 The Contractor's operations shall be limited to the minimum area necessary for undertaking the Work and they shall be responsible for all damage resulting from their Work on private property.

# E5. PERMITS, NOTICES, LICENSES, CERTIFICATES, LAWS AND RULES

- E5.1 Further to C6.13, the Contractor shall give all necessary notices, obtain all necessary permits and pay all fees in order that the Work may be carried out. The Contractor shall submit all plans required by any inspection authority and obtain approval of same before proceeding with the Work, and pay any cost attached to the inspection of such plans.
- E5.2 The Contractor shall comply with all laws, ordinances, rules and regulations that would relate to the Work.
- E5.3 All notices, consents, approvals, statements, authorizations, documents or other communications to the City shall be submitted to the Contract Administrator.
- E5.4 All Work shall be performed in compliance with the Manitoba Workplace Health and Safety Act.
- E5.5 All Work shall be performed in compliance with the Manitoba Workplace Health and Safety Fall Protection guidelines.
- E5.6 The Contractor and Sub-contractors must be fully aware of all Work involving hazardous materials. All Work must be performed in compliance with the Manitoba Department of Labour Workplace Health and Safety Guidelines and all other applicable codes. The Contractor is responsible for the immediate notification to the Contract Administrator of their encountering of suspected hazardous material during their course of Work.

### E6. DAMAGE TO EXISTING STRUCTURES, TREES AND PROPERTY

- E6.1 All necessary precautions shall be exercised by the Contractor so as not to remove, disturb, or damage any existing trees, shrubs, sod, pavements, streets, roads, boulevards, poles, hydrants, water pipes, gas pipes, electrical wires, cables, conduits, sewers or other existing facilities and equipment at the Site of the Work. For all damage incurred in the performance of the Work (either directly or indirectly), the Contractor shall either replace and repair such damage, whichever may be deemed necessary in the opinion of, and acceptable to City of Winnipeg Contract Administrator, and the cost of which shall be borne entirely by the Contractor. The Contractor shall also indemnify and save harmless the City from all claims made directly or indirectly against it in respect to any such damage.
- E6.2 The Contractor shall take the following precautionary steps to prevent damage from construction activities to existing park trees within the limits of the construction area:
  - (a) The Contractor shall not stockpile materials and soil or park vehicles and equipment within 2 metres of trees.
  - (b) Trees identified to be at risk by the Contract Administrator are to be strapped with 25x100x2400 wood planks, or suitable protection as approved by the Contract Administrator.
  - (c) Excavation shall be performed in a manner that minimizes damage to the existing root systems. Where possible, excavation shall be carried out such that the edge of the excavation shall be a minimum of 1.5 times the diameter (measured in inches), with the

The City of Winnipeg Specifications
Tender No. 146-2024 Page 3 of 27

Template Version: 2023 07 27 - Const noBidSecurity

- outcome read in feet, from the closest edge of the trunk. Where roots must be cut to facilitate excavation, they shall be pruned neatly at the face of excavation.
- (d) Operation of equipment within the drip line of the trees shall be kept to a minimum required to perform the Work required. Equipment shall not be parked, repaired, refuelled; construction materials shall not be stored, and earth materials shall not be stockpiled within the drip lines of trees. The drip line of a tree shall be considered to be the ground surface directly beneath the tips of its outermost branches. The Contractor shall ensure that the operations do not cause flooding or sediment deposition on areas where trees are located.
- E6.3 All damage to existing trees caused by the Contractor's activities shall be repaired to the requirements and satisfaction of the Contract Administrator and the City Forester or their designate.
- E6.4 No separate measurement or payment will be made for the protection of trees.

# E7. PEDESTRIAN SAFETY AND TRAFFIC MANAGEMENT

- E7.1 Further to CW 1130, the Contractor shall take such measures as are necessary to ensure safe and convenient pedestrian ingress and egress is maintained to private properties while they are working near them. Any damage caused by the negligence of the Contractor or their Sub-Contractors to the adjacent Works or properties, shall be promptly repaired by him at their own expense, to the satisfaction of the Contract Administrator.
- E7.2 Ambulance/ Emergency vehicle access must be maintained at all times.

# E8. PROTECTION OF THE SURVEY INFRASTRUCTURE

- E8.1 Notwithstanding clause 4 "Persons and municipalities to protect Outline Monuments"; under <a href="The Surveys Act">The Surveys Act</a>, of Manitoba, the Contractor shall be responsible to protect the Survey Infrastructure from damage as a result of the Work.
- E8.2 Further to C6.26 (g), at least 72 hours prior to the commencement of the On-Site Work the Contractor shall contact the City of Winnipeg, Geomatics Services Branch at 204-918-1360 (8:00 am to 4:00 pm Monday to Friday, excluding holidays) to obtain underground clearance. Geomatics Services will locate and mark all known outline survey monuments and geodetic control monuments and confirm the physical condition of those monuments upon completion of construction, at no cost to the Contractor.
- E8.3 Where a survey post, bar or control monument lies in the line of the proposed Work and must be disturbed, the Contractor shall provide the Contract Administrator with 48 hours' notice to permit referencing for future replacement, at no cost to the Contractor. Failure to provide the specified notice shall result in the Contractor paying for all costs associated with replacing or relocating the disturbed outline survey monuments and geodetic control monuments. Survey monuments and geodetic control monuments at or adjacent to the Site, not in the line of the proposed construction that are damaged or disturbed by the Contractor shall be replaced or relocated by the City or their agent and all associated costs shall be paid for by the Contractor.
- An approximate estimate of the cost to restore a legal survey monument is \$1,000 per bar and \$3,000 per control monument. Contractors shall ensure their landscaping and other subcontractors are aware of this clearance procedure and the potential restoration costs. Where possible, amounts owed to the City in accordance with the above will be deducted from payments to be made by the City to the Contractor.

# E9. SITE ENCLOSURES

- E9.1 Temporary Site enclosures, as determined necessary at the pre-construction meeting, shall be erected and maintained as required for the duration of the construction period.
- E9.2 Site enclosures shall be considered incidental to the Contract Work

The City of Winnipeg Specifications
Tender No. 146-2024 Page 4 of 27

Template Version: 2023 07 27 - Const noBidSecurity

- E9.3 Site enclosures shall be sturdy, steel construction fencing.
  - (a) Snow fencing will not be accepted.
- E9.4 Contractor to securely lock construction fencing at the end of each Working Day
- E9.5 Contractor shall install a minimum of one (1) construction safety sign per enclosure.

### SITE DEVELOPMENT

### E10. EXCAVATION AND GRADING

# E10.1 General Description

- E10.1.1 This Specification shall amend and supplement CW 3110 and CW 3170. It shall cover the excavation and legal disposal of existing earthen materials and site grading.
  - (a) If required by the Contract Administrator, layout and grades shall be established by a professional land surveyor.
- Excavation includes the removal of items (i.e. earthen materials) as indicated on the Drawings and as directed by the Contract Administrator. Work includes the satisfactory disposal of unsuitable Site material such as clays susceptible to frost-heaving, silts, rock, rubble, rubbish and any surplus suitable Site material.
  - (a) Work shall include but not be limited to the following:
    - (i) Excavate, add clean fill if necessary, and grade to the limits shown on Drawings to the depths necessary to achieve finish grades indicated in the Drawings.
    - (ii) New play area protective surfacing depth of excavation is approximately  $\pm$  375 mm with a variance of  $\pm$  25 mm throughout to ensure 0.5%
    - (iii) Excavate to depths required for proposed curb height and granular base layer as per detail drawings and grading plan.
    - (iv) Excavation for new asphalt seating areas as per detail drawings and grading plan.
    - (v) Excavation of existing granular pavement to be scraped and topped with new asphalt to be to a depth of  $\pm$  25mm below finished grade.
    - (vi) All extraneous materials are to be removed from the Site and disposed of in a safe and legal manner.
- E10.1.3 The Work to be completed by the Contractor under this Specification shall include the supply of all materials, and the furnishings of all superintendence, overhead, labour, equipment, tools, and all other things necessary for and incidental to the satisfactory completion of all the Work shown on the Drawings and specified herein.

# E10.2 Construction Methods

# E10.2.1 Excavation

- (a) Stockpile suitable, approved material on Site for reuse (clean topsoil, clean earth fill,) in a secure location. Remove and dispose of unsuitable material.
- (b) Disposal of material shall be understood to mean the hauling of all unsuitable material from the Site and the unloading in a legal manner acceptable to the Contract Administrator. If arrangements are made in advance excavated material may be disposed of on Site at a location designated by the Contract Administrator.
- (c) Contractor must coordinate with the Contract Administrator to ensure all removals have occurred.
- (d) Excavate to the limits shown and as necessary to achieve finish grades as indicated on the Drawings. Where design grades are not shown, the new surface materials shall be installed to meet flush with surrounding grades, and sloped so as not to impede the existing drainage pattern.

The City of Winnipeg Specifications
Tender No. 146-2024 Page 5 of 27

Template Version: 2023 07 27 - Const noBidSecurity

(e) The Contractor shall construct all sub-grades in accordance with CW 3110. This shall include the use of suitable compaction equipment as approved by the Contract Administrator to achieve a minimum compaction of 98% Standard Proctor Density below all paved areas, and 90% Standard Proctor Density in all other areas disturbed under this Contract unless otherwise indicated. Lifts shall not exceed a compacted thickness of 150 mm.

(f) Where new sod will meet existing, employ a vertical shearing operation, such as using a sharp spade or edger, along the outside edges of the excavation to create a clean and definite line for the new sod to abut flush to.

# E10.2.2 Grading

- (a) Site grading shall be as per the Drawings.
- (b) The design grade shall be considered to be straight grade between finished design elevations shown. Changes in grade at swales or where it meets existing sod shall be gently contoured to allow for ease of grass mowing operations.
- (c) Contractor to ensure site grading does not create tripping hazards and no areas of standing water remain.
- (d) If necessary the Contractor shall import clean fill to achieve grades as per the Drawings.
- (e) Backfill shall be placed in a dry, thawed condition and shall be maintained free of moisture or frost.
- (f) In fill areas where the difference between the existing ground elevation and the new finished design elevation is less than 300 mm, the Contractor shall scarify the existing ground to a minimum depth of 50 mm prior to placement of any fill.
- (g) In areas where new grades are greater than 75 mm than existing grades, clean fill shall be used to achieve finished subgrade levels. Clean fill can be used from On-Site grading operations. If additional clean fill is required, it must be hauled in from Off-Site.

# E10.2.3 Finish Grading

- (a) Following earthmoving, rough grading and compaction, the Work areas shall be finish graded to provide a maximum deviation of 50 mm in 10 meters from the design grade with no low areas that hold water. The finished surface of all disturbed areas shall be dragged and smoothed in such a manner that there are no loose soil particles greater than 50 mm.
- (b) When grading for an athletic field or swale, the grading work must be undertaken using earthmoving equipment that is guided by laser or GPS controlled data. Visual grade stakes shall also be installed to supplement the electronic data, unless otherwise agreed to by Contract Administrator.
- (c) All surplus fill material shall be removed and legally disposed off-site.
- (d) Do not disturb adjacent items designated to remain in place.

### E10.3 Method of Measurement and Basis of Payment

### E10.3.1 Method of Measurement shall be as follows:

- (a) Excavation and Grading shall be measured on a cubic metre basis for:
  - (i) "Excavate and Legally Dispose of existing earthen material for new play area";
  - (ii) "Excavate and Legally Dispose of existing earthen material for seating areas"; and,
  - (iii) "Scrape Top 1" Off Existing Gravel Path for New Asphalt over Existing Granular Pathway" on Form B: Prices.
- (b) Excavation and Grading shall be measured on a square metre basis for:
  - (i) "Site Grading" on Form B: Prices.

The City of Winnipeg Specifications
Tender No. 146-2024 Page 6 of 27

Template Version: 2023 07 27 - Const noBidSecurity

- (c) No separate measurement will be made for excavation and grading for the following items as these items are incidental to the Work therein:
  - (i) Asphalt Pavement;
  - (ii) Sod;
  - (iii) CIP Concrete Play Edging;
  - (iv) Import of clean fill to achieve grades and earthwork and site grading grades.
- (d) If required by the Contract Administrator, no separate measurement will be made for retaining services relating to survey of layout and establishing grades as these items are incidental to the Work herein.

# E10.3.2 Basis of Payment shall be as follows:

- (a) Excavation and grading will be paid for at the Contract Unit Prices on Form B: Prices. The amount to be paid for shall be the total number of units, measured as specified herein, which price shall be for full payment for supplying all labour, equipment and materials, and performing all operations herein described and all other items incidental to the Work and as accepted by the Contract Administrator.
- (b) If required by the Contract Administrator, no additional payment will be made for retaining services relating to survey of layout and establishing grades as these items are incidental to the Work herein.
- (c) No additional payment will be made for excavation and grading for the following items as these items are incidental to the Work herein:
  - (i) Asphalt pavement;
  - (ii) Sod;
  - (iii) CIP Concrete Play Area Edging;
  - (iv) Import of clean fill to achieve grades and earthwork and site grading grades.

### E11. ASPHALT PATHWAY AND SEATING AREAS

# E11.1 General Description

- (a) This Specification shall supplement E10, CW 3110, CW 3130, 3410 and SCD-648 and shall cover the supply and installation of the asphalt pathway and seating areas.
- (b) The Work to be completed by the Contractor under this Specification shall include the supply of all materials, and the furnishings of all superintendence, overhead, labour, equipment, tools, and all other things necessary for and incidental to the satisfactory completion of all the Work shown on the Drawings and specified herein.
- (c) The use of recycled concrete as a base material will not be permitted.

# E11.2 General Instructions

- (a) Quality Control for Hard Surfaced Areas
  - (i) Further to Section 10, Quality Control, of CW 3110 and CW 3410, the Contractor shall obtain a qualified independent testing lab to conduct tests on materials to determine the acceptability of the asphaltic concrete as placed by the Contractor in accordance with the requirements of this Specification.
  - (ii) The Contractor shall not proceed with asphalt installation until test results on the crushed limestone base have been reviewed and approval to proceed is granted by the Contract Administrator.
  - (iii) The Contract Administrator will conduct a survey of the operation to verify installation of specified layer thickness.
  - (iv) Non-conformity with the specified test requirements or compacted layer thickness will constitute sufficient grounds for rejection of the Work

# (b) Submittals

(i) Material samples may be required, at the discretion of the Contract Administrator, for materials supplied under this Specification.

The City of Winnipeg Specifications
Tender No. 146-2024 Page 7 of 27

#### Template Version: 2023 07 27 - Const noBidSecurity

Materials

E11.3

# (a) Geotextile Fabric

- The separation/ reinforcement non-woven geotextile fabric shall conform to the Products Approved as listed in City of Winnipeg Specification for Approved Products for Surface Works.
  - ♦ <a href="https://www.winnipeg.ca/finance/findata/matmgt/std">https://www.winnipeg.ca/finance/findata/matmgt/std</a> const\_spec/current/Docs/Ap proved Products Surface Works.pdf
- (b) Materials Limestone Materials Only
  - (i) 150 mm layer of 50 mm (2") down crushed limestone;
  - (ii) 75 mm layer of 20 mm (3/4") down crushed limestone.
  - (iii) Sub-base and Base course shall be Granular C as per current CW 3110, the Drawings, SCD-648 and this specification.
  - (iv) Notwithstanding current CW 3110 Section 1.2 Clause 1.2.7, Granular A, Granular B, and recycled aggregates or materials will not be accepted.
  - (v) Sub-base and Base Course Material Grading Requirements:

CANADIAN METRIC SIEVE SIZE	Percent of Total Dry Weight Passing Each Sieve		
	6 mm (1.4") Topping	20 mm (3/4") Base	<b>50</b> mm (2") Base
	Material	Course	Course
50 000			100%
25 000			
20 000		100%	
10 000	100%		
5 000	65% - 100%	40% - 70%	25% - 60%
2 500	40% - 75%	25% - 60%	
1 250	35% - 65%		
630	19% - 36%		
315	14% - 28%	8% - 25%	1
160	12% - 24%	-	-
80	10% - 25%	6% - 17%	4% - 15%

### (c) Asphaltic Concrete

(i) Asphaltic Concrete shall be Type 1A as specified and to a compacted thickness of 75mm (3") as shown on the Drawings.

### E11.4 Construction Methods

### (a) Excavation

- (i) Excavation shall be done in accordance with E10, SCD-648 and as outlined in Section 3.2 of CW 3110.
- (ii) The Contractor shall survey and stake out the proposed asphalt entry path area prior to the start of construction as shown on the Construction Drawings. Layout shall be checked and confirmed with Contract Administrator prior to construction.
- (iii) Existing pavement within the limits of the designated area of removal shall be saw cut for the full depth of the pavement prior to the demolition and removal operations. All costs in connection with saw cutting are incidental and shall be included in the unit price for the asphalt entry path.
- (iv) All excavated material shall be removed, hauled, and legally disposed of off-site to the satisfaction of the Contract Administrator.

#### (b) Sub-grade Compaction

- (i) Sub-grade compaction shall be performed as outlined in Section 3.3 of CW 3110.
- (ii) Sub-grade shall be free of any fibrous organics, softened and disturbed soil. The prepared sub-grade shall be proof rolled with a heavy sheep's foot roller (minimum 25 passes) and inspected by the Contract Administrator to detect for any soft spots prior to the placement of overlying granular fills.
- (c) Geotextile Fabric

The City of Winnipeg Specifications
Tender No. 146-2024 Page 8 of 27

Template Version: 2023 07 27 - Const noBidSecurity

(i) Separation/ Reinforcement geotextile fabric shall be installed as outlined in Section 3.1 of CW 3110.

- (d) Crushed limestone sub-base and base material
  - (i) Crushed limestone sub-base and base material shall be installed as outlined in CW 3110 and shall be shall be placed and compacted as specified to a finished thickness as shown on the Drawings.
- (e) Asphaltic Pavement
  - (i) Asphaltic Pavement for the path entry area shall be installed in accordance with City of Winnipeg Standard Construction Specification CW 3410 "Asphaltic Concrete Pavement Works" and SCD-648.
- (f) Rolled asphalt edge for play area
  - (i) Rolled asphalt edge for play area shall be installed as per the Drawings
- (g) Crack Sealing
  - (i) As a Warranty requirement, the Contractor shall rout and seal any and all cracks which may appear in the pathway and court approach area during the one-year warranty period. Crack sealing shall conform to the requirements of City of Winnipeg Standard Construction CW 3250.
  - (ii) No separate payment will be made for this item as it is considered a warranty issue.

#### E11.5 Method of Measurement

- (a) Method of Measurement and Basis of Payment for Crushed Limestone Sub-base Course shall be measured on a per tonne basis for:
  - (i) "Supply and install crushed sub-base course material for asphalt pathway and seating area" on Form B: Prices.
- (b) Method of Measurement and Basis of Payment for Crushed Limestone Base Course shall be measured on a cubic metre basis for:
  - (i) "Supply and install crushed base course material for asphalt pathway and seating areas" on Form B: Prices.
- (c) Method of Measurement and Basis of Payment for geotextile fabric shall be measured on a square metre basis for:
  - (i) "Supply & install separation geotextile fabric for asphalt pathway and seating areas" on Form B: Prices.
- (d) Asphalt for pathway and seating areas
  - (i) Asphalt pathway and seating area works shall be measured on per tonne basis for: "Supply and install asphalt pathways and seating areas as per SCD-648 c/w rolled asphalt edge for play area"; and,
  - (ii) "Supply and install new asphalt over existing gravel path" on Form B: Prices.
- (e) No measurement will be made for material testing as this item is incidental to the Work herein.

### E11.6 Basis of Payment

- (a) Asphalt pathway and seating areas
  - (i) Asphalt pathway and seating areas will be paid for at the Contract Unit Prices. The amount to be paid for shall be the total number of units, as indicated on Form B: Prices. This price shall be full payment for asphalt pathway and seating areas including asphalt pavement as per SCD-648 supplying all labour, equipment and materials, and performing all operations herein described and all other items incidental to the Work and as accepted by the Contract Administrator.
  - (ii) No payment shall be made for excavation and grading as this item is incidental to the Work herein.
- (b) No payment will be made for material testing as this item is incidental to the Work herein.

The City of Winnipeg Specifications
Tender No. 146-2024 Page 9 of 27

Template Version: 2023 07 27 - Const noBidSecurity

#### E12. CIP CONCRETE EDGING

- E12.1 General Description
- E12.1.1 This section shall cover the supply and installation of cast in place concrete play edging as per the Drawings. It shall amend and supplement the most up-to-date version of City of Winnipeg Standard Construction Specifications section 3310.
- E12.2 Materials
- E12.2.1 Concrete shall be Type 1 as per the most up-to-date version of City of Winnipeg Standard Construction Specifications section 3310 and shall adhere to the dimensions on the Drawings.
- E12.2.2 Granular base shall be 19mm diameter crushed limestone.
- E12.2.3 Reinforcing steel for play edging shall be 15m with 15m ties at 600 mm O.C.
- E12.2.4 Bond breaker between curb and concrete path shall be buffalo board, or approved Bond breaker as per B7.
- E12.3 Construction Methods
- E12.3.1 Layout is to be established on Site, after excavation and grading operations and reviewed by Contract Administrator prior to formwork being completed.
  - (a) Contractor is to confirm and warrant that play equipment and swings (complete with required safety surfacing zones) will fit within curbs as laid out on Site.
- E12.3.2 Granular base, formwork and reinforcing are to be reviewed on Site by the Contract Administrator prior to pouring of concrete.
- E12.3.3 Concrete is to be trowel finish. All exposed edges are to be bull nose as shown on the Drawings. Front, top and back of curb are to be finished.
- E12.3.4 Concrete edging shall have saw cut control joints at 1.5m intervals.
- E12.3.5 Place bond breaker as per Manufacturer's instructions
- E12.4 Method of Measurement and Basis of Payment
- E12.4.1 Method of Measurement shall be as follows:
  - (a) Concrete edging will be measured on a Linear Metre basis for:
    - (i) "Supply and install CIP concrete play edging" on Form B: Prices.
- E12.5 Basis of Payment Shall be as follows:
- E12.5.1 Concrete edging will be paid for at the Contract Unit Prices. The amount to be paid for shall be the total number of units, as indicated on Form B: Prices. This price shall be full payment for supplying all labour, equipment and materials, and performing all operations herein described and all other items incidental to the Work and as accepted by the Contract Administrator.
- E12.5.2 This payment shall be understood to include all concrete, excavation, base, reinforcing, compaction, placement and finishing.

### E13. PROTECTIVE SURFACING - ENGINEERED WOOD FIBRE

- E13.1 General Description
- E13.1.1 This Specification shall cover the supply and install of engineered wood fibre safety surfacing, including drainage layer.
- E13.1.2 The Work to be completed by the Contractor under this Specification shall include the supply of all materials, and the furnishings of all superintendence, overhead, labour, equipment, tools, and all other things necessary for and incidental to the satisfactory completion of all the Work shown on the Drawings and specified herein.

The City of Winnipeg Specifications
Tender No. 146-2024 Page 10 of 27

Template Version: 2023 07 27 - Const noBidSecurity

### E13.2 General Instructions

# E13.2.1 Quality Control

- (a) Testing and Approval of Materials
  - Material testing may be required as per this Specification and as directed by the Contract Administrator.
  - (ii) IPEMA Third Party Certification for impact attenuation may be required at the discretion of the Contract Administrator.

### E13.2.2 Submittals

- (a) Samples
  - (i) Material samples may be required, at the discretion of the Contract Administrator, for materials supplied in this Specification.

# E13.2.3 Product Data

(a) Contractor to submit Engineered Wood Fibre delivery slips and/or a warranty certificates to the Contract Administrator prior to installation as evidence that wood fibre surfacing has been supplied by an authorized distributor.

# E13.3 Materials

- E13.3.1 Wood Fibre product shall be either:
  - (a) Zeager Woodcarpet System 1
    - (i) Woodcarpet
      - ♦ Manufacturer: Zeagar Bros. Inc.

4000 East Harrisburg Pike ·

Middletown, PA 17057, USA

Ph: (1-888) 346-8524 or (717) 944-7481

Fax (717) 944-7681

Email; sales@zeager.com

- (ii) Specifications: <a href="https://www.zeager.com/products/recreation/woodcarpet-system-1/">https://www.zeager.com/products/recreation/woodcarpet-system-1/</a>
- (b) FibarSystem 300
  - (i) FibarSystem 300
    - The Fibar Group LLC

80 Business Park Drive, Suite 300

Armonk, NY 10504-1705, USA

Ph: (800) 342-2721 Fax: (914) 273-8659

Email: info@FibarPlaygrounds.com

- (ii) Specifications: <a href="http://www.fibar.com/playgrounds/specs200.htm">http://www.fibar.com/playgrounds/specs200.htm</a>
- (c) Or approved substitute as per B7.
  - If substitute to Zeagar Woodcarpet or Fibar FibarSystem 300 is proposed, it must meet the following conditions:
    - Materials must be IPEMA certified Engineered Wood Fiber;
    - Material must consist of random-sized, clean, engineered hardwood chips. Standard wood chips or bark mulch are not acceptable;
    - Materials must meet or exceed ASTM F1292 standards for impact attenuation;
    - Materials must be certified by the CSA and approved for playground use;
    - Materials must comply with ASTM F1951 for accessibility under the Canadians with Disabilities Act; and

The City of Winnipeg Specifications
Tender No. 146-2024 Page 11 of 27

Template Version: 2023 07 27 - Const noBidSecurity

- ◆ Materials must be covered by \$10,000,000.00 product liability insurance as well as provide a minimum 10 year warranty against loss of resiliency.
- (d) Wood Fibre surfacing shall include wood fibre, drainage mats / channels and mats under swings and ends of slides.
- (e) Mats are to be installed directly on top of the drainage mats / channels secured in place with two (2) duckbill anchors per mat.

### E13.4 Construction Methods

- Wood Fibre shall be installed within the <u>play areas</u>, as defined by the concrete and lumber edging to a **minimum depth of 300 mm** (after compaction). In the case where proposed play equipment includes a maximum fall height greater than 2400 mm (8-0"), depth of material to directly correspond to maximum fall height of play equipment in accordance with manufacturer's specifications.
- E13.4.2 The installation of the Wood Fibre shall be done immediately after the play equipment and drainage mats / channels has been installed.
- E13.4.3 Installation of entire system, including fibre, drainage mats / channels and mats under swings and slide ends shall be done according manufacturer's instructions. Adequate drainage within play equipment area must be ensured as per same.
- E13.4.4 Mud grade of play area shall be graded as the Drawings so that water will not puddle in any one area, and the area shall be cleared of any debris which inhibits proper drainage or installation of products.
- E13.4.5 Filter fabric (if required) must be cut and fit around playground equipment footings and overlap seams by 300 mm.
- E13.4.6 Installation shall be done by equipment sized to suit the Work being done and the Wood Fibre shall be spread by hand as necessary in the immediate vicinity of the play equipment so as not to damage same. The play equipment shall be swept clean to the satisfaction of the Contract Administrator after installation of the Wood Fibre.
- E13.5 Method of Measurement and Basis of Payment
- E13.5.1 Method of Measurement shall be as follows:
  - (a) Protective Surfacing will be measured on a square metre basis for:
    - (i) "Supply and install engineered wood fibre safety surfacing c/w subsurface drainage system" on Form B: Prices.
  - (b) No measurement will be made for subsurface drainage within the play area as this item is incidental to the Work herein.
- E13.5.2 Basis of Payment shall be as follows:
  - (a) Protective Surfacing will be paid for at the Contract Unit Prices. The amount to be paid for shall be the total number of units, as indicated on Form B: Prices. This price shall be full payment for supplying all labour, equipment and materials, and performing all operations herein described and all other items incidental to the Work and as accepted by the Contract Administrator.
  - (b) No payment will be made for subsurface drainage within the play area as this item is incidental to the Work herein.

# E14. SUB-SURFACE DRAINAGE OF PROTECTIVE SURFACING AREAS

# E14.1 General Description

E14.1.1 This Specification shall cover the supply and installation of a prefabricated geocomposite drain system or a perforated HDPE drainage pipe drain system to drain protective surfacing areas, complete with connection to an existing catch basin.

The City of Winnipeg Specifications
Tender No. 146-2024 Page 12 of 27

Template Version: 2023 07 27 - Const noBidSecurity

E14.1.2 Proposed subsurface drainage plan is subject to approval by the City of Winnipeg Parks Department and the Contractor Administrator.

- E14.1.3 Work to be executed as per CW-2130, CW-3120, CW-3130, SCD-650, SCD-659, SCD-661, and as shown on the Drawings.
- E14.1.4 The Work to be completed by the Contractor under this Specification shall include the supply of all materials, and the furnishings of all superintendence, overhead, labour, equipment, tools, and all other things necessary for and incidental to the satisfactory completion of all the Work shown on the Drawings and specified herein.

### E14.2 Materials

- E14.2.1 Drainage pipe may be either:
  - (a) "Goldline" 100 mm dia. (4") high-density polyethylene (HDPE) perforated drainage pipe, complete with fittings and polyester sock.
    - (i) Goldline®
      - ♦ Manufacturer: Prinsco Water Management Solutions
      - Website: <a href="https://www.prinsco.com/prinsco-markets/products/goldline-stormwater/">https://www.prinsco.com/prinsco-markets/products/goldline-stormwater/</a>
      - ♦ Ph: 1-800-992-1725
      - Specifications: <a href="https://www.prinsco.com/wp-content/uploads/2017/09/Goldline-HD-Prinsco-Single-Wall-Specification.pdf">https://www.prinsco.com/wp-content/uploads/2017/09/Goldline-HD-Prinsco-Single-Wall-Specification.pdf</a>
    - (ii) Or approved substitute as per B7.
      - Substitutions must the requirements of the American Association of State Highway and Transportation Officials (AASHTO) M252 and AASHTO M294.
  - (b) 150 mm (6") "Multi-Flow" drainage system, complete with fittings.
    - (i) Multi-Flow
      - Manufacturer: Varicore Technologies
      - ♦ Website: <a href="http://www.Multi-Flow.com">http://www.Multi-Flow.com</a>
      - ♦ Ph: 1-800-979-8007
      - ◆ Email: service@varicore.com
      - ◆ Multi-Flow Technical Properties Specifications: <a href="http://www.Multi-Flow.com/Menu/tech">http://www.Multi-Flow.com/Menu/tech</a> props.html
      - Model Specifications for Subsurface Drainage Section 2.1.1: <a href="http://www.Multi-">http://www.Multi-</a>
         <a href="http://www.Multi-">Flow.com/PDF Documents/Model Specs/Model NaturalTurf Spec.pdf</a>
    - (ii) Or approved substitute as per B7.
      - ◆ Geotextile cover substitutions must meet requirements of ASTM D-3776, ASTM D-4632, ASTM D-751, ASTM D-3786, ASTM D-4533, ASTM D-4491, ASTM D-4751, ASTM D-4595 and ASTM G-21
      - Drainage core substitutions must meet requirements of ASTM D-1777, ASTM D-4716 and ASTM D-1621

# E14.2.2 Fittings

(a) The fittings used with the edge drain shall be of a snap together design. In no case shall any drainage product be joined without the use of the manufacturer's connector designed specifically for the purpose. Cleanouts will be provided as indicated on the Drawings.

# E14.2.3 Pipe

(a) Pipe for drain outlet laterals shall be 75 mm (3") high-density polyethylene (HDPE) pipe meeting the requirements of AASHTO M252.

The City of Winnipeg Specifications
Tender No. 146-2024 Page 13 of 27

Template Version: 2023 07 27 - Const noBidSecurity

(b) A rodent screen made of 7.6 mm (0.3") by 7.6 mm (0.3") square opening size, 1.6 mm (0.063") gauge, stainless steel or galvanized, welded wire mesh shall be installed in each outlet lateral line. When using galvanized welded wire mesh, the rodent screen shall be galvanized after it has been formed to the shape and dimensions shown on the plans or specified by the Contract Administrator.

### E14.2.4 Backfill for Trenches

- (a) Backfill for trenches utilizing HDPE perforated drainage pipe as per CW-3120, CW-3130 and SCD-661.
- (b) Backfill for trenches utilizing Multi-Flow as per SCD-659.

#### E14.3 Construction Methods

- E14.3.1 Installation of Goldline (HDPE) perforated drainage pipe
  - (a) Subdrain is not to proceed until after the excavation/grading has been approved by the Contract Administrator.
  - (b) The layout of the subdrain is to be marked on Site and approved by the Contract Administrator prior to trenching.
  - (c) Layout of subdrain to be coordinated with layout of play equipment so as to prevent damage to subdrain during equipment installation
  - (d) Install as per the Drawings or as per CW-3120, CW-3130, and SCD-661.
- E14.3.2 Installation of Multi-Flow drainage system
  - (a) Multi-Flow installation is not to proceed until after the excavation/grading has been approved by the Contract Administrator.
  - (b) The layout of the subdrain is to be marked on Site and approved by the Contract Administrator prior to trenching.
  - (c) Install as per Manufacturer's written specifications.
- E14.3.3 Subdrains within play areas are to be laid on the prepared surface to facilitate cross movement of water. Subdrains shall be installed below geotextile and in conformance with details provided.
  - (a) Play areas are to be graded to drain towards subdrain. If using Engineered Wood Fibre, subdrain is to be used in conjunction with specified wood fibre drainage layer to bring excess water out of the play area as per SCD-650.
- E14.3.4 Fittings for the drain will be installed in accordance with the Manufacturer's recommendations and written specifications.
- E14.3.5 Any damaged edge drain or outlet lateral will be replaced or repaired by splicing in an undamaged section of drain at the Contractor's expense. The repair must be in accordance with the manufacturer's specification and to the satisfaction of the Contract Administrator.
- E14.3.6 Contractor is to protect subdrain from excessive weight during the duration of construction and to repair and make good any pipe collapsed prior to acceptance.
- E14.3.7 The Contractor shall be responsible for restoration of any surfaces damaged during the Work under this section.
- E14.3.8 The top of the trench is to be finished as shown on the Drawings.
- E14.3.9 The Multi-Flow drain system is to be connected to a solid pipe in accordance with manufacturer's recommendations and the pipe is then connected to the existing catch basin.
- E14.3.10 Connection to catch basin
  - (a) Connection to existing catch basin as per Section 3.15 of CW 2130.
- E14.3.11 Trenches are to be inspected by the Contract Administrator prior to backfilling.
- E14.4 Method of Measurement and Basis of Payment

The City of Winnipeg Specifications
Tender No. 146-2024 Page 14 of 27

Template Version: 2023 07 27 - Const noBidSecurity

### E14.4.1 Method of Measurement shall be as follows:

- (a) Sub-surface Drainage shall be measured on a linear metre basis for
  - (i) "Supply and install subsurface drainage system tied into catch basin" on Form B: Prices.
- (b) No measurement will be made for subsurface drainage within the play area as this item is incidental to the Work herein.
- (c) No separate measurement shall be made for connection to the catch basin as this item is incidental to the Work herein.

# E14.4.2 Basis of Payment shall be as follows:

- (a) Protective Surfacing will be paid for at the Contract Unit Prices. The amount to be paid for shall be the total number of units, as indicated on Form B: Prices. This price shall be full payment for supplying all labour, equipment and materials, and performing all operations herein described and all other items incidental to the Work and as accepted by the Contract Administrator.
- (b) No separate payment shall be made for connection to the catch basin as this item is incidental to the work herein.

### E15. SITE FURNISHINGS

- E15.1 General Description
- E15.1.1 This Specification shall cover the <u>supply and installation</u> of eleven (11) benches, one (1) accessible picnic tables, one (1) picnic table, and one (1) in-ground waste receptacle as per the Drawings.
- E15.1.2 The Work to be completed by the Contractor under this Specification shall include the supply of all materials, and the furnishings of all superintendence, overhead, labour, equipment, tools, and all other things necessary for and incidental to the satisfactory completion of all the Work shown on the Drawings and specified herein.
- E15.2 Materials
- E15.2.1 All materials supplied under this specification shall be of a type approved by the Contract Administrator, and subject to inspection and testing by the Contract Administrator.
- E15.2.2 All site furnishings as per the Drawings, or approved substitutions in accordance with B7.
- E15.3 Ordering
- E15.3.1 To order City of Winnipeg supplied site furnishings email: <a href="mailto:pwd-cps-orderdesk@winnipeg.ca">pwd-cps-orderdesk@winnipeg.ca</a>
- E15.4 City of Winnipeg Site Furnishings:
- E15.4.1 City of Winnipeg Site Furnishings are as follows:
  - (a) Tache Bench Composite with arms per SCD-121A x 11 Price \$1415.00 ea.
    - (i) Finish:
      - ♦ Composite Slats: Cedar Tone Finish
      - Metal: Galvanized
  - (b) Tache Style Wheelchair Metal Frame Picnic Table x 1 **Price \$1686.00 ea.** 
    - (i) Product Number: per SCD-122A
    - (ii) Finish:
      - ♦ Wood Finish: Latex Paint, Colour: Cedar
      - ♦ Metal: Galvanized
  - (c) Tache Style Metal Frame Picnic Table x 1 **Price \$1632.00 ea.** 
    - (i) Product Number: per SCD-122
    - (ii) Finish:

The City of Winnipeg Specifications
Tender No. 146-2024 Page 15 of 27

Template Version: 2023 07 27 - Const noBidSecurity

♦ Wood Finish: Latex Paint, Colour: Cedar

Metal: Galvanized

# E15.5 Bidder Supplied Site Furnishings

- (a) In-ground Waste Receptacle:
  - Alpha Products Inc. Alfa Maxi 30
  - (ii) Container Colour: sandstone
  - (iii) Lid Colour: green
  - (iv) Size: 762 mm (30") diameter x 2440 mm (96") height, with standard Maxi lid.
  - (v) Supplier: Equinox Industries tel: 1-800-665-7487. Concrete Foundations
- E15.5.1 Concrete foundation materials per E20.

# E15.6 Construction Methods

- E15.6.1 All Work is to be located and installed in accordance with the Drawings, and associated SCDs and/or Manufacturer's written instructions and specifications, using approved non-rusting, tamper resistant fasteners to ensure solid, durable, finished work suitable for the purpose intended. Fasteners and assembly hardware shall be incidental to the Work.
  - (a) All furnishings and fixtures to be installed plumb and true to correct elevations and location, as directed by the Contract Administrator. The Contractor shall confirm proposed locations of all site furnishings with Contract Administrator prior to installation.
  - (b) All furnishings and fixtures to be carefully handled so that no parts will be bent, broken or otherwise damaged. Hammering is prohibited.
  - (c) Damaged Site Furnishings will not be accepted.
  - (d) In-ground waste receptacle:
    - (i) Waste receptacle shall be installed as per the manufacturer's recommendation and the Drawings.
    - (ii) Set container on a 150 300 mm depth of pea gravel which has been levelled flat.
    - (iii) Container shall be placed in a hole which is 300 450 mm wider around the entire container.
    - (iv) Backfill pea gravel around the container in lifts which are placed equally around the entire container to prevent the container from shifting or deforming out of round shape.
    - (v) Ensure container remains plumb.
    - (vi) Install interior bags and lid. Install City supplied padlock to secure lid in place.

# E15.6.2 Concrete Foundations

- (a) Concrete foundation construction per E20.
- E15.7 Method of Measurement and Basis of Payment
- E15.7.1 Method of Measurement shall be as follows:
  - (a) <u>Supply and installation</u> of Site Furnishings will be paid for at the Contract Unit Price per unit for:
    - (i) "Supply and install Tache benches";
    - (ii) "Supply and install picnic table";
    - (iii) "Supply and install accessible picnic table"; and,
    - (iv) "Supply and Install In-ground waste receptacle" on Form B: Prices.
  - (b) Price shall be payment in full for supplying all materials and for performing all operations herein described and all other items incidental to the work included in this Specification.

The City of Winnipeg Specifications
Tender No. 146-2024 Page 16 of 27

Template Version: 2023 07 27 - Const noBidSecurity

# E15.7.2 Basis of Payment shall be as follows:

(a) Site Furnishings will be paid for at the Contract Unit Prices. The amount to be paid for shall be the total number of units, as indicated on Form B: Prices. The price shall be full payment for supplying all labour, equipment and materials, and performing all operations herein described and all other items incidental to the Work and as accepted by the Contract Administrator.

### E16. TOPSOIL AND SODDING

- E16.1 General Description
- E16.1.1 This Specification shall amend and supplement CW 3510, CW 3520, and CW 3540 and cover the supply and installation of sodding and seeding.
  - (a) The Contractor shall install mineral sod or seed and a minimum 75 mm compacted thickness of topsoil, as required.
- E16.1.2 The Work to be completed by the Contractor under this Specification shall include the supply of all materials, and the furnishings of all superintendence, overhead, labour, equipment, tools, and all other things necessary for and incidental to the satisfactory completion of all the Work shown on the Drawings and specified herein.
- E16.2 General Instructions
- E16.2.1 Quality Control
  - (a) Testing and Approval of Materials
    - Material testing may be required as per this Specification and as directed by the Contract Administrator.
- E16.3 Materials and Construction Methods
- E16.3.1 Topsoil shall be as per CW 3540.
  - (a) Sod shall be as per CW 3510.
  - (b) The Contractor shall install sod in locations as shown on Drawings to cover areas indicated on Drawings.
  - (c) Any areas damaged beyond the areas indicated on the Drawings shall be the responsibility of the Contractor to restore through use of topsoil and sod, unless otherwise approved by the Contract Administrator.
  - (d) Areas to be sodded are to be laid out on Site and approved by the Contract Administrator before commencing Work. Work outside the limit approved by the Contract Administrator will not be measured and will not be paid for under this section but considered incidental to the Work.
- E16.3.2 Where new sod will meet existing, employ a vertical shearing operation, such as using a sharp spade or edger, along the outside edges of the excavation to create a clean and definite line for the new sod to abut flush to.
- E16.3.3 Restoration shall be achieved using topsoil and sod unless otherwise directed by the Contract Administrator.
- E16.4 Maintenance Period
- E16.4.1 Thirty (30) day maintenance period on sod and seed will commence at Total Performance and acceptance.
- E16.4.2 Termination of maintenance period
  - (a) Termination of maintenance period for sod per Section 9.10 of CW 3510.
- E16.5 Method of Measurement and Basis of Payment
- E16.5.1 Method of Measurement shall be as follows:

The City of Winnipeg Specifications
Tender No. 146-2024 Page 17 of 27

Template Version: 2023 07 27 - Const noBidSecurity

- (a) Topsoil and sodding will be measured on a per square metre basis for:
  - (i) "Supply and install soil and sod" on Form B: Prices.
- E16.5.2 Basis of Payment shall be as follows:
  - (a) Topsoil and sodding will be paid for at the Contract Unit Prices. The amount to be paid for shall be the total number of units, as indicated on Form B: Prices. This price shall be full payment for supplying all labour, equipment and materials, and performing all operations herein described and all other items incidental to the Work and as accepted by the Contract Administrator.

### E17. SHADE STRUCTURE

- E17.1 General Description
- E17.1.1 This specification shall cover the supply and installation of a shade structure.
- E17.2 Shade Structure
- E17.2.1 The shade structure shall be:
  - (a) **Poligon Model 24' x 24' Square Hip Roof Shelter** by Poligon with no ornamentation. Complete with 4 columns & 7.5' height. **Model # SQR-24MR** 
    - (i) Frame and roof colour to be determined by Contract Administrator
    - (ii) Contact for Poligon Picnic Shelter:
      - ♦ Playgrounds R Us: Matthew Lacroix
      - ♦ 250 Transport Rd
      - ♦ Box 7, GRP 582, R.R. #5
      - ♦ Winnipeg. MB
      - (204) 632-7000
  - (b) Or approved substitute as per B7.
- E17.2.2 Shade Structure drawings must be supplied and stamped by a professional engineer licensed to practice in the Province of Manitoba.
- E17.3 Foundation
- E17.3.1 Shade Structure foundation is to be **CIP concrete piles <u>OR</u> screw piles with concrete pile cap**. This specification shall amend and supplement the City of Winnipeg Specification CW 3310.
  - (a) Structural drawings must be supplied and stamped by a professional engineer licensed to practice in the Province of Manitoba.
- E17.4 Permits
- E17.4.1 The Contractor shall be responsible to obtain **all necessary permits** for the supply and installation of the Shade Structure, including a Development Permit, Building Permit, and Occupancy Permit, from the City of Winnipeg. A copy of the Development and Building Permits shall be given to the Contract Administrator before Work on site occurs.
- E17.5 Shop Drawings
- E17.5.1 Contractor to provide shop drawings of both the structure and the foundation that are stamped by a professional engineer registered in the Province of Manitoba.
- E17.6 Installation
- E17.6.1 Structure and foundation to be installed in accordance with Shop Drawings and manufacturer's recommendation.
- E17.7 Method of Measurement and Basis of Payment

The City of Winnipeg Specifications
Tender No. 146-2024 Page 18 of 27

Template Version: 2023 07 27 - Const noBidSecurity

### E17.7.1 Method of Measurement shall be as follows:

- (a) Shade Structure will be measured on a lump sum basis for:
  - (i) "Supply and Install Shade Structure Including Piles and All Permits" on Form B: Prices.
- (b) No separate measurement shall be made for production of engineer stamped drawings as that is incidental to the Work herein.

# E17.7.2 Basis of Payment shall be as follows:

(a) Shade Structure will be paid for at the Contract Unit Prices. The amount to be paid for shall be the total number of units, as indicated on Form B: Prices. This price shall be full payment for supplying all labour, equipment and materials, and performing all operations herein described and all other items incidental to the Work and as accepted by the Contract Administrator.

# **PLAY EQUIPMENT**

# E18. PLAY EQUIPMENT

- E18.1 This specification shall cover the supply and installation of the Play Equipment as listed below and specified herein.
- E18.2 The Contractor shall furnish all labour, materials, equipment and services necessary to complete the Work in in accordance with E1 Applicable Specifications and Drawings
- E18.3 The Contractor shall obtain all approvals including permit if required.
- E18.4 Further to CW 1110 Shop drawing shall be submitted to the Contract Administrator for all the play equipment specified herein.

# E18.5 Play Area

- (a) Play equipment designed is predominantly for children ages 5-12. Play equipment shall provide the following play activities:
  - (i) Sensory & Imaginative Play, and;
  - (ii) Climbing/Gross Motor Skills, and;
  - (iii) Cooperation.
- (b) The play equipment shall be Landscape Structures PLAYBOOSTER DESIGN ID # 240223EE-01-4K, as per drawings and items listed below, or approved substitute as per B7.
- (c) The following components will make up the play equipment
  - (i) 1 x Landscape Structures Inc <u>152444A:</u> Grid Walk w/Guardrails
  - (ii) 1 x Landscape Structures Inc 146812A: Sky Rail Climber 64"Dk DB1
    - 1 x Landscape Structures Inc <u>152907A:</u> Deck Link w/Barriers Steel end panels 1 Step
    - 1 x Landscape Structures Inc <u>122916C:</u> Double Wave Climber 16"Dk Difference 48"Dk DB
  - (iii) 1 x Landscape Structures Inc 145624A: Vertical Ascent 48"Dk
  - (iv) 1 x Landscape Structures Inc 116249A: Vertical Ladder 32"Dk DB
  - (v) 1 x Landscape Structures Inc 152911A: Curved Transfer Module Left 32"Dk DB
  - (vi) 2 x Landscape Structures Inc 178710A: Hexagon Tenderdeck
  - (vii) 1 x Landscape Structures Inc 111228A: Square Tenderdeck
  - (viii) 1 x Landscape Structures Inc 115228A: Driver Panel Above Deck
  - (ix) 1 x Landscape Structures Inc <u>115235A</u>: House Panel Above Deck
  - (x) 2 x Landscape Structures Inc <u>116244A</u>: Pipe Barrier Above Deck
  - (xi) 1 x Landscape Structures Inc <u>115254A:</u> Storefront Panel

The City of Winnipeg Specifications
Tender No. 146-2024 Page 19 of 27

Template Version: 2023 07 27 - Const noBidSecurity

- (xii) 1 x Landscape Structures Inc 127440A: Trail Tracker Reach Panel Ground Level
- (xiii) 1 x Landscape Structures Inc 111275A: Handloop Assembly
- (xiv) 3 x Landscape Structures Inc 111404F: 108"Alum Post DB
- (xv) 1 x Landscape Structures Inc <u>111404E</u>: 116"Alum Post DB
- (xvi) 2 x Landscape Structures Inc <u>111404D</u>: 124"Alum Post DB
- (xvii) 6 x Landscape Structures Inc 111404B: 140"Alum Post DB
- (xviii) 6 x Landscape Structures Inc 1114003D: 158"Alum Post For Roof DB
- (xix) 1 x Landscape Structures Inc 130567A: Hex Shingle Roof
  - 1 x Landscape Structures Inc 130390A: Double Swoosh Slide 64"Dk DB1
- (xx) 2 x Landscape Structures Inc 148426B: Firepole Perm Handholds 64"Dk DB
- (xxi) 2 x Landscape Structures Inc 123337A: Single Slide 48"Dk DB
- (xxii) 1 x Landscape Structures Inc <u>247179A:</u> Curva Spinner DB Only
- (xxiii) 1 x Landscape Structures Inc 164074B: Single Bobble Rider DB
- (xxiv) 1 x Landscape Structures Inc <u>159881A:</u> 18x18 Shade Pyramid 8'Roof Height 60"Bury
- (xxv) 1 x Landscape Structures Inc 298208A: Symbol Communication Sign w/2 Posts DB
- (xxvi) 1 x Landscape Structures Inc <u>182503C:</u> Welcome Sign (LSI Provided) Ages 5-12 years Direct Bury
- (xxvii) 1 x Landscape Structures Inc 100041A: Curved Balance Beam DB
- E18.6 Contact for Play Equipment:

E18.7

Playgrounds-R-Us: Matthew Lacroix 250 Transport Rd. Box 7, Grp 582, RR #5 Winnipeg, MB.

- (204) 632-7000

  Colours for Play Equipment shall be determined by the Contract Administrator. If colour is a
- feature of posts, top caps and panels, the Contract Administrator shall have the ability to modify specified colours from the proposed design after Contract Award. If the price of the equipment in the Bid Submission is subject to the colours of the proposed design, this shall be indicated in the Bid Submission.
- E18.8 Components which are unacceptable are the following:
  - (a) Wooden structures;
  - (b) Tube (enclosed) slides and enclosed crawl tubes;
  - (c) Play panels with many small moving parts;
  - (d) Talk Tubes;
  - (e) Barrel rollers;
  - (f) Large number of plastic components; and
  - (g) Battery operated components.
- E18.9 Components which are generally not accepted but may be considered are the following:
  - (a) Cable rides;
  - (b) Sand diggers;
  - (c) Merry-go-rounds; and
  - (d) Tire Swings.
- E18.10 Play structures
- E18.10.1 Materials
  - (a) Posts / Caps

The City of Winnipeg Specifications
Tender No. 146-2024 Page 20 of 27

Template Version: 2023 07 27 - Const noBidSecurity

(i) All posts shall be a minimum 127 mm (5") O.D. round or 100 mm (4") square tubing for a post and deck structure.

- (ii) 89 mm (3.5") O.D. round or 73 mm (3") square tubing will be permitted in circumstances where a multi-deck structure has decks of varied heights which are all under 1220 mm (4'-0").
- (iii) All posts shall be fabricated from either aluminum 3 mm (0.125") 11 ga min. wall thickness or galvanized steel 3 mm (0.120") 11 ga min. wall thickness tubing. All fabrication cuts, drill holes and weld joints shall be sprayed with a corrosion resistant coating. The bottom end of the posts is to be sealed with a moisture barrier.
- (iv) In the case of a deckless structure, a minimum size of 60 mm (2 3/8") O.D. round posts fabricated out of steel or aluminum is acceptable.
- (v) Top caps shall be made of steel construction and shall be factory installed and secured in place with tamper proof, self-sealing rivets. Plastic top caps will be accepted if made of solid construction (hollow caps not accepted).
- (vi) If painted colour is a feature of posts and top caps, it shall be a baked-on polyester powder coating. The powder coating finish shall meet or exceed ASTM standards for hardness, adhesion, impact and salt spray resistance.

# (b) Decks and ramps

- (i) All decks and ramps shall be manufactured from vinyl-coated perforated steel or a steel core composite. Deck heights may vary to a maximum height of 1830 mm (6'-0").
- (ii) Must provide a secure connection to wall and pathway at beginning of elevated accessible entry ramp. See Drawings for reference.
- (iii) All ramps with slope 5% or greater shall provide a handrail as per the current City of Winnipeg Accessibility Design Standard: Section 1.1.5.
  - https://winnipeg.ca/finance/findata/matmgt/documents//2018/388-2018//388-2018 Appendix A.pdf

# (c) Clamping System

(i) All deck, rail and play component clamping systems shall be fabricated from zinc plated, galvanized steel, stainless steel or aluminum. Tamper proof, corrosion resistant fasteners shall be used to retain clamping systems.

# (d) Handrails, Safety Rails and Handloops (if applicable)

- (i) All handrails, safety rails and handloops shall be fabricated using a minimum of 24 mm (15/16") O.D. with 3 mm (0.120") 11 ga min. wall thickness steel tubing. After all fabrication activities have occurred including end cuts, drill holes, bends and weld joints, all components shall be hot dipped galvanized.
- (ii) Smooth all cut edges and weld joints prior to hot dip galvanizing and ensure that all tubing is free from burrs, cracks, defects and other imperfections.
- (iii) A section of handrail must be installed that extends from the edge of the elevated ramp entry at the top of the retaining wall to the first play structure post as per the drawings.

#### (e) Hardware

- All fasteners shall be socketed and tamper proof in design and requiring special tools.
- (ii) Hardware shall either be carbon steel plated with zinc/nickel and iridescent chromate finish or stainless steel.
- (iii) All necessary hardware and tools shall be provided.

### (f) Poly Components

- (i) Poly components such as slides and hoods shall be fabricated from U.V. stabilized rotationally moulded linear low-density polyethylene.
- (ii) Poly components such as play panels shall be fabricated from compression moulded solid colour, U.V. stabilized, high-density polyethylene.

The City of Winnipeg Specifications
Tender No. 146-2024 Page 21 of 27

Template Version: 2023 07 27 - Const noBidSecurity

- (g) Slides (if applicable)
  - A minimum of one stainless steel slide is required, north or east orientation is preferred.
- (h) Kick plates and hand loops
  - (i) Each play structure shall have kick plates and hand loops as required to meet the current version of the Canadian Standards Association (CSA) Standards.
- (i) Climbing Net Structures
  - (i) Climbing Net Structures must be comprised of separate rope segments versus long stretches of rope clamped with connectors, for ease of maintenance.
- (j) Cast-In-Place (CIP) Concrete Foundations
  - (i) CIP Concrete Foundations shall be as per E20.

### E18.10.2 Construction Methods

- (a) Play equipment shall be installed as per Manufacturer's written specifications, in accordance with the most recent version of Canadian Standards Association Standards, and as per the Drawings.
- (b) All posts and other vertical items shall be plumb and true to vertical, if so designed.
- (c) All decks shall be level, if so designed.
- (d) Functionally linked items such as stepping pods, logs, balance beams, etc should be placed at minimum 150mm to a maximum of 300mm for Children less than 5 years of age and between 300mm to a maximum of 450mm for children 5 12 years old.
- (e) CIP Concrete Foundations construction shall be per E20.
- (f) One play equipment installer (minimum) must be a valid certified Canadian Certified Playground Inspector and on site for the duration of assembly and installation of play equipment.

### E18.11 Independent Component Play Equipment

# E18.11.1 Materials

- (a) All materials shall be structurally sound and suitable for safe play. Durability shall be ensured on all parts and materials.
- (b) There shall be a minimum (or no) amount of hollow plastic components. Solid plastic is acceptable.
- (c) There shall be a minimum number of solid elements which limit visibility through the Site.
- (d) Decks and ramps
  - (i) All decks and ramps shall be manufactured from vinyl-coated perforated steel or a steel core composite. Deck heights may vary to a maximum height of 1830 mm (6'-0").
  - (ii) Must provide a secure connection to wall and pathway at beginning of elevated accessible entry ramp. See Drawings for reference.
  - (iii) All ramps with slope 5% or greater shall provide a handrail as per the current City of Winnipeg Accessibility Design Standard: Section 1.1.5.
    - https://winnipeg.ca/finance/findata/matmgt/documents//2018/388-2018//388-2018\_Appendix\_A.pdf

### (e) Hardware

- All fasteners shall be socketed and tamper proof in design and requiring special tools.
- (ii) Hardware shall either be carbon steel plated with zinc/nickel and iridescent chromate finish or stainless steel.
- (iii) All necessary hardware and tools shall be provided.
- (f) Finishes

The City of Winnipeg Specifications
Tender No. 146-2024 Page 22 of 27

Template Version: 2023 07 27 - Const noBidSecurity

(i) Finishes shall meet or exceed ASTM standards for hardness, adhesion, impact and salt spray resistance. All fabrication cuts, drill holes and weld joints shall be sprayed with a corrosion resistant coating.

# (g) Slides

- (i) If an independent slide is proposed, stainless steel is preferred. If other slides are proposed on the Site one may be plastic. North or east orientation preferred. If independent slide over 1220 mm (4'-0") high is proposed, support posts shall be minimum 127 mm (5") O.D.
- (ii) Tube (enclosed) slides and plastic spiral slides will not be accepted.
- (h) CIP Concrete Foundations
  - (i) Shall be as per E20.

### E18.11.2 Construction Methods

- (a) Independent component play equipment shall be installed as per Manufacturer's written specifications, in accordance with the most recent version of Canadian Standards Association Standards, and as per the Drawings.
- (b) All posts and other vertical items shall be plumb and true to vertical, if so designed.
- (c) All decks shall be level, if so designed.
- (d) Independent items that are functionally linked such as stepping pods, logs, balance beams, etc should be placed at minimum 150mm to a maximum of 300mm for Children less than 5 years of age and between 300mm to a maximum of 450mm for children 5- 12 yrs old.
- (e) CIP Concrete Foundation construction shall be per E20.
- (f) One independent component play equipment installer (minimum) must be a valid certified Canadian Certified Playground Inspector and on site for the duration of assembly and installation of independent components play equipment.
- E18.12 Method of Measurement and Basis of Payment
- E18.12.1 Method of Measurement shall be as follows:
  - (a) Play Equipment shall be measured on a lump sum basis for:
    - (i) "Supply and Install 5-12 play equipment" on Form B: Prices.
  - (b) No separate measurement will be made for CIP Concrete Foundations as this item is incidental to the Work herein.
- E18.12.2 Basis of Payment shall be as follows:
  - (a) Play Equipment will be paid for at the Contract Unit Prices. The amount to be paid for shall be the total number of units, as indicated on Form B: Prices. This price shall be full payment for supplying all labour, equipment and materials, and performing all operations herein described and all other items incidental to the Work and as accepted by the Contract Administrator.
  - (b) No additional payment will be made for CIP Concrete Foundations as this item is incidental to the Work herein.

### E19. SWING SETS

- E19.1 General Description
- E19.1.1 The Contractor shall furnish all labour, materials, equipment and services necessary to complete the Work according to the specifications.
- E19.1.2 This specification shall cover the supply and installation of minimum one (1) complete swing standard as specified herein:

The City of Winnipeg Specifications
Tender No. 146-2024 Page 23 of 27

Template Version: 2023 07 27 - Const noBidSecurity

(a) Three Leg Heavy Duty Swing Frame, 2.4 m (8ft.) high, 2-Bay, complete with four (4) slash-proof rubber belt seat, heavy-duty chain, swing hangers and hammer locks/bolt links.

#### OF

(b) Single post, 125mm (5") O.D. posts, 2-Bay, complete with four (4) slash-proof rubber belt seat, heavy-duty chain, swing hangers and hammer locks/bolt links.

### E19.2 Materials

# E19.2.1 Topbeam

- (a) Topbeams shall be fabricated from min. 89mm (3.5") O.D. one piece welded construction of galvanized steel tubing and 8 gauge galvanized steel plate or 6005-T5 aluminium alloy tube. All fabrication cuts, drill holes and weld joints shall be sprayed with a corrosion resistant coating.
  - (i) Topbeams for Single post swings shall comprised of tee clamps and 125mm (5") O.D. extruded aluminium alloy or steel tube with a .125" wall.

# E19.2.2 Legs

- (a) Three legs swings shall be fabricated from 60mm (2 3/8") O.D. 10 gauge, RS40 galvanized steel pipe. All fabrication cuts, drill holes and weld joints shall be sprayed with a corrosion resistant coating. The bottom end of the posts is to be sealed with a moisture barrier.
- (b) Single post swing legs shall be fabricated from min 5" O.D. one piece welded construction of HPRO EW steel tubing finished with cadmium yellow chromate plating. All fabrication cuts, drill holes and weld joints shall be sprayed with a corrosion resistant coating. The bottom end of the posts is to be sealed with a moisture barrier.

### E19.2.3 Threadlock

- (a) Product: Loctite Red High Strength requiring heat for removal
  - (i) Manufacturer: Henkel
  - (ii) Website: https://www.henkel-adhesives.com
  - (iii) Or approved substitute.

### E19.2.4 Yoke Clamps

(a) All yoke clamps shall be either one piece construction and fabricated from 8 gauge, RS40 galvanized steel pipe or two piece, compression clamping cast aluminium or galvanized metal complete with tamper-proof hardware.

### E19.2.5 Swing Hangers

(a) All swing hangers shall be fabricated from galvanized malleable iron and have oil impregnated bearings pressed in.

# E19.2.6 Swing Chain

(a) All swing chain shall be 4/0 straight link, galvanized steel.

# E19.2.7 Enclosed Infant (Bucket) Seats

(a) All enclosed infant seats shall be moulded of U.V. stabilized, high quality, rubber with a tempered stainless steel reinforcement plate insert moulded inside, rendering the seats slashproof. Infant seats shall be fully enclosed to prevent slipping out and provide extra lower back support.

### E19.2.8 Belt Seats

(a) All belt seats shall be moulded of U.V. stabilized, high quality, rubber with a tempered stainless steel reinforcement plate insert moulded inside, rendering the seats slash-proof. The perimeter shall be moulded to form a blunt, impact absorbing edge.

# E19.2.9 Hardware

The City of Winnipeg Specifications
Tender No. 146-2024 Page 24 of 27

Template Version: 2023 07 27 - Const noBidSecurity

(a) All fasteners shall be tamper proof in design, requiring special tools. The fasteners shall be either carbon steel plated with zinc/nickel and iridescent chromate finish or stainless steel.

### E19.2.10 Concrete Foundations

- (a) Post shall be installed into a concrete footing the composition of which is detailed in E23.
  - i) Concrete footings for single post swings shall be as per E20.4.3

# E19.2.11 Unacceptable swings are as follows:

- (a) Dish swings
- (b) Tire swings

### E19.3 Installation

- (a) Installation shall be in accordance with Manufacturers specifications and in accordance with the most recent Canadian Standards Association Standards within the designated play equipment area on the Drawings.
- (b) Contractor shall use threadlock, per E19.2.3, on all hardware for swing components assembled on site by Contractor, as per Manufacturer's written specifications and instructions
- (c) Top rail is to be level and posts securing anchored in concrete.
- (d) Swing seats shall not be installed until the protective surfacing, has been installed

# E19.4 Method of Measurement and Basis of Payment

- (a) Method of Measurement shall be as follows:
- (b) Swing set will be measured on a per unit basis for:
  - (i) "Supply and Install 8' Tall, 2 bay, Swing Set";

# E19.4.2 Basis of Payment shall be as follows:

(a) Swing set will be paid for at the Contract Unit Prices. The amount to be paid for shall be the total number of units, as indicated on Form B: Prices. This price shall be full payment for supplying all labour, equipment and materials, and performing all operations herein described and all other items incidental to the Work and as accepted by the Contract Administrator.

# E20. CAST-IN-PLACE CONCRETE FOUNDATIONS

# E20.1 General Description

- E20.1.1 This Specification shall supplement CW 2160 and cover the supply and installation of cast-in-place concrete foundations for Site Furnishings, Play Equipment, and Swing Sets.
  - (a) All underground cast-in-place concrete foundations for Site Furnishings, Play Equipment, and Swing Set posts, bases and anchors are to be set in concrete footings or piles per CW 2160 to ensure stability and prevent frost heaving.
- E20.1.2 The Work to be completed by the Contractor under this Specification shall include the supply of all materials, and the furnishings of all superintendence, overhead, labour, equipment, tools, and all other things necessary for and incidental to the satisfactory completion of all the Work shown on the Drawings and specified herein.

# E20.2 General Instructions

# E20.2.1 Quality Control

- (a) Testing and Approval of Materials
  - Material testing may be required as per this Specification and as directed by the Contract Administrator.

The City of Winnipeg Specifications
Tender No. 146-2024 Page 25 of 27

Template Version: 2023 07 27 - Const noBidSecurity

### E20.3 Materials

# E20.3.1 All materials as per CW 2160.

- (a) Concrete
  - (i) Maximum Size of aggregate: 20 mm, nominal;
  - (ii) Compression Strength: 28 day compressive strength of 30 Mpa;
  - (iii) Slump/Flow: 80 +/- 20mm;
  - (iv) Sulphate resistant, Type 50 Cement; and
  - (v) Maximum water/cement ratio: 0.49.
  - (vi) Air Content: 4-7%

# E20.4 Construction Methods

# E20.4.1 Construction Methods as per CW 2160.

- (a) If concrete testing is required, do not place concrete until material testing is performed and reviewed by Contract Administrator.
- (b) All concrete foundations for site furnishings as per the Drawings.

# E20.4.2 Playground Equipment Footing

- (a) Holes for concrete footing for play equipment and swings must be inspected and approved by the Contract Administrator prior to installation of concrete. Contractor to provide min. two (2) Business Days' notice for inspection.
- (b) All concrete footings for play equipment and swing sets shall be in accordance with Manufacturer's specifications and be minimum 24" deep. Bidders are to include drawings showing Manufacturer's Footing Specification in their Bid Submission.
- (c) All posts and supports shall be centred in the concrete footing such that there is a complete collar of concrete around each post and support. Where posts are not perfectly centred there should be a minimum of 50mm (2") concrete at any point around the post.
- (d) The full depth of concrete footing must be below subgrade. If required for specified embedment of post in the footing, footing shall extend in sonotube through the granular drainage layer. Footing must not extend into the wood fibre safety surface.

# E20.4.3 Single Post Swing Footing

- (a) Holes for concrete footing for single post swings must be inspected and approved by the Contract Administrator prior to installation of concrete. Contractor to provide min. two (2) Business Days' notice for inspection.
- (b) Concrete footing for single post swings shall be in accordance with Manufacturer's specifications and be **minimum 40" deep and 24" wide**. Bidders are to include drawings showing Manufacturer's Footing Specification in their Bid Submission.
- (c) All posts and supports shall be centred in the concrete footing such that there is a complete collar of concrete around each post and support. Where posts are not perfectly centred there should be a minimum of 50mm (2") concrete at any point around the post.
- (d) The full depth of concrete footing must be below subgrade. If required for specified embedment of post in the footing, footing shall extend in sonotube through the granular drainage layer. Footing must not extend into the wood fibre safety surface.

# E20.4.4 Cold Weather Concreting

- (a) Cold weather concreting shall be as per Section 3.9 of CW 2160 and CSA A23.1.
  - (i) All material and equipment needed for adequate protection and curing shall be on hand and ready to use before concrete placement is started.
  - (ii) Before concrete is placed all ice, snow, and frost shall be removed from formwork and all surfaces against which concrete will be placed.

The City of Winnipeg Specifications
Tender No. 146-2024 Page 26 of 27

Template Version: 2023 07 27 - Const noBidSecurity

- Temperatures of adjacent surfaces shall be raised to and maintained at 5° C minimum, prior to and during concreting.
- Calcium chloride or other de-icing salts shall not be used as a de-icing agent in the forms.
- (iii) Heating equipment and enclosures shall be per CW 2160 and CSA A23.1.
- E20.5 Method of Measurement and Basis of Payment
- E20.5.1 Method of Measurement shall be as follows:
  - (a) No separate measurement for Cast-in-Place Concrete Foundations shall be made for Site Furnishings or Swing Sets, as Foundations are incidental to the Works therein.
  - (b) If required by the Contract Administrator, no measurement will be made for material testing as this item is incidental to the Work herein.
- E20.5.2 Basis of Payment shall be as follows:
  - (a) No additional payment for Cast-in-Place Concrete Foundations shall be made for Site Furnishings or Swing Sets, as Foundations are incidental to the Works therein.
  - (b) If required by the Contract Administrator, no payment will be made for material testing as this item is incidental to the Work herein.

### **E21. MAINTENANCE KITS**

- E21.1 General Description
- E21.1.1 This specification shall cover the supply of maintenance kits for Play Equipment.
- E21.1.2 The Work to be completed by the Contractor under this Specification shall include the supply of all materials, and the furnishings of all superintendence, overhead, labour, equipment, tools, and all other things necessary for and incidental to the satisfactory completion of all the Work shown on the Drawings and specified herein.
- E21.2 Materials
- E21.2.1 All play equipment and swings shall include the supply of maintenance kits.
- E21.2.2 Maintenance kits shall include maintenance manuals, complete manufacturer's parts lists, touch-up paint, PVC repair paint, 10% extra of each bolt, washer and any other hardware utilized on the play equipment, and all special tools necessary for assembly and maintenance.
- E21.3 Delivery of maintenance kits
- E21.3.1 Maintenance kits shall be delivered two (2) Working Days prior to achieving Total Performance.
  - (a) Deliver to:

Attn: Marc Laurin and/or Derrick Downey

Parks and Open Space Division, Public Works

960 Thomas Avenue, Winnipeg, MB

Ph: Marc Laurin: 204-479-5489

Ph: Derrick Downey: 204-391-2860

- (b) Contractor to forward Contract Administrator a copy of the Transmittal prior to achieving Total Performance.
- E21.4 Method of Measurement and Basis of Payment
- E21.4.1 Method of Measurement shall be as follows:
  - (a) No separate measurement for maintenance kits or delivery shall be made for Play Equipment or Swing Sets as maintenance kits is incidental to the Works herein.

The City of Winnipeg Specifications Tender No. 146-2024 Specifications Page 27 of 27

Template Version: 2023 07 27 - Const noBidSecurity

# E21.4.2 Basis of Payment shall be as follows:

(a) No additional payment for maintenance kits or delivery shall be made for Swing Sets as maintenance kits is incidental to the Works herein