

CW 3010 – CLEARING AND GRUBBING

TABLE OF CONTENTS

1.	GENERAL CONDITIONS.....	1
3.	DESCRIPTION.....	1
9.	CONSTRUCTION METHODS	1
12.	METHOD OF MEASUREMENT.....	1
13.	BASIS OF PAYMENT	2

CW 3010 - CLEARING AND GRUBBING**1. GENERAL CONDITIONS**

The General Conditions and Standard Provisions attached hereto shall apply to and be a part of this Specification.

3. DESCRIPTION

This Specification shall cover the removal from the site of trees, stumps, roots, logs, brush, rubbish and all other surface litter within the full limits of the works, and the disposal of same in a manner hereinafter specified.

The work to be done by the Contractor under this Specification shall include the furnishing of all superintendence, overhead, labour, materials, equipment, tools, supplies and all other things necessary for and incidental to the satisfactory performance and completion of all work as hereinafter specified.

9. CONSTRUCTION METHODS

Before commencement of any work, the Contractor shall consult with the Contract Administrator as to which trees and/or shrubs shall remain on site and be protected, if any. Those so designated shall be protected against damage from all construction activity.

The Contractor shall restrict his activities strictly to within the limits of the works, unless receiving prior written approval from the Contract Administrator. Trees are to be felled so as to land within the limits of the works. The Contractor shall take all precautions to prevent damage to traffic, structures, pole lines, adjacent property and to trees and shrubs designated to be saved, and he shall be liable for any damages occurring in the performance of this work.

The Contractor shall cut down all trees and shrubs, except those designated by the Contract Administrator to be saved, and grub out all stumps and roots. The Contractor shall load and haul all trees, stumps, roots, logs, brush, rubbish and all other surface litter from the site and dispose of these materials at dumps located by the Contractor and approved by the Contract Administrator. Any materials dropped or spilled on any streets during the hauling operations shall be promptly cleaned up by and at the expense of the Contractor, to the satisfaction of the Contract Administrator.

The Contractor shall ensure that upon completion of the clearing and grubbing operations the site shall be left free of any hazardous depressions and in a neat condition.

12. METHOD OF MEASUREMENT

Clearing and grubbing will be measured on an area basis. The area to be paid for shall be the total number of hectares within the limits of the works that are cleared and grubbed in accordance with this Specification acceptable to the Contract Administrator, as computed from measurements made by the Contract Administrator.

13. BASIS OF PAYMENT

Clearing and grubbing will be paid for at the Contract Unit Price per hectare for "Clearing and Grubbing", measured as specified herein, which price shall be payment in full for performing all operations herein described and all other items incidental to the work included in this Specification.